

A
COMPENDIOUS COURSE
OF
Practical Mathematicks.
Particularly Adapted to the
Use of the GENTLEMEN
OF THE
ARMY and NAVY.

IN THREE VOLUMES.

For the most Part translated from the TRACTS publish'd
in *French* by P. HOSTE, Professor of MATHEMATICKS.
in the *Royal Academy of Thoulon.*

By *WILLIAM WEBSTER.*

VOL. III. containing,

- | | |
|-----------------------|--------------------|
| I. Use of the GLOBES. | III. The THEORY of |
| II. NAVIGATION. | Working a Ship. |
-

To which are added,

- | |
|---|
| I. An ALPHABETICAL EXPLANATION of such Sea-Terms and
Phrases as occur in the WORK. |
| II. An APPENDIX, containing the DESCRIPTION and Use of
a Complete SET or CASE of Pocket-Instruments. |
-

L O N D O N :

Printed for A. BETTESWORTH in *Pater-Noster-Row*,
and C. KING in *Westminster-Hall.* M.DCC.XXX.

CONFIDENTIAL

G E O R G E

John Wilson, Esq.

Well Road, London, E.C.

My Dear Sir,

I have the pleasure to acknowledge the receipt of your letter of the 14th inst.

in relation to the matter of the

of the Treasury, and to be assured that

will be forwarded to the proper authorities

for their consideration.

I am, Sir, very respectfully,

Yours, Sir, very respectfully,

the Goodbye, Sir, and I hope

will be well, Sir, and I hope

to hear from you again.



G

I

Fi



Sir
of
me
na
Tr
ted
his
ner
the
ship
De
reg
ten



To the Right Honourable

G E O R G E,

Lord Viscount TORRINGTON,

First Lord COMMISSIONER of the
Admiralty, &c.

MY LORD,



AS a Treatise on Numbers could nowhere have been so properly addressed as to that eminent Master of Figures the Rt. Honourable Sir Robert Walpole, First Lord Commissioner of the Treasury, who has done my *Arithmetick in Epitome* the Honour of his Patronage ; nor a *Collection of Mathematical Tracts on the Principles of Military Architecture*, &c. laid so rightly as at the Feet of his Grace the Duke of Argyle, Master-General of the Ordnance, who has likewise had the Goodness to accept it : So Your Lordship will, I hope, excuse my Ambition in Dedicating this Part of the Work, which regards the Marine, and contains an *Attempt towards a Rationale on the Practical*
Part

DEDICATION.
*Part of Navigation, to Your Lordship, who,
with such deserved Honour, presides in the
Naval Affairs of Great-Britain.*

It is a peculiar Happiness to a Writer when his Work so naturally points out its Patron; and the Author of these Tracts, more fortunate in that Respect in his Translation, than in his Original, will (if living) rejoice to see his Performance honour'd with the Eminent Names of the Duke of *Argyle* and Your Lordship.

I have no Plea, as a Stranger, for this Address, but the Aptness of the Subject, which I hope will excuse, both to Your Lordship, and the World, this Presumption of,


MY LORD,

Your Lordship's

Most Obedient, and

Most Humble Servant,

William Webster.



THE CONTENTS.

TRACT the First, The Use of the GLOBES.

S uppositions and Definitions	Page 1
Of the Armillary Sphere	4
Of the Cœlestial Globe	8
Of the Terrestrial Globe	9
Of the Sphere in Plano	14

TRACT the Second.

NAVIGATION.

PART I.

Of Instruments and their Uses	20
Of the Fore-Staff	22
Of the English Quadrant	25
Of Errors in taking Heights	25
Of the Compasses	27
Of the Variation of the Compass	29
Of Charts	31
Of Tables	34

PART II.

Of Sailing by the Sines.

Of a Ship's Course	38
Of the Loxodromick Triang's	40
	Of

The CONTENTS.

Of a Ship's Reckoning	Page 41
Of the Difference of Latitude	43
Of the Longitude	45
Of the Angles of the Loxodromick Triangle	46
Of resolving the Loxodromick Triangle	47

PART III.

Of sailing without regarding the Sines.

Of Sailing by Tables	53
———— by the Quadrant	56
———— by Charts	61
Of Tides	64
Of the Situation of Ports	65
Of the Hour of the Moon	65
Of the Moon's Age	66
Of the Time of High Water	68
Of Currents	68

TRACT the Third,
The Working of a Ship.

Advertisment thereon	71
Definitions	73
Suppositions	75

PART I.

Of the Instruments made use of to put a
Ship in Motion.

Of the Hull or Body of a Ship	79
Of the Rudder	85
Of the Sails in general	87
Of the Head Sails	91
Of the Main Sail	96
Of the Mizzen	98

PART

The CONTENTS.

PART II.

To turn a Ship any Way.

Of rendering a Ship ready to turn	Page 100
To make a Ship fall off	101
To bring a Ship to the Wind	103
To tack with the Wind before the Beam	104
To change the Board with the Wind abaft the Beam	107
To prevent the Accident called Building a Chapel	108
To lye to under the Top-Sails	110
To lye to under the Courses	112
To govern a Ship with the Yards	114

PART III.

Of failing from one Place to another at a Distance.

To come to sail	116
Of gaining to Windward	117
To find the most advantageous Situation of a Sail for a Course given, when a Ship makes no Lee-way	122
Of the Alteration made by Lee-way	123
To find the proper Rhumb a Ship should keep, in sailing from one fix'd Place to another	130
To find the proper Course for chasing a Vessel to Leeward	131
To find the proper Course for a Ship to cut, or cross the Way of another to Windward of her	133
To find the Point where a Ship ought to tack, to cut or cross another to Windward of her	133
Remarks upon giving Chace	136
Of boarding a Ship	137
Of running into Land	140
To bring a Ship to an Anchor	141
To moor	142
An Alphabetical Explanation of Terms.	145

The

The CONTENTS of the APPENDIX,
Containing the Description and Use of a
Case of Instruments.

General Description	179
Of the Compasses	180
Of the Drawing Pen and Protracting Pin	181
Of the Parallel Ruler	182
Of the Protractor	182
Of Scales of equal Parts, simply divided	184
————— diagonally divided	185
The Construction and Use of the Plain Scale	187
Of the Sector	194
Of the Foundation and General Use of the Sector	197
Of the particular Uses of the Lines of Lines	200
Of the Lines of Polygons	208
Of the Lines of Artificial Numbers, Sines, and Tangents	209
Of working Proportions on the Sectoral and Artificial Lines	214

N. B. The reader is desired to excuse an inadvertency in page 16, where the calculation is by new style, as the difference stood before the year 1700. And in the same page, line 15, to supply the word *days*, by reading, *as many degrees as there are days*.



THE USE of the GLOBES.



Sphere or Globe is a round solid body, upon the surface whereof are drawn certain circles and figures, representing the movement and disposition of the heavenly bodies; or the situation and extent of the Earth and Water.

There are three sorts of Spheres.

1. The Cœlestial, for the Stars, &c.
2. The Terrestrial, for the Earth and Seas.
3. The Armillary, which has respect both to the one and the other.

N.B. To make what follows the more intelligible, the Reader should have an Armillary Sphere before him.

Suppositions and Definitions.

1. The Heavens appear like the concave surface of a globe, whose centre is the middle of the earth;

earth ; and which continually turning round upon two of its points diametrically opposite to each other, carries about with it the stars and planets, which seem fix'd therein ; making them every day describe circles, which have the said point for their poles.

2. The two points upon which the heavens thus turn, are called *The Poles of the World*. That which is visible to us in *Europe*, is the north, or artick pole ; the other the south, or antartick : The streight line passing from the one pole to the other, is called, *The Axis of the World*. And the circles which the stars every day seem to describe, are nam'd, *The Parallels* of each star. Every fifteen degrees of these circles, make an hour of time.

3. Some of these heavenly bodies sensibly change their places in the heavens, and those we call *Planets*. And the circle which these stars describe by their particular movement in thus changing their places, is called, *The Ecliptick*. Those stars which do not sensibly change their places in the heavens, are called *Fix'd Stars*. For the better recollection of the several fix'd stars, they are reduc'd to certain figures, called, *Constellations* ; the 12 principal of which, are those which give names to the 12 divisions of the ecliptick, and are call'd, *The 12 Signs of the Zodiack*.

4. A Body is said to descend, when it approaches towards the center of the earth ; but when it recedes from it, and becomes more distant, it is said to ascend. A line is said to be plumb or

right to the earth, when being prplong'd it would pass thro' its centre as A C. *Fig. 1.* A line is said to be horizontal, when it is perpendicular to such a plumb or right line as D E ; and when a line makes an acute angle with a plumb line as C F, it is then said to be inclined.

5. In whatever place of the earth we are, we may sensibly perceive one half of the heavens ; and may easily imagine a circle dividing that part which we see, from the other which we do not see ; and such circle is call'd, *The Horizon* ; the middle point of the visible part of the heavens (which is directly over our heads) is call'd, *The Zenith* ; and the middle point of the invisible part (which is directly under our feet) is call'd, *The Nadir* : And as these two Points answer in every place to a line plumb or perpendicular to the earth, there are therefore as many different zeniths and nadirs, and consequently horizons as there are different points upon the earth. For example, if I stand at the point A, my zenith will be the point in the heavens *Fig. 2.* C, my nadir F, and my horizon the circle B D. But if I am at the point K, my horizon will be H I, my zenith G, and my nadir L.

6. We call it *Day* when the sun is in that part of the heavens which we see ; but when it is in the other part invisible to us, we call it *Night*. In the same manner we call that part of the parallel which is described by any star in the visible part of the heavens, its *diurnal Arch* ; the remaining part of the parallel is call'd its *nocturnal Arch*. That little glimmering of light which ap-

pears before or after day, we call the *Twilight* or *Crepuscle*.

P R O P. I.

Of the Armillary Sphere.

1. An Armillary Sphere is composed of ten open circles, with a little ball or button in the middle, answering to the center of the earth, supported by a small wire, representing the axis of the world.

2. There are 6 great circles, and four small ones: the great ones are, the Horizon, the Meridian, the Equator, the Zodiack, and the two Colures.

H O R I Z O N.

The Horizon is a great circle, dividing that part of the heavens visible to us, from the other part which we do not see.

But there being as many different horizons as there are different places, the horizon of the sphere is therefore made moveable.* This circle is divided into 32 equal parts, answerable to the 32 points of the mariner's compass, the 4 chief of which are the north, or that point of the horizon answering to the north pole; the south, answering to the south pole; the east, or that point of the horizon where the sun rises, when the days and nights are equal; and the west, which is that point where the sun sets when the

* Or rather, it should be said, the sphere is contriv'd to turn within this circle. The same thing is to be understood in the next paragraph, with regard to the meridian.

days and nights are equal. The middle points betwixt any two of these principal ones, take their names from those two they are between, as the northeast is the middle point between the north and east. The same is also to be understood of the other divisions, for we call that point the north-nor-east which is between the north and the northeast, &c. And thus names are given to the 32 points of the horizon. The horizon is again divided into 360 degrees, which last division is also applied to the three following circles of the sphere. The horizon serves to shew the rising and setting of the heavenly bodies, the length of the days and nights, and the course of the winds, or points of the compass.

M E R I D I A N.

The Meridian is a great circle passing thro' the two poles of the world, and through the zenith and nadir points of *Fig. 5.* each country. It is made moveable in the sphere, to the end it may represent the different meridians of the several countries. This circle chiefly serves, 1. To divide the diurnal and nocturnal arches into two equal parts, so that when the sun is in the meridian, it is then mid-day or midnight. 2. To mark the meridian height of the stars, which is an arch of the said circle, comprehended between the star and the horizon. 3. To shew the latitude of every country, which is that arch of the meridian comprehended between the horizon of the country and the pole; or that arch of the said circle included betwixt the zenith of the place and the equator; of which we now proceed to speak.

B 3

EQUA-

EQUATOR.

The Equator is a great circle equally distant from the two poles of the world. It

Fig. 6. has divers uses, 1. When the sun is in the equator, the days and nights are equal every where, except under the poles. 2. The equator is the boundary from whence we begin to measure the latitude of places, and the declination of the heavenly bodies : For as the latitude of a country is that arch of the meridian contain'd between the equator and the zenith of the place ; so the declination of a star is also that arch of the meridian included between the equator and the star. If the zenith of a country is between the equator and the north pole, its latitude is north ; but if between the south pole and the equator, its latitude is south ; the same is to be understood of declination. 3. On the equator is reckon'd the longitude of places, and the right ascension of the heavenly bodies : For the longitude of a country is the arch of the equator between the meridian of such place, and the place through which the first meridian is accounted to pass (which with us is *London*, or the pike of *Tenerif*, and with the *French* the *isle de Fer*) and the right ascension of a star is also the arch of the equator, between the first degree of *Aries*, and the meridian passing through the said star.

Note, Both longitude and right ascension are reckoned from west to east 4. The circles daily described by the heavenly bodies, being apparently parallel to the equator, time is therefore measured by the degrees of the equator, 15 of which are

are equal to an hour, and consequently the whole 360 to 24 hours.

Z O D I A C K.

The Zodiack is a broad Circle 16 degrees wide, through the middle of which runs the ecliptick of the sun, or that great circle which the sun describes yearly, as it changes its place in the heavens; by its particular movement. The ecliptick cuts the equator in two points, called the *Equinoxes*, making therewith an angle of $23^{\circ} 29'$ which is the greatest declination of the sun. The ecliptick and zodiack are divided into 12 equal parts, call'd *Signs*; beginning from the first equinoctial point, or first degree of *Aries*, and proceeding from west to east. They have the names and figures following, viz. *Aries* ♈, *Taurus* ♉, *Gemini* ♊, *Cancer* ♋, *Leo* ♌, *Virgo* ♍, *Libra* ♎, *Scorpio* ♏, *Sagittarius* ♐, *Capricornus* ♑, *Aquarius* ♒, *Pisces* ♓. The particular day of each month upon which the sun enters each sign, is also added: lastly, each sign is divided into 30 degrees, and the sun running through very near a degree every day from west to east, is a little more than 365 days in passing through the whole ecliptick.

C O L U R E S.

The Colures are two particular meridians, one of which passing through the equinoctial points of the ecliptick, is call'd the *Equinoctial Colure*: The other, passing through the two points of the ecliptick, which are farthest distant from the equator, is call'd the *Solstitial Colure*. They

cut the equator into 4 equal parts, which make the 4 seasons, *viz.* 1. The spring, or that part of the ecliptick between the first point of Aries and the last of Gemini. 2. The summer, or that part of the ecliptick between the last point of Gemini and the first of Libra. 3. The autumn, or that part of the ecliptick between the first point of Libra and the last of Sagittarius. 4. The winter, or that part of the ecliptick between the last point of Sagittarius and the first of Aries.

3. There are also 4 lesser circles, *viz.* the two tropicks, and the two polar circles. The tropicks are the sun's most distant parallels from the equator; that towards the north is called the *Tropick of Cancer*; and that towards the south the *Tropick of Capricorn*. The polar circles are also parallel to the equator, and pass through the poles of the ecliptick; one is call'd the *Artick*, or *North polar Circle*; the other *Antartick*, or *South polar Circle*.

P R O P. II.

Of the Cœlestial Globe.

1. The Cœlestial Sphere is furnished with the several circles before describ'd, *viz.* the horizon, meridian, equator, the ecliptick of the sun, the two colures, the tropicks, and the polar circles.

2. Through the poles of the world and the divisions of the equator, are drawn circles at every 10 or 15 degrees, which are call'd *Circles of Right Ascension*. And through the divisions of the meridian, at every 10 degrees, are also drawn circles

Circles parallel to the equator, called *Circles of Declination*.

3. In the same manner, through the divisions, and through the poles of the ecliptick at every 10 degrees, are also drawn circles, to which we give the name of *Circles of Astronomical Longitude*: And, lastly, through the divisions of the solstitial colure at every 10 degrees, are drawn circles parallel to the ecliptick, and called *Circles of Astronomical Latitude*.

4. Every star is plac'd in the intersection of its right ascension and its declination; for example, to find the bright star of Aries, whose right ascension is $27^{\circ} 35'$ and its declination $22^{\circ} 1' N$. place the moveable meridian upon $27^{\circ} 35'$ of the equator, and that point of the globe answering to $22^{\circ} 1'$ of the meridian, betwixt the equator and the north pole, is the place of the said star; and so of all the rest.

P R O P. III.

Of the Terrestrial Globes.

1. The Terrestrial Globe is also provided with a moveable horizon and meridian; and the equator, ecliptick, the tropicks, and the polar circles, in like manner too at every 10 degrees, circles are drawn parallel to the equator, which are call'd *Parallels of Latitude*; and also through the poles, and through every 10 degrees of the equator, other circles which are called *Circles of Longitude*.

Note, *These circles of longitude are more commonly drawn through every 15 degrees of the equator.*

2. Every country is laid down in the intersection of its proper longitude and latitude. Thus to find the pike of *Tenerif*, whose longitude (if the first meridian be supposed to pass through *London*) is $26^{\circ} 31'$, and its latitude $38^{\circ} 32'$, being the moveable meridian to $26^{\circ} 31'$ of the equator, and counting on the meridian from the equator northwards $38^{\circ} 32'$, under that point will be found the pike of *Tenerif*. Or if *London* were the place you look for, whose longitude is $0'$ and latitude $51^{\circ} 32'$ being the moveable meridian to the first point of the equator, and $51^{\circ} 32'$ on the meridian gives you the place of *London* on the globe. Thus knowing the longitude and latitude, any place on the globe may be easily found. Hereafter the manner of finding both the one and the other shall be shewn.

3. The terrestrial globe may be plac'd in three different situations. 1. If the equator is perpendicular to the horizon, we call it a right sphere. 2. If the equator is inclined to the horizon, we call it an oblique sphere. 3. If the equator is parallel to the horizon, we call it a parallel sphere. The people who live under the line, that is, who have their zenith in the equator, have their sphere right: Those that dwell under either of the poles (if there be inhabitants there) have their sphere parallel. All the rest of the world have their sphere oblique.

4. When

4. When the sphere is right, the horizon cuts all the parallels of the sun into two equal parts, and consequently the days are all equal to the nights. But when the sphere is oblique, the horizon cuts those parallels into two unequal parts, and therefore the days are longer than the nights in summer, and shorter in winter. Whereas the sphere being parallel, the horizon not at all cutting the parallels, but the one half being above, and the other half below, causes six months day, and six months night, to those who have the sphere in such a situation.

5. Under the equator the longest days are but 12 hours, and the further distant we go from it, the longer their days are in summer, so that under the polar circles the longest day is 24 hours, and approaching still nearer to the poles, we find one month, two months, three months of day-light, till at the poles themselves they come to six months.

6. The 4 lesser circles of the sphere divide it into five parts, call'd *Zones*, viz. two frigid, which are between the poles and the polar circles; two temperate, between the polar circles and the tropicks; and one torrid, betwixt the two tropicks.

7. The northern and southern hemispheres are each divided into 30 climates. We call a climate such a portion of the globe lying between two parallels of latitude; as has a month of day-light more than another, in the two frigid zones; or half an hour in the other zones. There are there-

fore 24 climates betwixt the equator and either of the polar circles; because there are 12 hours of day-light difference: And there are 6 climates betwixt each of the polar circles and its pole, because there are 6 months of day-light difference.

8. There is annexed to the globe, a moveable quadrant, call'd, *The Quadrant of Altitude*, to represent the azimuths, and the almicanures. The azimuths are great circles passing through the divisions and poles of the horizon. The almicanures are circles parallel to the horizon. The use both of the one and the other shall be shewa further on.

P R O P. IV.

Of the Use of the Sphere.

Since the intelligent reader will easily of himself discover the most part of the uses of the sphere; I shall here only set down a few, which may serve to open the way for the rest.

To render the problems on the globes the more easy, on one of the poles is plac'd a circle, divided into 24 hours, with an index fix'd upon the end of the axis; so that in turning about the globe, the index will pass over all the hours.

1. Set the globe to the elevation of the country you are in, that is, raise the pole according to the latitude of the place, counting the degrees on the brass meridian from the pole to the horizon.

2. Observe upon the ecliptick the sun's place, and bring it under the meridian. Then will that point

point of the ecliptick shew upon the meridian the declination of the sun, and the meridian will shew upon the equator its right ascension. Before you move the globe for the following operations, set the index of the hour circle to the upper 12.

3. Bring the sun's place in the ecliptick to the east part of the horizon, and the index of the hour circle will shew the hour of the sun's rising for that day; then moving the said point of the ecliptick to the western part of the horizon, the index will point to the hour of the sun's setting.

4. Having taken the height of the sun before noon, and fix'd the quadrant of altitude on the zenith point, bring the sun's place in the ecliptick to coincide with the quadrant of altitude, on the eastern side of the globe, then will the index shew the hour of the day, and the quadrant will mark the sun's azimuth on the horizon. The same may be done on the west side of the globe for the afternoon.

5. Having found the azimuth of the sun with a compass, there fix the quadrant of altitude, and bringing the sun's place in the ecliptick to the quadrant, the same point of the ecliptick will shew the sun's height on the quadrant, and the index will shew the hour.

6. The same things may be done with the other heavenly bodies, whose places you know, and many other curiosities; as to determine the whole situation of the heavens for any given time, the rising and setting of all the stars, &c.

P R O P.

P R O P. V.

Of the Sphere in Plano.

1. The sphere in plano is nothing else but the shadow of the several circles of an armillary sphere upon the plain of the meridian, if it were enlightned with rays perpendicular to that plain,

2. It is evident that if the circle $A D C$ be enlightned with rays perpendicular to it, the shadow of any other circle as $A B C$, perpendicular to it will be their common section $A C$. From whence it follows, that in the sphere in plano, all the circles which are perpendicular to the meridian are express'd by right lines: as the equator, the ecliptick, the horizon, and all the circles parallel to these.

3. It is also evident, that each point of the shadow $A C$, answers to each point of the circle $A B C$ by a perpendicular line $A C$. From whence it follows, that to know the number of degrees between the point A and the point F of the shadow

Fig. 9. of a circle $A B$, the semi-circle $A G B$ must be described upon $A B$, and the perpendicular $F G$ be drawn, so will the arch $A G$ give the degrees of its shadow $A F$.

4. In the same manner, to divide the shadow of a circle $A G$ into equal parts, draw over it a semi-circle, and dividing it into equal parts, from every division let fall perpendiculars upon $A G$.

5. The

5. The other circles of the globe must be express'd by ellipses; but I forbear to demonstrate that here, because it is not necessary to the following problems, which are sufficient for our present design.

PROBLEM I.

To project the Sphere in Plano.

Prepare the meridian $A G B F$ with its divisions, and let the points $G F$ be the poles of the World; the line $A B$ will be the equator, and making the arch $A C 23^{\circ} 29'$, $C E D$ will be the ecliptick. $C H$, $D H$ will be the tropicks, and $L N$ the polar circles; supposing $F L 23^{\circ} 29'$, as also $G L$. Further, having divided the ecliptick $D E C$ into 6 parts, of which each must be 30° ; draw thro' the points of the divisions the lines parallel to the equator, which will represent the signs. Lastly, divide the equator $A E B$ into 12 parts, each of which must be 15° , and through each point of the divisions, and the two poles, draw the several ellipses, and you will have the hour-circles $G N F$. There should also be placed on the center E , a moveable ruler to represent the horizon, divided as above describ'd; there should also be another little ruler, so plac'd upon this, as always to stand perpendicular to it. The figure will make all plain. The use of this sphere is too easy, to require further explanation. It is sufficient to know, that it serves to find the amplitudes, the declination, the hour, the right ascension and azimuth of the sun, as we are going to explain it

it in a manner the most universal, and which does not require the apparatus of an astrolabe, rulers and other machines, too troublesome for carriage.

PROBLEM II.

To describe upon the Sphere in Plano, the Parallels of a Day given.

Having determined A B to represent *Fig. 12.* the equator, and C D the ecliptick; draw E H perpendicular to the ecliptick C D, and the point H will be the place of the sun on the 20th of *March*; take then from H upwards toward C, as many times 30 degrees as there are months past, from the 20th of *March* to the day given; and also as many degrees as there are above the months, and you will have the point of the ecliptick answering to the day given: For example, Suppose the 23d of *May* was the day given; take 63 degrees from H to I, which will be the place of the sun on the 23d of *May*: From the point I draw I L perpendicular to the ecliptick C D, and through the point L, draw M N parallel to the equator, and you have the parallel of the given day; that is to say, the shadow of the circle which the sun will describe that day.

Note, For the greater exactness, it will be necessary to observe the day the sun enters into each sign, and so to count a degree for each day.

PROBLEM III.

To find the Declination of the Sun.

Having laid down the parallel of the day MN, measure with a graduated semi-circle, the arch AM, or the angle AEM, which is the sun's declination for the day given. *Fig. 12.*

PROBLEM IV.

To find the Right Ascension of the Sun.

After having found the point L for the given day; the ellipsis FLG will cut the equator in the point O, and OE will be the distance of the sun at its nearest approach to the equinox E; and as LR contains the same number of degrees as OE, you must find the number of degrees in LR (See *Fig. 9.*) to have the distance of the sun at its nearest approach to the equinox, which will be the right ascension of the sun during the spring, and its supplement during the summer; but during the autumn, you must add 180, and subtract it from 360 during the winter, to find the sun's right ascension, as is plain from *Figure 14.* *Fig. 14.*

P R O B L E M V.

To find the Point of the Horizon where the Sun will be, at any Day or Place given.















After having found the parallel
Fig. 15. M N, for the given day; take A H, the complement of the latitude of the place, and the line H E L will be the horizon of the place; and consequently the point I will be the point sought. The degrees between I and E will be the distance of the sun from the true east or west points of the world, which is the point E. This distance is call'd the eastern amplitude with regard to the rising; and the western amplitude, with regard to the setting of the sun.

P R O B L E M VI.

To find the Hour of the Sun's rising and setting.

In the foregoing figure the line I N will give the degrees of the parallel which the sun has run through from midnight at N, to its rising at I. In the same manner the line M I will give the degrees the sun has run through from its mid day point M, to its setting at I. Divide then the number of those degrees by 15, and you have the hours from midnight to the sun's rising, and from noon to its setting.

Use of the Globes.




PROBLEM VII.

The height of the Sun being given, to find the Hour and Azimuth of the Place given.

Resume the foregoing figure, and add to it the line OD parallel to the horizon HL, so that the arches HO and LD, will be the height of the sun : Then will OD be the almicanure of the sun, and cutting the parallel of the sun in the point V, will give VN for the hours since midnight ; VM for the hours since noon. In the same manner VO will give the degrees of the almicanure between the sun and the meridian, or the angle of the sun's azimuth with the meridian. Fig. 16.

REMARK.

A very little reflection upon what has been laid down, will render the demonstration easy ; and help to find out many other such like problems, by which may be discover'd a general method of resolving spherical triangles, with only a ruler, a pair of compasses, and a protractor.



NAVIGATION.



NAVIGATION is a science, by which we learn to conduct a ship upon the sea with ease and safety.

We say nothing of the terms, * since the persons for whom this work is intended, will learn them much easier from practice than by books.

PART I.

Of the Instruments useful in Navigation.

I *T* would be proper the reader should have the instruments described, before him, when he reads what follows.

* Tho' the author (intending this part of his work only for the use of sea-faring people) has given no explanation of sea-terms and phrases, yet being desirous to make the following tracts intelligible to those likewise who are unacquainted with the sea language; I have annexed to the translation, an alphabetical explanation of the several terms and phrases therein made use of, which I doubt not will be acceptable.

P R O P

P R O P. I.

Of Instruments for taking Heights with a plumb Line.

It has been already remark'd, that the height of a star above the horizon, is an arch of a vertical circle, or of an azimuth, comprehended between such star and the horizon. Thus the height of the star A, above the horizon C B, is nothing else but the arch A B, or the angle A D B. Fig. 1.

1. The height therefore of the star A may be taken with a quadrant or semi-circle divided into degrees: That is to say, having dispos'd the instrument in such manner upon its foot, that the plummet may play freely upon the limb, direct the sights towards the star A, and the plumb line will give the height of the star, or angle A D B.

2. In the same manner an astrolabe may be made use of, which is a graduated circle, whose divisions begin from the point D. It is to be suspended by the point A, then will the weight B keep the line A B vertical, and the line C D horizontal. Upon the center E, a moveable ruler with two sights is contriv'd to turn, which being directed to the star H, the angle G E D gives its height. Fig. 2.

3. The ring A B is still a better instrument; because its divisions are more distinguishable. There is a hole pierc'd

Fig. 3.
thro'

thro' in the point C, and as it is suspended by the point A, the weight B renders the line A B vertical, and consequently its parallel C D, and the line C E horizontal. Thus when the ray of the sun F, passes through the hole C, it falls upon the point G, and the angle G C E gives the sun's height. The whole artifice consists in dividing the semi-circle E G D into 90 degrees, beginning at the point E.

These kinds of instruments are not so fit for service at sea, by reason the motion of the ship will not permit the plumb line to settle, yet notwithstanding they may be made use of, by hanging them in jambols (that is double circles) or upon revers'd arches.

P R O P. II.

Of the Fore-Staff.

1. The Fore Staff used at sea, is composed of three pieces, viz. a cross piece or vane D C, a moveable sight E F, and a strait quadrangular piece, or the staff its self B A, upon which the vane is made to slide, and so exactly fitted, as that it may always stand at right angles with it.

2. The most usual way of taking the sun's height with this instrument, is thus ; place the vane C D at the end B of the staff, then applying the eye to the end C of the vane, and turning the back to the sun, move the sight-vane E F backwards and forwards till the shadow of the end D falls exactly upon the sight E F, at the same time that the eye at C sees the extremity of the horizon across the same sight E F : For then

ended by the line CE is horizontal, and the angle DEC is the height of the sun above the horizon; this angle is mark'd upon the staff at the point E , where the sight-vane is brought.

3. Another method is used, to take the height of stars which give no sensible shadow. Placing the eye at the point B of the staff, move the vane CD backwards and forwards, till the eye at B at once sees the star it is observing by the end of the vane C , and the horizon by the other end D ; for then will the line BD be horizontal, and the angle DBC will be the star's height above the horizon. *Fig. 5.*

R E M A R K.

In both ways the part EB of the staff, is the tangent of the angle BCE , the complement of BE in figure 5. and of CEB in figure 4. which is the half of the angle CBD , or CED the angle of the height found: Therefore the same divisions of the staff serve in both cases.

4. The staff BA is thus divided; Draw the perpendicular BC , equal to one half of the vane; then from the point C , describe a quadrant DEF , and having set off 45 degrees from D to E , draw CE , which will cut the staff BA in the point G , and so give the division of 90 degrees, since BG will be the tangent of 45 degrees, the complement of the half of 90 degrees. In the same manner divide the half quadrant EF into 90 parts, and from the point C , drawing lines to the mid divisions, your staff will be divided into degrees;

degrees ; for in proportion as the angle GCB augmented half a degree, the angle CGH will be diminished a whole degree.

The same method is to be pursued to lay down the minutes, every 10 of which should be distinguished, or, if practicable, every 5.

5. It would be still much more easy to divide the staff BA , by means of a scale, of the length of half the vane, divided into a thousand equal parts, and a table of tangents, whose sign total must be but 1000 parts : For taking from the scale so many parts as are found contained in the tangent of 45 degrees, and laying them down upon the staff from B to G , you have your first division of 90 degrees. In the same manner taking from the scale the number of parts contained in the tangent of 45 degrees 30', and setting them upon the staff from the point B , you have the second division of 89 degrees, &c. Do the same for the minutes.

R E M A R K.

If the vane is small, the divisions will stand too close, and if large, many of them will fall beyond the length of the staff : They have therefore commonly four vanes, the least of which serves for the sight vane, and gives almost all the divisions. Each vane is adapted to one particular side of the staff, to which the divisions thereof agree ; and as the half of each vane, answers to the division of 90 degrees upon its corresponding side, they are easily distinguished.

P R O P. III.

Of the English Quadrant.

1. The *English Quadrant* is composed of the Staff A D, and two arches of a circle, both which have the point A for their center, viz. B C, D E; these two arches together make up a quadrant; the divisions upon B C are of 5 degrees each, but upon D E not only every single degree is mark'd, but even every two minutes: There are three sights or vanes, all perpendicular to the plane of the instrument; the first is fix'd at the point A, the two others run one upon the arch B C, and the other upon D E.

2. To use this instrument, they first fix the vane F, and then raise or fall the vane G, till the shadow of the vane F falling upon the vane A, the eye being applied to the vane G, sees the horizon a-cross the same vane A: For then is the line G A horizontal, and the angle F A G is the height of the sun.

It will be easy to apply this instrument to the stars, nor will the Reader find much difficulty in discovering by himself the other uses of the quadrant, and of the other instruments which differ but very little from it.

P R O P. IV.

Errors to be corrected in taking Heights.

1. I say nothing here concerning the parallax, wherein the error is hardly sensible.

Vol. II.

C

2. The

2. The first error common to heights, is occasion'd by refraction, which makes a star, &c. appear more elevated than its true

Fig. 8. height: As supposing A the sun, E the eye, and B C the horizon, the true height of the sun will be A E C; but because the ray A D entering into the vapours of the earth, is broke in the point D, and passes to the eye E, thro' the line D E, the sun will seem to be in the line E D G, and its apparent height will be D E C, therefore the angle A E G must be substracted, to have the true height A E C. The angle A E G is greatest, when the star, &c. has the least altitude, as may be seen in the following table, wherein is set down, what ought to be deducted from the apparent height, to obtain the true.

Apparent Heights of the Sun	Value of the Angle of Refraction.
Degrees	Minutes
0 - - - - -	31
1 - - - - -	23
5 - - - - -	11
10 - - - - -	7
20 - - - - -	1

3. The second error regards the observation of the horizon at sea; and it proceeds from that the eye of the person making the observation, being rais'd above the surface of the sea, sees

Fig. 9. the bounds of the horizon by the tangent A B, which differs from the horizontal line A C, by the angle B A C. It would be easy to make a table of this error, with regard to the different elevation of the eye: For as E

the radius of the earth with the elevation of the eye, is to the sign total ; so is the radius of the earth to the sign complement of the error BCA . But care must be taken, that if the height is observed with the eye directed to the object, the error of the height found be subtracted ; but if the observation is made with the back turn'd there-to, the error is then to be added.

4. The error arising from the not piercing the sights of instruments, is still more considerable ; for such sights give only the upper limb of the sun, and consequently sometimes give the height $15'$ above the truth. For if the end D of the vane be obverted towards the sun ACB , the shadow G will give the height of the limb A , and not that of the center C , which is sometimes less by $15'$. Fig. 10.

P R O P. V.

Of the Mariner's Compass.

1. There are two opposite points in a load-stone, which are call'd its *Poles* ; because being suffer'd to move freely, whether suspended by a thread, or floating upon cork in the water, it will turn one of these points towards the north pole, and the other towards the south.

2. This stone communicates its virtue to iron. Having therefore a load-stone, whose north pole is A , and its south pole B , prepare a thin plate of iron, hollow'd out in the middle, and rounded at the two ends, then apply the plate to the load-stone in such manner, that the point C may be between Fig. 11.

between the two poles at E, and conduct it softly along the stone, till the point C touches the pole A ; then will the plate have the virtue of turning its point C towards the north pole, and its point D towards the south.

3. Prepare a circle of paste-board, having on one side laid down upon it the points of the compass, and to the other so fasten your iron plate, that the point C may exactly answer to the north point of the card, and the point D to the south ; then fixing in the center of the card, a hollow cone of brass, and placing it upon a pivot, the card will play freely, and turn its north point towards the north pole of the world, and consequently its several divisions will mark out the whole course of the winds, each respecting its proper point.

I shall not stay to describe the other parts of the compass, nor to observe the manner of its use ; neither do I think it needful to describe the compass of variation, or azimuth compass, since I write for persons to whom these things are very familiar.

4. I shall therefore only add, that the compass is necessary to take the plan of a place at sea, because of the motion of the vessel. The manner of using it to that purpose, is as follows. Suppose,

for example, it was required to take the plan of the road BCDEP.

At the point A, so place your compass, that through the sights you may observe the point B, and mark the degrees of the card cut by one of the sights ; do the same for the point C, and the degrees found between the points B

and

and C will be the measure of the angle B A C. In the same manner you may find the angles C A D, D A E, E A F, then from the point G, taking also the angles F G A, E G F, D G E, C G D, B G C, you have sufficient *cognita* to form the plan of the road. See *Practical Geometry*, Prop. 4.

P R O P. VI.

The declination or variation of the Compass.

The compass has very often a sensible declination, that is to say, its north point does not always answer exactly to the north pole of the world, but tends either towards the east or west. We should therefore be often deceiv'd, if this declination, which frequently changes, were not exactly observed.

I shall only give the three ways of observing the variation (for so they term the declination of the compass) which are most easy, and most commonly used; but for the better understanding them, it would be convenient for the reader to have before him an azimuth compass.

1. When the lower limb of the Sun just appears above the horizon, set the compass of variation, so that the sights may exactly respect the sun's center, and observe the point of the compass which the sights cut. If that point is the same whereon the sun ought to rise or set (which you may know by the amplitude of its rising or setting) the compass has no variation: But if that point is farther from the north than the point whereon the sun ought to be, the compass declines so many

degrees, and on the same side with the sun ; if the said point is less distant, the compass declines so many degrees towards the side opposite to the sun, that is to say, N. E. in the evening, and N. W. in the morning.

2. At any hour of the day set the compass so that the shadow of a thread, joining the two sights, may fall exactly upon the middle of the chapel (for so the brass cone upon which the compass turns, is call'd) and observe how much the said shadow deviates from the north point of the compass ; then seeking by the azimuth the sun's distance from the north at the time of the observation, if the two deviations are equal, there is no variation of the compass ; but if they are unequal, the variation will be as above describ'd.

3. When the pole-star, and the third star in the tail of the great bear (beginning with that at the end of the tail) may be cut by a plumb line: So set the compass of variation, that the same line which cuts the two stars, may also cut the two sights of the compass, for then if the sights of the compass fall exactly upon its north point, there is no declination ; but if the sights and north point do not answer each other, the difference will be the declination on the same side with the north point of the compass.

The demonstration of these practices is very evident ; as well as the manner of correcting the variation, or declination of the compass.

Of Sea Charts.

I shall say nothing of charts which some pretend to make, comprehending large parts or portions of the globe; it will be seen by what follows, how useless they are.

1. Those charts wherein the circles of latitude and of longitude are laid down as parallels, and of equal distance, are of no worth (unless they only represent a small space, and that near the pole) because they give the same extent to a degree in those parallels near the pole, as in those near the equator.

2. Charts of distance may be useful enough, if they are exactly made. They are begun by laying down the square or oblong *Fig. 13.* *ABCD*, and dividing the side *AB*, which serves as a parallel, into so many equal parts as there are leagues between the two most distant places towards the east and west to be laid down in the chart; and the line *AB* so divided, will serve as a scale of leagues. Then having fixed upon some certain point as *D*, for some noted port, as *Toulon*, to lay down another, as supposing *Cape Quiel*, draw the line *DF* upon that point of the compass, which the cape of *Quiel* bears from *Toulon*, and taking upon the scale so many leagues as is the distance between the places, lay it down from *D* upon the said line to *F*, which shall be the point where cape *Quiel* is to be plac'd. The same thing is to be done for all the other places to be laid down in your chart.

There are two methods of trying the truth of this sort of charts. 1. By observing if the places laid down answer to one another by their proper bearings ; for example, after having laid down *Marfeils* and *Majorca*, see if they answer each other according to the points of the compass they ought to lie upon. 2. By observing if the places which should have the same latitude, fall in the same line, parallel to A B. The latitudes may be laid down upon these charts, and from the latitude, or two different bearings, the distance of places may be determined.

It is further to be observ'd, that to render this sort of charts truly serviceable, they must include but a small space, and that not near the poles, especially if the latitude be laid down in equal parts taken from the line A C.

4. * Reduced charts are the best sort, the construction of which will appear in the following remarks.

R E M A R K S.

In sea charts, the meridians ought to be parallel, that the points of the compass may bear in straight lines ; but then this parallelism will occasion a considerable error in making the degrees of all the parallels equal, and laying down, for example, 20 leagues in a degree in the parallel of 60, which ought to have but 10.

To remedy this error, the degrees of latitude ought to be enlarged in the same ratio, as the

* What the *French* call *Reduc'd Charts*, are the same which with us go by the name of *Mercator Charts*.

degrees of longitude are diminished, and the degrees of latitude will serve as a scale in such sort, that the scale increasing in proportion, as we approach the pole, the degrees of longitude, which have all the same length, will contain fewer leagues in proportion as they approach the pole.

To find the ratio between the degrees of latitude and longitude, observe that if AB be taken for the radius of the equator, *Fig. 14.* and CD for the radius of a circle parallel to the equator; the degrees of the equator will be to the degrees of the parallel, as the radius AB to the radius CD , (by the 1. 12 of *Euclid*) or as the *sign* total to the *sign* complement of the arch AC ; and as the *sign* total is a mean proportional between the *sign* complement and the secant, (by the last Prop. of *Trig.*) we conclude, that the degrees of the equator, or of the latitude, are to the degrees of the parallel, or of the longitude, as the secant to the *sign* total. Thus taking the degrees of longitude always equal for the *sign* total, the degrees of latitude must consequently encrease as the secants.

5. Having prepared the rectangle $ABCD$, and divided its side AB *Fig. 15.* into so many equal parts as you would have degrees of longitude in your chart: Draw through the divisions, lines parallel to the side AC , which will represent the meridians: Then having fix'd the latitude where you would have your chart begin, and laid it down on the line AC , for example, 36 degrees north: make AE one degree of longitude, the radius of a circle, from whence take the secant of 37 degrees for the line AF , and the
 C 5
Fig. 16.
secant

secant of 38 degrees for F G, &c. and thus you will have the side A C divided into increasing latitudes. Through these divisions draw lines parallel to A B, and they shall represent the circles of latitude. After which it will be no difficult matter to lay down each place in the intersection of its respective longitude and latitude; and to add a compass to your chart.

A scale of increasing latitudes, may be still more exactly made with a rule of 1000 equal parts, to one degree of longitude; to lay down every 10 minutes, it will be sufficient to divide each degree into six equal parts. But to perform the thing in the most exact manner, by the help of tables and such scale of 1000 parts: From the sixth part of a degree, subtract so many parts as the secant of a degree, and 10' is less than the secant of a degree and 60', and the remainder will be the first part, or the first 10 minutes; and by adding them, you will obtain the last part; in the same manner subtracting from the sixth part of a degree, so many parts as the secant of a degree and 20' is less than the secant of a degree and 50' the remainder will give the second part, and adding the same, you will get the fifth part. All which is clear.

P R O P. VIII.

Of Tables.

In Navigation we make use of several tables; but the chief are the tables of the sun's declination, those of his right ascension, of his rising and setting, of his eastern or western amplitude, and of his azimuth, or of his hour for his several heights.

heights. The construction of all which follows. Further on shall likewise be given a loxodromick Table.

1. Borrowing from Astronomers a table of the sun's longitude for every day at noon, with the greatest declination of the sun, which is $23^{\circ} 29'$, and in consequence thereof, supposing in Figure 17, A B C to represent the Fig. 17. equator, E B D the ecliptick, H F I a meridian, F B the given longitude of the sun for each day, F G the declination correspondent to the given longitude, and the arch D C, or the angle F B G the sun's greatest declination; we shall be thence furnished with the following analogy, according to the 1st prop. of *Spherical Trigonometry*.

Sign total : sign B F :: sign F B G : sign F G.

That is to say, the sign total is to the sign of the sun's longitude as the sign of the greatest declination, to the sign of the declination answering the longitude given.

2. In the same manner may be found the arch B G, or the distance of the sun from the equinoctial point, by saying (by prop. 2. *Sp. Trig.*)

The tangent of the greatest declination F B G :

sign total :: the tangent of the declination

F G : sign of B G the distance of the sun from the equinoctial point.

After which it will be easy to find the right ascension.

3. To get the amplitude, let E B D Fig. 18. represent the horizon, so that F B may

C 6

be

be the eastern or western amplitude ; the point F remaining the place of the sun, and the arch FG its declination, and then the angle DBC will be the complement of the latitude of the place. Which will furnish the following analogy (by prop. 1. *Sp. Trig.*)

The sign of the compl. of the latitude B : sign of the declination FG :: sign total G : sign of the amplitude FB.

4. For the hour of the sun's rising and setting ; it is to be observed in the same figure, that if the declination and the latitude of the place, are both towards the same pole, the arch GC *Fig. 18.* will be the hour of the sun's rising, and the arch GA that of its setting ; but if the declination of the sun be one way, and the latitude of the place the other, the arch GA will be the hour of the sun's rising, and the arch GC that of its setting. It will therefore be easy to say,

The tangent of the sign B the compl. of the latitude : tangent of the declination FG :: sign total : sign of GB the compl. of the arch GC, or GA.

5. Thus may be calculated a table of the hour and azimuth of the sun at all heights, for any place whose latitude is known. For let AB be the equator, E the poles of the world, *Fig. 19.* G the sun, its height above the horizon GL, its declination GH ; the azimuth will be the angle GFE, which may be known by the resolution of the triangle GFE, whose three sides are known, viz. GE the compl. of the declination, FE the complement of the lati-

latitude of the place, and FG the compl. of the sun's height. For by cor. prop. 5. *Sp. Trig.*

1. *Add the logarithms answering the sign of the compl. of the latitude, and of the compl. of the sun's height.*

2. *Double the log. of the sign total.*

3. *Add the log. answering to the sign of half the arch composed of the compl. of the declination, and of the difference between the latitude and the height; to that which answers to the sign of half the difference between the compl. of the declination, and the difference of the latitude, and of the height,*

Subtract the first term from the sum of the other two, and the half of what remains will be the log. of half the azimuth GFE .

The same must be done to have the angle GEF , which being divided by 15 will give the hour before or after noon; only observing to put the height instead of the declination, in such sort that where-ever the declination is used in the first operation, the height is to be made use of in the second, and so reciprocally.





PART II.

Of SAILING by the SIGNS.

P R O P. IX.

Of a Ship's Course.

1. **W**HEN a ship sails due north and south, the line she describes is a true meridian, each degree of which is nearly 60 thousand geometrical paces.
2. When a ship sails east and west under the line, her course is the equator its self, the degrees of which are equal to the degrees of the meridians: But sailing east and west out of the line, her course describes a parallel to the equator, the degrees of which are to those of the equator, as the sign compl. of their latitude to the sign total (by prop. 7.)
3. When a ship sails upon a rumb line, which makes an acute angle with a line due north and south, her course does not form a circle, because
it

it describes a line making the same acute angle with all the meridians, which no circle can do. For example, let CD represent the equator, AB any meridian, and EF *Fig. 20.* the ship's course, I say EF is not the arch of a circle.

Demonst. Since the ship keeps the same point of the compass in running through the line EF , all the angles made by the course EF with the several meridians will be equal, and moreover by the supposition acute. But if EF was a portion of a circle, it would make a right angle with the meridian passing through its poles (by *sup. 6 Sph. Trig.*) and with the other meridians, angles more or less acute, in proportion as they are nearer or farther from that.

4. The course EF will be a curve line, composed of an infinite number of right lines: To explain the matter, suppose *Fig. 20.* that in parting from the point E , the ship holds a course which makes with the meridian the angle AER , some one meridian as AR must measure this angle, and that meridian will fall perpendicular upon ER ; now the angle AER , will be more acute than the angle AKR , which the ship will make with the next following meridian, if she describes the arch ER ; therefore when the ship comes to the point K , she must quit the arch EKR , and fall into the line KH , so that the angle AKH , may be the same as the angle AER ; but the ship's course, be it ever so small, must meet with an infinite number of different meridians, it therefore follows, that she must continually deviate from the circle ER ,
and

and those that succeed it, and that her course must be composed of an infinite number of lines, of which each will be part of the ship's keel, and consequently a right line.

R E M A R K.

A ship's course deviates more from the equator, or approaches less towards it, than if it describ'd a great circle; because in order to make the angles equal, the course must approach something towards the nearest Pole. For supposing *G* the place of departure, when the ship comes to the point *L*, continuing the great circle, the angles would become less acute; and consequently to keep them equal, the ship must leave the arch *LE*, and fall into *LM*, which will carry the course towards the pole *B*. It was said, that the angles which any one circle makes with the meridians, would become less acute in proportion as they approach the equator, or the line; because in approaching the line, they become more distant from that circle with which they make a right angle, or whose poles or most distant points are in the equator, upon which the poles of all the meridians fall.

P R O P. X.

Of the Loxodromick Triangle.

Let us suppose the course *AB* composed of an infinite number of right lines, making
Fig. 21. the same angle *CAB* with all the meridians: We may then imagine an infinite number of right lines *CD*, perpendicular
 to

to the meridians in the points C, which with the parts of the meridians CA, likewise right lines, will form an infinite number of rectangled triangles ACD, right-lined and similar to each other, which will furnish us with the following reflections.

1. All the bases AD of these triangles make up the ship's course; all the sides AC make up the Arch AL, or the ship's advance in latitude; and all the sides CD make up a mean arch between AF and EB, or the ship's advance in longitude.

2. All the bases AD of the triangles ACD, are to all the sides AC, or to all the sides CD; as any one base AD, to one side AC, or one side CD; so that giving to one base AD, the value of all the bases; and to one side AC, or CD, the value of all the respective sides; by the resolution of the right lined and rectangled triangle ADC, we obtain the resolution of the loxodromick triangle ALB.

P R O P. XI.

Of a Ship's reckoning.

1. To make a judgment of a ship's way, we must regard the force of the wind, the number of sails, and the manner in which they are set, but above all must be considered, the rapidity of the water passing along the sides of the vessel; all which with good experience may enable a man to make a tolerable reckoning, especially in a ship he has before tried.

2. The

2. The use of the *Lag* is very good. It is a piece of wood of half a foot long, and two inches broad, cut into the shape of a boat, as *AB*, underneath which is fix'd a little lead by way of ballast, this log is fastened to a line by two cords, one of which is fastened at the point *A*, and the other at the point *B* is only held by a pin thrust into a hole, out of which it may easily be recovered. The log being thus prepared, when they would judge by it the ship's way, they throw it into the sea over the stern, and veer out the line as the ship advances to the length of 20 fathoms; observing by a half-minute glass the number of fathoms run out in that time; if then the number is 25, they conclude the ship makes one league an hour: For if 30" gives 25 fathoms, 60' or an hour will give 3000 fathoms, or one league, the ship then makes so many leagues an hour as the log runs out 25 fathoms in half a minute. It will therefore be easy to divide the log line in the following manner: Measuring 20 fathoms from the log, there place a white mark, as visible as may be; then at the end of 6 fathoms and $\frac{1}{4}$, place a mark for $\frac{1}{4}$ of a league; and at 6 fathoms and $\frac{1}{4}$ further, a mark for $\frac{1}{2}$ a league, &c.

3. I shall not stop here to consider those machines with wheels, which some Authors have proposed for the same purpose. The sight of the sea its self is sufficient to shew their uselessness.

PROP. XII.

Of the difference of Latitude.

The difference of latitude between the place of departure, and that of arrival, may be found several ways.

1. Take the sun's height at noon, and to the complement thereof, add the sun's declination for the time, if it be on the same side of the equator with your zenith, and if it be less than the said complement, the sum shall be the latitude of the place where you have taken the altitude: But if the declination of the sun be on the other side of the equator, it must be subtracted from the complement of the sun's height, to find the latitude of the place.

To demonstrate this rule, let us suppose AB the equator, G the zenith, CD the horizon, the arch AG will be the latitude of the place; and if we suppose the sun at the point H , the arch HG will be the complement of its height, and HA will be its declination; but if the sun be supposed at the point F , the arch FG will be the complement of its height, and FA will be its declination. Fig. 23.

Demonst. It is evident, that if the sun be on the same side as the zenith, that is to say, if it be at the point F , the declination AF , ought to be added to FG , the complement of the sun's height, to give the latitude AG . On the contrary, if the sun be on the other side the equator at the point H , its declination HA , ought to be subtracted

subtracted from HG , the complement of height to obtain the latitude AG .

It may happen in the torid zone, that the zenith and the sun may be both on the same side of the equator; but the sun's declination may be greater than the complement of his height; as for example, if the sun be at the point G , and the zenith at the point F ; in that case FG the complement of its height, must be subtracted from GA its declination, to have the latitude FA .

2. The same thing may be done by such stars whose declinations are known.

3. When the pole star, and the third star in the tail of the great bear, reckoning from the end may be cut by a plumb line, take the height of the pole-star, and if it be above the other, subtract $2^{\circ} 22' 40''$ or add the same quantity if it be below, and you will obtain the height of the pole, or the latitude of the place. *

4. Several tables may be made for correcting the height of the pole; but one of the most useful is that which is composed of the height of the

* By reason of the variation of the pole-star's height in its present approximation towards the pole, which at a mean ratio is accounted nearly $19'' \frac{1}{18}$ yearly, the present quantity to be added or subtracted to the altitude of the pole-star, to obtain the true elevation of the pole, is $2^{\circ} 8' 32'' \frac{1}{2}$ instead of $2^{\circ} 22' 40''$ as above.

neighbouring stars, when they are found equal
with the height of the pole*.

I omit the other methods of discovering the
latitude by taking altitudes, because they are not
proper for use at sea.

P R O P. XIII.

Of the Longitude.

This is a problem which has hitherto been
sought in vain, I mean to find the longitude at
sea, with the same ease and certainty as the
latitude.

I. Some have thought to find it by means of an
exact pendulum, which being set to the meridian
at their departure, may keep the exact time of
their course, so that observing the hour at the
place of their arrival, and comparing it with the
hour of the place of their departure shewn by
the pendulum, they thereby may see exactly the
difference of the meridians; for, say they, if the
hour found at the place of arrival, is earlier than
the hour shewn by the pendulum, divide the
difference of the time by 4 minutes, and the
quotient will give the number of degrees made
westward in the course. But besides the difficulty

* The table in this place mentioned (tho' inserted in
the original) is purposely here omitted, by reason of the
above-hinted variation of the pole-star, and as the other
stars are likewise more or less subject to such variation,
there can be no fixing of certain allowances for any long
continuance of time, which must consequently render
such table in a manner useless.

of getting a pendulum not to be affected with the ship's motion, and the trouble of finding the hour exactly at sea; the smallest error will be found considerable, because 1 minute of time gives 15 minutes of longitude.

2. Those who would make use of the Moon's longitude, or the satellites of Jupiter to the same purpose, succeed still worse: 'Tho' indeed by the immersions and emersions of the first satellite of Jupiter, the longitude of a place may be found ashore, where there is opportunity of frequently repeating the observation.

3. There remains therefore no means more certain for finding the longitude, than by the resolution of the loxodromick triangle.

P R O P. XIV.

Of the Angles of the loxodromick Triangle.

1. The angle opposite to the ship's way is right, and the angle opposite to the difference of longitude is given by the compass, being the angle of the rumb, or the angle made by the ship's keel with the meridian (by prop. 10). For which purpose the box of the compass is so disposed that the black line thereof may answer exactly to the ship's head; and so the rumb answering to the said black line, is the line of the ship's course, and the angle which this rumb line makes with the meridian, or the arch between the said black line, and the meridian upon the compass, gives the angle opposite to the longitude.

It is to be observed, that each rumb line or point of the compass gives an angle of $11^{\circ} 15'$, therefore multiplying the points of the compass between the black line and the meridian by 114, the product gives the angle opposite to the difference of longitude.

2. Care must be taken to correct the variation, that is, it must be added, or subtracted, as occasion requires, to the angle given by the compass; there are many ways of doing this, but the most easy is to turn the black line of the compass in proportion, to starboard or larboard of the ship's head, on the side the variation lies; for then the black line will give the rumb, or point of the compass corrected.

P R O P. XV.

To resolve the loxodromick Triangle.

The loxodromick triangle, which may be taken for a right-lin'd rectangled triangle, may be resolv'd, if so much of its angles or sides are known, as are necessary for its determination; and by this resolution, we obtain the angles and sides unknown.

S E C T. I.

Departing from the latitude of 40° N. and being arrived at 42° by a N. N. E. course, it is required to find the distance sailed, and the difference of longitude. That is to say, in the loxodromick triangle A B C, wherein the angle B is right, the difference

Fig. 24.

rence

rence of latitude A B, and the angle of the rumb B A C are known, and the course A C and the difference of longitude C B are required.

1. Multiplying the 2 degrees, the advance in latitude, by 60 miles, and the side A B is found to contain 120 miles, and multiplying the 2 points between N. N. E. and the north point by $11\frac{1}{2}$ the angle B A C is found to be $22^{\circ} 30'$, then form the following analogies;

Sign C, comp. of $22^{\circ} 30'$: 120 miles :: sign total B : the miles of the course A C 136.

Sign C, comp. of $22^{\circ} 30'$: 120 miles :: sign A : the miles of the longitude B C 52.

2. If you would reduce the miles of longitude B C, into degrees, observe that these miles are run upon the different parallels between 40° at the departure, and 42° at the arrival, and therefore without any considerable error, you may suppose them run upon the parallel of 41° a mean proportional between 40 and 42 . To reduce them then into miles of the equator, correspondent to the miles run upon the parallel of 41° , use the following analogy.

Sign comp. of 41° : sign total :: 52 miles of the parallel 41° : miles of the equator 69.

And thus you will find $1^{\circ} 9'$ for the difference of longitude.

S E C T. II.

Departing from the latitude of 40° N. and arriving at 42° , after sailing eastward 136 miles it's requir'd to find upon what point of the com

base the course was held, and what the difference of longitude.

In the same triangle $A B C$ we say,
136 miles contained in the base $A C$; sign total
1120 miles contained in the line $A B$; sign of
the angle C , compl. of the angle A .

Afterwards the difference of longitude is found as in the preceding section.

S E C T. III.

Departing from the latitude of 40° N. and having sailed 136 miles on a N. N. E. course, the difference of latitude, and the difference of longitude are required:

In the same triangle $A B C$ we say,
Sign total $B : 136$ miles $A C ::$ sign C compl. of
 $A : \text{difference of latitude } A B. 120$ miles, or 2° .
 The longitude $C B$ is found as in Sect. 1.

S E C T. IV.

If the longitude and latitude be known in degrees, the point of the compass and length of the course may be found. *Fig. 24.*
 For in the triangle $A B C$, the miles contained in the line $A B$ may be found, by multiplying the degrees of the difference of latitude by 60 miles; and further, the miles of the difference of longitude may be found, by multiplying the given degrees by 60, which will give the miles of the equator answering to the miles of the line $B C$; then to find the miles of the line $A C$ form the following analogy :

VOL. II.

D

Signs

Sign total : sign comp. of the mean parallel between the departure and arrival : : the miles of the equator : miles of the line C B.

After having thus determined the miles of the line A B, and of the line B C, form the following analogies.

*Miles of A B : miles of B C : : sign total : tangent of the angle of the rumb A. Then,
Sign of the angle A : miles of B C : : sign total : miles of the course A C.*

R E M A R K S.

1. The same thing may be done with the longitude as with the latitude, since the longitude is given in miles, and not in degrees.

2. When the latitude of the departure, and that of the arrival, are one south, and the other north; it requires two operations, of which the one shall take for the difference of latitude, the distance from the departure to the line, and the other shall include the rest. Also if the course be given, it must be divided as the latitude, by this analogy ;

Miles of the whole difference of latitude : miles of the whole course : : the miles of the latitude in the first operation : miles of that part of the course.

3. When a Ship has made several different courses, it is easy to reduce them to one, after having seen by the resolution, what each gives with respect to the four cardinal points ; for adding together all that tend towards one point

and subtracting therefrom whatsoever tends to the contrary point; the remainder will be the true difference in longitude and latitude, from whence may be deduc'd the true course, and the point of the compass or rumb line answering the several Rout. See the following example.

		N.	S.	E.	W.
1 Rout	Degrees	2	0	1	0
2 - - - - -		0	3	2	0
3 - - - - -		4	0	0	5
Sum		6	3	3	5
		3			3

Value of the roots 3° North 2° West

SECT. V.

CORRECTIONS.

It often happens, that after you have resolv'd the loxodromick triangle (by Sect. 3.) with respect to the reckoning made of the ship's way, and the rumb line given by the compass, you may find by some observation of an altitude, a latitude different from that found by the said resolution; and as an observation by an altitude is more certain, than either your reckoning, or the compass, either the one, or the other, or both, are to be corrected in the following manner. 1. If the course fall'd on is very near to a due north and south line, the reckoning is corrected by making the resolution by Sect. 1. 2. If the course fall'd on, be nearly an east and west line, we keep to the latitude and distance, and correct the rumb line by Sect. 2.

D 2

3. If

3. If the course sailed on is nearly N E, and S. W or S. E. and N. W. we first correct the distance by Sect. 1. then taking a mean distance between that of the reckoning, and that given by the correction, and by this mean distance, correct the course or rumb line. The reason of these practices is easily discoverable.





P A R T III.

Of SAILING without regarding the SIGNS.

P R O P. XVI.

Of sailing by the help of Tables.

1. **T**HE loxodromick table shews under each rumb the difference in longitude, and the distance answering to each difference in latitude.

2. The table consists of but seven columns; seven rums being sufficient to distinguish the whole compass, and by the help of this table, may be performed all the operations before done by the signs. For if we allow, for example, one degree of difference in latitude by the N. N. E. look in the column which gives 22 degrees 30' for the rumb, the distance answering to one degree of latitude, to wit, 65 miles, will be the distance sailed; and the 24' of longitude opposite thereto, is the difference of longitude. In the same manner having sailed 60 miles by the N. E. $\frac{1}{4}$ N. I look in the column of the third rumb for 60, and I

D 3

find

find over against it $27'$ for the difference of longitude, and $40'$ for the difference of latitude.

3. Regard must be had to the latitude of the departure in the usage of this table, and subtract that which goes before, from that which follows in the table, to find what you look for ; for example, having departed from the latitude of 40° N. and being arrived at the latitude of one degree N. after having sailed 102 miles ; I run through the columns of rumb's till I find one, where the distance answering to $40'$ being subtracted from that answering to one degree, the remainder is 102 miles, and I find it to be the column of the seventh rumb, or of the $E. \frac{1}{4} N.$ E. if I sailed on the east side. In the same manner I subtract the longitude answering to $40'$ from that answering to one degree, and the remainder is $1^\circ 40'$ for the difference of longitude.

4. The construction of this Table is easy ; for having found (by Sect. 1.) the miles which 10 in latitude gives under each rumb for the longitude, and for the distance, we set down twice the number for $20'$; three times for $30'$, &c. and then reduce the miles of longitude into degrees.

5. Those tables which give the value of degrees of each parallel are not to be neglected : Their construction will appear from what has been before said, in the seventh proposition.

A L O X O D R O M I C K Y a b l e .

Lati- tude	1. Rumb 11° 15'	2. Rumb 22° 30'	3. Rumb 33° 45'	4. Rumb 45° 0'	5. Rumb 56° 15'	6. Rumb 67° 30'	7. Rumb 78° 45'
D. M.	Long. D. M.	Course D. M.	Long. D. M.	Course D. M.	Long. D. M.	Course D. M.	Long. D. M.
0 10 0	2 10 0	4 11 0	7 12 0	10 14 0	15 18 0	24 26 0	30 51
0 20 0	4 20 0	8 22 0	13 24 0	20 29 0	30 36 0	48 52	102
0 30 0	6 30 0	12 33 0	20 48 0	30 44 0	45 54 0	12 79	153
0 40 0	8 40 0	16 44 0	27 60 0	40 59 0	1 72 0	36 105	204
0 50 0	10 50 0	20 54 0	33 72 0	50 74 0	15 90 0	2 131	255
1 0 0	12 61 0	24 65 0	40 84 0	1 88 0	30 108 0	24 157	306

P R O P. XVII.

Of sailing by the Quadrant.

The *Quadrant of Reduction* (as it is called by the *French*) or *Sinical Quadrant*, is nothing else but a great square divided into several small ones, upon which may be found all sorts of right-lin'd rectangular triangles, with their sides divided into equal parts. The construction will appear plain from the

figure ; only take notice that the scale *Fig. 25.* *E F*, is a scale of increasing latitudes, or of secants, whose radius is equal to one of the equal parts of the quadrant. The nine lines drawn from the center *A*, represents all the rumbes of the wind ; the line *A C* serving for the north and south, and the line *A B* for the east and west.

S E C T. I.

Having sailed between the 36th and 40th degrees of north latitude, and having advanced 85 miles towards the east, it is required to know the degrees of longitude answering the said 85 miles ; or, which is the same thing, it is required to find how many miles of the equator are equal to these 85 miles : And this is what is call'd reducing the miles of longitude, to miles of the equator.

There are two ways of resolving this question by the quadrant.

1. Take upon the line *A C*, so many parts as there are degrees of latitude between the departure

D 4

and

and arrival, viz. 4, and you will have AK, then extend the compasses upon the scale EF from 36 to 40, and carry that extent from A to N; then counting upon the parallel KL 85 parts to L, reckoning 8 to each division of the quadrant, and the line AL cutting the parallel NM in the point M, gives upon NM, the miles of the equator, answering to the miles of the parallel, viz. 104 equal to $1^{\circ} 44'$. The demonstration is founded upon this, that the line AK will be to the line AN, as the sign total to the secant; or as the sign complement to the sign total; and, consequently, KL will be to NM, as the miles of the parallel, to the miles of the equator (by *Prop. 7.*)

2. Extend the thread of the quadrant from A to the 38th degree of the Arch BC; because 38 is the mean between 36 and 40, then counting upon the line AB, 85 parts to the point H, reckoning 8 parts to each division of the quadrant; the parallel HI cutting the thread in the point I, will give the miles of the equator upon IA; since in the triangle AHI, the side HA is the sign complement of the mean parallel 38, and IA is the sign total; accounting therefore 8 parts to each division of IA, you will find 104 miles or $1^{\circ} 44'$.

3. If you would change the degrees of longitude into miles, first reduce them into miles of the equator, which are measured upon the line MN, or AI, to have the lines KL, or AH, in reversing the operation.

S E C T. II.

Sailing from the latitude of 36° N. and having run 120 miles upon a N. W. course, it is required to find the difference in longitude, and in latitude.

1. Reckon upon the line A C 120 parts from A to E, allowing 6 parts to each division of the quadrant. Then having extended the thread from A to E, set it off upon the line A D which represents the N. W. and it will give the point F, and the rectangle triangle A F G will represent the loxodromick triangle, whose side A G will be the difference in latitude, and the side G F the difference in longitude; allowing therefore 6 parts to each division of these sides, you will find 85 miles, or $1^{\circ} 25'$ for the difference in latitude, and 85 miles for the difference in longitude, which you may reduce into degrees (by the prec.)

S E C T. III.

Sailing from 36 degrees of north latitude, and having run 120 miles towards the east, it is found by an observation, that the ship is arrived in $37^{\circ} 25'$ N. it is required therefore to find the rumb, and difference of longitude.

1. Reduce the difference of latitude, which is $1^{\circ} 25'$ into miles, which will be found 85, and reckoning them upon the line A C, from A to G, accounting 6 to each division; reckon likewise 120 upon the same line to E, and extending the thread to E, move it about till it cuts the parallel G F in the point F, so shall you have the loxodromick triangle A F G, whose angle G A F

45°, will give you the N. W. rumb line, and the line G F will give you 85 miles for the difference in longitude, which may be reduc'd to degrees. (by Sect. 1.)

S E C T. IV.

Sailing from 36 degrees of north latitude, and 100 degrees of longitude, a ship is to be brought to a place in the latitude of 37° 25' N. and in the longitude of 97° 39' it is required to find her course and distance. Reduce both the longitude and latitude into miles, and you will find 85 miles answer both to the one and the other, which you are to number upon the line A C for the latitude to the point G, and for the longitude, from the point G upon the parallel G F to the point F; so shall the line F A be the distance, *viz.* 120 miles, and the angle F A G will give the rumb line or course, *viz.* N. W.

S E C T. V.

Departing from 36 degrees of north latitude, and having sail'd to 37° 25' upon a N. W. course, it is required to find the distance sail'd, and the difference in longitude. Reckon the miles of the difference in latitude, *viz.* 85, upon A C to G, the parallel G F cutting the N. W. rumb in the point F, gives F A for the distance failed, and F G for the difference in longitude,

R E M A R K S.

1. There is nothing particular with respect to corrections, upon the quadrant.

D 6

2. The

2. The analogies may be all worked on the quadrant, without recourse to the table of signs: for example,

To find the amplitude, there is given the following analogy,

*The sign compl. of the latitude : sign total : :
sign of the declination : sign of the amplitude.*

Supposing then, that we were to seek the amplitude in a place whose latitude is 38° , and that the sun's declination was 10° , extend the thread from A to the 38 degree of the arch BC, and taking CR of 10° , the parallel RO will cut the thread in the point O; transfer AO upon AP, and the parallel PT shall cut the arch BC in $12^{\circ} 33'$, which will be the amplitude. The reason of which is, that in the operation 38 G, the sign compl. of the latitude, is to 38 A the sign total, as QO, the sign of the declination, to AO, or AP which will consequently be the sign of the amplitude (by 4. 6. Euc.)

3. In the same manner may be done those analogies, where the tangents and secants are made use of. For example, suppose this analogy,

Tangent of the sun's greatest declination : tangent of the declination of 10 degrees : : sign total : sign of the sun's distance at its nearest approach to the equinox.

Extending the thread thro' the 10° of the arch BC to get the tangent XB, and having transferr'd it upon the point Y, so that it may pass through $23^{\circ} 29'$, which is the sun's greatest declination, find the parallel XZ cuts in the point Z, and the parallel ZV cutting the arch BC in the point V,

will

will give VC for the arch sought. For so the tangent YB of $23^{\circ} 29'$ will be to the tangent XB, or ZS of 10° , as the sign total AB, to the sign SA, or V to that which will consequently be the arch sought (by 4. 6. *Euc.*)

P R O P. XVIII.

Of sailing by Charts.

The same rules before given, concerning the chart of distance, may be applied to the reduced chart with more ease and certainty in taking the scale of latitude.

S E C T. I.

Departing from the point A, and having made two degrees to the north, *Fig. 26.* and 240 miles to the west, the place of arrival is required. The 2° reduc'd, make 120 miles, which taken upon the scale, are to be laid down from A to B northwards, upon a line parallel to a line N. and S. then taking upon the scale 240 miles, lay them down westward, upon a line parallel to a line E. and W. and you will find the point of the arrival C: So that the line AC will be the distance sail'd, and the rumb line upon which the course was made.

S E C T. II.

Departing from the point A in the latitude of 48° N. and having made a N. W. course, by an observation at noon, the latitude is found to be $48^{\circ} 45'$ N. it is required to find the place of arrival.

arrival. Take 45 miles from the scale, and laying them down due north, you will find the point D, from whence drawing the line D E to the west, and from the point A the line A E to the north-west, the intersection E will be the place fought.

S E C T. III.

Departing from the point A, and having made 150 miles upon a N. N. W. course, the point of arrival is required. Take 150 miles on the scale, and lay them down on a line parallel to the N. N. W. and you will find the point F, the place of arrival.

S E C T. IV.

Departing from the point A, after having sail'd 130 miles, it appears by an observation, that the ship has advanced 30' towards the north, it is therefore required to find the place of her arrival. From the point A, lay down 30 miles due north to G, and draw G H due E. and W. then taking 130 miles, with that distance from the point A, make an arch cutting the line G H in the point H, which point H will be place of arrival.

Note, The arch is made to the east or west, according as the course was held.

S E C T. V.

Being within sight of land, the point A is found to bear S. E. and the point B east; it is required to find the place of observation. Thro' the point A draw a line parallel to the S. E. and

through the point B a line parallel to the line due east and west, and the point C, where the two lines intersect, will be the station or point of observation.

S E C T. VI.

In the same manner, if we were at 130 miles distance from the point A, and at the distance of 85 miles from the point G; from the point A describe an arch with the radius of 130 miles, and from the point G, another with the radius of 85, so will the point where the arches intersect each other, give the station.

R E M A R K S.

These operations are easily perform'd with a pair of compasses; for if one point be run along any line, the other point will describe a line parallel thereto, since the compasses will keep the distance they are set to, which distance may be look'd upon as a line perpendicular to that upon which one of the points runs.

I say nothing of keeping a journal, since the Court has prescrib'd a certain method, which all are to follow; besides that my design is not to offer every thing that relates to Navigation; but only what more immediately depends on the mathematics, otherwise several large volumes would hardly be sufficient.

P R O P.

PROPOSITION the last.

Of Tides and Currents.

By the Tide, we mean that flux and reflux of the sea, which is perceptible upon the coasts of the *Mediterranean*; but much more sensible on the several coasts of the Ocean. The tides then, are that rising and falling of the sea, which is observable twice every lunar day, under the following circumstances. 1. The waters are forc'd towards the shoars, during 6 hours before high tide, and this motion of the Waters is called the *Flood*; in like manner they retreat again for 6 hours before low water, and this last motion is called the *Ebb*. 2. High tide does not happen at the same time in all places; but each place has a particular time for its tide. 3. The time of the tides is not according to the hours of the sun, but according to the hours of the moon, and as the lunar hours are later every day by 48', the tides are in the same proportion of time later. 4. The tides are highest at the full and new of the moon, at the times of the equinoxes, and most especially at the autumnal equinox.

COROLLARY.

To determine the time of high tide at any place for each day, two things are to be known. 1. At what hour of the moon, the tide comes to that place. 2. What hour of the sun answers to that lunar hour for each day.

SECT.

SECT. I.

Of the Scituation of Ports.

1. The scituation of a port, is that point of the compass, shewing the hour of the moon when high tide happens in such port. Pilots distinguish the hours of the moon by the points of the compass, beginning by the north and south, upon which they place mid-day and mid-night, allowing to each point of the compass $\frac{1}{4}$ of an hour. Thus when it is said that *Brest* (or *London*) is scituate N. E. and S. W. 'tis understood that high tide happens there at the third hour of the moon.

2. To find the scituation of a port, it must once be observ'd, at what hour high tide happens, and then see what hour of the moon answers that day, to the said hour observ'd, as shall be shewn below. For example, the 16th of *April* 1729, I observe at *Brest* (or *London*) that high tide happen'd at 2 hours $\frac{1}{4}$, and I know that that day 2 hours $\frac{1}{4}$ answers to 3 hours of the moon; therefore I conclude, that the scituation of *Brest* (or *London*) is 3 hours, or N. E. and S. W.

SECT. II.

Of the Hour of the Moon.

The hour of the moon is the same with that of the sun at the time of new moon; losing every day 48' or $\frac{1}{3}$ of an hour. Knowing therefore the number of days since new moon, we easily know

know what time the lunar hours are behind the solar. For example, if the moon is 6 days old, multiply 6 by $\frac{2}{3}$, and you will find 4 hours $\frac{2}{3}$, or 4 hours 48', the time the moon has lost with respect to the sun, whence you may conclude, that noon by the sun answers to 7 hours $\frac{1}{3}$ of the moon.

S E C T. III.

Of the Moon's Age.

By the Moon's age, we mean the number of days passed since the new moon. To determine the moon's age, we must suppose as follows:

1. That the lunar month is shorter than the solar, nearly by one day, and consequently the lunar year falls short of the solar year by above eleven days.

2. That the year before the birth of Christ, a new moon happen'd upon the first of *March*; but the year after, the new moon fell out 11 days before the first of *March*; nor did the new moon happen again upon the same day, till after a revolution of 19 years: Thus every 19 years, beginning from the year before the birth of Christ, the new moon falls upon the first day of *March*; and these 19 years make up one compleat revolution of the moon.

3. The moon's age cannot exceed 30 days, therefore in every calculation of the moon's age, 30 must be thrown out as often as it is found.

4. The

4. The Epact is the moon's age at the beginning of *March*; it arises therefore from the addition of 11 days to the moon's age each year.

5. The Golden number, is the number of years pass'd since the last revolution of the moon.

6. To find the golden number, add 1 to the current year, and dividing the sum by 19, the remainder shall be the golden number. For example, to find the golden number for the year 1729, divide 1730 by 19, and the remainder will be 1 for the golden number.

7. To find the epact, divide the golden number by 3, and if 0 remains, the epact is the same with the golden number; if there remains 1, add 10 to the golden number, and if there remain 2, add 20, and the sum (rejecting 30, if exceeding that number, as above directed) will accordingly be the epact. For example, to find the epact for the year 1729, divide the golden number of the year, viz. 1 by 3, and as the remainder is 1, add 10 to 1, the golden number, the sum is 11 for the epact. The reason of this rule, is founded upon, that as the epact increases every year 11 days, and the golden number 1 day, therefore to the golden number must be added so many times 10, as there are unites above 1; but as every 3 years make 30, which must be deducted, it is better not to add the tens till after you have thrown out all the threes.

8. Having the epact, to find the moon's age for any given day, to the epact add the number of

of months pass'd since *March*, and the number of days pass'd of the current month. Thus to find the moon's age for the 6th of *July* 1729; to the epact 11 add 4 for the months pass'd, and 6 the given day of the current month, and you will find 21 for the moon's age.

S E C T. IV.

Of the Time of high Tide.

Having the moon's age, and the scituation of the port, the time of high tide is thus found multiply the moon's age by 4, and divide the product by 5, the quotient gives the hours, and multiplying what remains by 12, you will get the minutes, which time being added to the scituation of the port, gives the time of high water. For example, to find the time of high tide at *Brest* (or *London*) for the 6th of *July* 1729, multiply the moon's age, which is 6 days (after having deducted 15 days, which brings the moon to the full, and the tide to the hour of the sun, as a new moon) by 4, the product will be 24, the first part of which is 4 hours, and the remainder multiplied by 12, gives 48', adding therefore 4 hours 48' to 3 hours, the scituation of *Brest*, find the time of high tide for the said day, 7 hours 48'.


S E C T. V.












Of Currents.

We oftentimes attribute to imaginary currents the error arising from the wrong disposition of the

the coasts in charts, as in the gulf of *Lions*,
 where the cape of *Quiel* is really much more
 westward than it is laid down; nevertheless we
 cannot deny but there are currents, and more
 specially near land; and that it is of the utmost
 importance to have a due knowledge of them.
 It is no great difficulty to judge of them when
 within sight of land; but out at sea the most easy
 method is, to set out the boat, and throwing out
 heavy grapling or other considerable weight,
 with as much line as possible, the boat, as if at
 anchor, will vere with the wind, if there be no
 current; but if there be a current, and little or
 no wind, the boat will then drive with the cur-
 rent, and plainly enough shew which way it
 sets.







F. 25. Vide Plate 3.






Fig: 25



E F



The true form of
the Sinical Quadrant
when perfected accord-
ing to the English method
of Projection



OF THE
WORKING
OF A
SHIP.

ADVERTISEMENT.



HO' the working of a Vessel is, without dispute, the most important knowledge with regard to the sea-service, yet no one hitherto has writ a compleat treatise on the subject. F. Pardies, indeed, in a tract of local motion, has, in few words, given at light into this matter; nor would it be difficult, from the principles he has advanc'd, to deduce all that may be thought necessary on the subject. The Author of the Theory of working a ship, entered into the matter more largely, and more judiciously and solidly determined four or five of the most difficult propositions. The tract, call'd
The

The exercise of working a ship, is also a useful work, and must be acknowledg'd a production suitable to that great capacity, which all France admires in its most illustrious Author. Nevertheless, these several works not seeming to me sufficient to give a perfect knowledge in this art, I have undertaken the following tract, wherein I have endeavour'd to explain in order, all the several managements of a Vessel, with the rules for their proper application. I have, in the clearest manner I was able, laid down all I thought proper for my design, believing I had more reason to fear censure, for omissions of any thing necessary to the instruction of those for whom I write, than for the publication of what might otherwise have been better concealed from Strangers.

Caution to the *English* Seaman.

To this advertisement of the Author's concern the original, I beg leave to subjoin the following caution to the *English* Sailor, with respect to translation: That he would not be prejudiced against the work, upon sometimes finding the French practice different from the *English*: For though the reasons why a thing is done, may not be affected by the manner in which it is performed; yet if according to the worst way of performance, the expediency of the thing be demonstrated; certainly the better method is thereby more abundantly justified. Therefore as the Theory here laid down will be found universal, and as the *English* are confessedly the best navigators in the world, their application to their practice will consequently appear the most natural; and will probably furnish many useful hints for future improvements.

Of the Working of a Ship.

Y the working of a Ship, is here meant the Art of giving a vessel all the motions of which is capable, and the giving them properly.

We shall divide this Tract into three parts. In the first of which we shall consider the use and effect of several Instruments made use of to put a Ship in motion. In the second, the several ways of turning a Ship. And in the third, lay down the rules for navigating a Vessel upon the open sea, from one Port to another.

DEFINITIONS.

The *Motion* of a body, is that which carries it successively, from one place to another.

The *Direction* of motion, is the right line along which the body is thrust, or determin'd to move, and through which it moves it in effect when free. Thus when *Fig. 1.* a body A is determined to pass along the line A B, the line A B, is call'd *The direction of motion.*

The *Wind* may be considered as a great number of little bodies of air thrust along in parallel

parallel lines. These lines compose what may call'd a *Bed or Body of Wind*; so likewise *Current* is a great number of drops of water pushed forward in parallel lines, which form the *Body of the Current*.

4. In each of these lines which form the body of wind, may be considered two points, of which the nearest to the rise of the wind, is said to be to windward of the other. For example, if

Fig. 2. corpuscles which compose the body of wind are thrust from the points A, the points B, we say the points A, the points C, are to windward of the points B, and that the points B are to leeward of the points A and C. We say likewise, that all the points A, on the line A A, perpendicular to the body of wind, are equally to windward. The reason is, because if two vessels D and E, depart at the same time from two points of the line A A, and move with equal velocity along the lines E F and D F, equally inclined to the body of wind, they will meet each other at the point F, and neither shall pass to windward of the other.

5. Supposing again, the wind to blow from B, if a vessel made her course from B to A, she would be said she went in the wind's eye, or directly against the wind, which is impossible; so likewise, if a vessel sail along the line B H, she would go less to windward, or less against the wind, than in the line B A; but more to windward than in the line B H.

6. We say a vessel comes to the wind, or to, when she ranges on a line more contrary

the direction of the wind ; and that she wares
falls off, when she ranges on a line less con-
ary to the wind. For example, if a vessel on
the line *BH*, should range on the line *BG*, she
comes too ; but if being on the line *BG* she
ould range on the line *BH*, she wares.

7. When a vessel keeps a line the most contrary
the wind that she can sail on, she is said to
ill upon a wind ; but when she runs upon a line
early perpendicualar to the course of the wind,
e say she sails with a large wind ; and having
the wind right a stern, she then sails before the
ind.

S U P P O S I T I O N S.

1. If at the same time that the body
moves from *A* to *B*, in the canal *Fig. 3.*
B, the canal its self is carried from
B to *CD*, the body *A* shall move in the dia-
nal *AD*, and its true motion be compos'd of
the motion carrying it from *A* to *B*, and of the
otion whereby it is carried with the canal from
B to *CD* ; that is to say, if the body *A*
oves in the diagonal *AD*, two motions may
ways be distingulshed, one approaching the
e *BD* perpendicular to the canal *AB*, the other
proaching the line *CD*, parallel to *AB*.

2. A body in motion, will only thrust on such
ers as oppo'e it. Therefore the body
moving along the line *AB*, parallel *Fig. 4.*
the line *CD* of another body, will
press no motion on it ; but moving *Fig. 5.*
the line *AC*, perpendicular to *CD*,

it will then communicate all its motion. Farther if the motion of the body A be along the diagonal A D, it will communicate in the point D only the motion approaching the line C D; that is to say, it will make the same impression as if it had fallen upon C D by the perpendicular A C, or B D, provided it took up the same time in running through B D, as it does in running through A D.

3. From whence it follows. 1. That when the body A falls upon C D, in the diagonal A D, its own motion, is to that it communicates, in proportion as the sign total A D, is to A C, the sine of the angle of incidence A D C. 2. That the body A does not force the body C D, by the direction A D, but by a direction perpendicular to the face C D, viz. A C or B D.

R E M A R K.

The body C D thus thrust, does not in effect move in the direction B D perpendicular to the face C D, but under two considerations. 1. That all parts of the body C D receive the same impression, all being struck in the same manner, or that the impression made on the point D, which is suppos'd to be the center of gravity, be equally communicated to the other parts. 2. That the several parts of the body C D have all the same facility of moving.

4. If an infinite number of cylinders E F, fall perpendicularly upon the face A B of a body, they will have a greater effect than if they fell upon the two faces A B and B C; because to the plane face A B, the

* Of the projected weight. ft. 7.

could communicate all their own motion, but to the faces AC , BC , only a motion in proportion to their own, as the signs of the angles $EF C$, to the sign total : From whence it follows, that a body AB will more easily divide the water in presenting its two faces AC , BC , or its convex face ABC , than in presenting its plane face AB . *

5. When the wind which strikes a sail, freshens, two things happen: 1. Each of those little bodies which compose the wind, push the sail with greater force. 2. A greater number of those little bodies strike the sail in an equal time. From whence it follows, that the motion which the wind impresses on the sail, increases in a duplicate proportion to its force, which is nothing else but the velocity of the bodies which compose it.

6. The difficulty which a ship finds in dividing the water, arises from that the water strikes the ship with the same force, as if she remained immoveable, and that the water came against her with the same velocity as she moves against the water. From whence it follows, that the difficulty of a ship's cutting the water, increases in a duplicate proportion to her velocity; for the farther she moves, 1. Each particle of water strikes against her with greater force: 2. A greater number of such particles strike against her in an equal space of time.

* Of the Motion of Fluids, and the Resistance made to projected Bodies; Vide Sir *Is. Newton's Principia*, Book II. Sect. 7.

7. From which observations it follows, that the velocity of a ship increases only as the root of the forces which give it motion.

8. If the sail AB be perpendicularly opposed to the wind, and another equal sail

Fig. 8. CD be set slant-ways, the impulse on the sail AB will be greater than on the sail CD , in two respects; for 1. The force of each particle of the wind upon the sail AB , in comparison with the same particles on the sail CD , is as the sign total GE , to the sign GH of the angle of incidence CEG (by *Sup. 2*) 2. The quantity of wind which strikes the sail AB , in comparison with the quantity of wind striking the sail CD , will also be as the sign total EA , to the sign EC of the angle of incidence CEA . From whence it follows, that the impulse upon the sail AB , will be to that upon the sail CD in a duplicate proportion of the sign total, to the sign of the angle of incidence GE , and universally the impulses which a sail receives from the same wind in different situations, are to one another as the squares of the signs of the angles of incidence, which the wind makes upon the sail.





PART I.

*of the INSTRUMENTS made use of to put
a Ship in Motion.*

PROP. I.

Of the Hull or Body of a Ship.

THE whole figure of a vessel may
be refer'd to two profiles, viz. the Fig. 9.
vertical A, and the horizontal B.

1. The profile A, shews that a vessel naturally
presents her head to the wind, and the profile
B, shews that she as naturally presents her head
to the current; for in that position only, the wind
and current have the least hold of her, and striking
equally on each side, keep her as it were, in a
perfect equilibrium.

2. It does not hence follow, that if the hull of
a ship were floating at liberty in the middle of the
sea, that it must needs always present its head to
the wind; because in proportion as the ship gets
down-way, the water abast getting more power

of her stern, forces it up against the wind; but the wind in its turn, as it thereby obtains a greater hold, repels it back again; the ship therefore cannot keep one constant situation; but must sometimes offer her head, sometimes her stern; but most commonly her side to the wind.

3. 'Tis not the same in a current; for if the vessel be therein free, she will constantly present her head to the stream, for the reasons before given; because the water abaft, being carried on as fast as the ship, does not consequently strike against her counter.

4. If a ship could be so fix'd in the sea, as to turn easily about her center of gravity, she would constantly present her head to the wind, or the current.

5. So likewise, if a ship without wind or current, was mov'd by a power applied to its center of gravity, which would admit its turning any way, she would go head foremost, because the water, which is supposed motionless, would have the same effect upon a vessel in motion, as a current would have upon a vessel not in motion.

C O R O L L A R I E S.

1. From these considerations, we see why ships so easily come to the wind, and why it is necessary to increase the head sails, to make them ware.

2. The reason is as clearly seen, of a ship's falling off as soon as she gets stern-way, and why so long in staying when she runs a head; for when she goes
for-

forward, the water striking on both sides, hinders her from readily turning either to the right or left; whereas in her recoiling or stern way, the water abast thrusting up her stern, causes her to fall off, as soon as ever she loses her perfect equilibrium.

6. If a ship were perfectly round, she would always keep the direction of motion given her; but being of a figure more adapted to cut the water with her stem, than with her sides, she does not always follow that direction of motion; for example, Suppose the vessel A B, pre'd along by the sail C D, whose *Fig. 10.* direction is E F; if the vessel were round, she would keep the direction given, and sail on the line E F, and consequently the motion she would receive from the sail in this disposition, is a compound of two motions, one carrying her straight forward, the other side-ways. Or if the ship had the same difficulty to divide the water with her stem, as with her side, she would keep the line E F; that is, she would gain the length E A, eight forwards in the same time that she would gain A F side-ways. But if a ship finds ten times the difficulty to divide the water with her side, as she finds in dividing it with her stem, she will then gain but the $\frac{1}{10}$ of A F, *viz.* A G, in the time of her gaining the length E A; and consequently she will be found at the point G, at the same time she would have been at the point F, if it had been as easy for her to have divided the water with her side as with her stem.

R E M A R K S.

1. The line EG will be the true course of the vessel, and the angle AEG the angle of variation. The line AG will always be to the line AF , as the difficulty the ship finds in dividing the water by her head, is to that she finds in dividing it by her side.

2. The angle AEG changes, and becomes greater, in proportion as the angle AEF is increased; for the tangent of the angle AEG is to the tangent of the angle AEF , as AG to AF .

7. If any obstacle absolutely takes off the sidemotion of a vessel, she will keep the line EA and will arrive at the point A , in the same time she would have come to the point F , if she could as easily have cut the water with her side as with her stem.

C O R O L L A R Y.

From hence it follows, that if a vessel did not fall off, and a semi-circle were made

Fig. II. upon the line of direction EF of the sail, the vessel would arrive in the same time at any intended point of the semi-circle; that is, she would come in the same time to the point H , or the point I , as to the point F , if she had no more difficulty in dividing the water by her side than by her stem.

8.

necess
articl
one.

toward

ble p

adv

Set

time, a

is an

ne E

ther p

ship h

keeps

method

ou ma

ngle A

The

tange

the s

the d

1. As

eximen

peated

2. Th

be c

rection

rection

rection

mean d

ut as t

8. As all vessels do not fall off alike, it is necessary to find the lee-way of any

particular vessel ; which may be thus *Fig. 10.*

one. Suppose the ship A B advancing towards some coast ; take notice of some remarkable point, as H on the shore towards which she is advancing, which you may observe two ways.

1. Set the point H by the compass from time to time, and if you find it always in the same rumb, it is an infallible mark, that the ship sails on the line E H.

2. If the point H answers to some other point as I, and continues to do so after the ship has sail'd some time, it is evident the ship keeps her course E H I. When by one of these methods you find the ship keeps the line E G H, you may compare the angle A E G, with the angle A E F, by the following analogy ;

The tangent A G of the angle A E G : the tangent A F of the angle A E F : : the difficulty the ship finds in dividing the water by its stem : the difficulty of dividing the water by its side.

R E M A R K S.

1. As the waves and currents render this experiment very uncertain, it must be frequently repeated, and that under different circumstances.

2. The hull of a ship is also in some measure to be considered as a sail, giving the ship a direction perpendicular to that of her keel ; this direction with that of her sails, compose a mean direction between E F, and E L, and with this mean direction the lee-way should be computed : but as the thing is indeed impracticable, 'tis sufficient

sufficient to make the experiment as before directed, with the sail set in different positions; when if the same ratio is constantly found between AG and AF , it may be concluded that the ship's hull makes no difference in the trial; but if the ratio of AG to AF , is found least when the sail is sharpest trim'd, the difference is justly attributed to the ship's hull; and the remedy is to brace the sail in proportion to such difference.

9. If a ship AB , were of the same figure, both head and stern, we might from thence draw the following conclusions. 1. That if her

Fig. 12. head A only, were push'd in a direction perpendicular to her keel, she would turn about, and the center of her motion would be evidently in her stern B ; so likewise if she were push'd by the stern, she would turn about her head A .

2. If she be push'd at the same time, on the same side, and with equal force in the points A and B , her movement will be in a line perpendicular to her keel. 3. But if she be push'd on different sides at the same time, she will then turn about her center of gravity.

10. The form of a ship gives her a greater facility of dividing the water with her

Fig. 13. head than with her stern: If the vessel AB be push'd by the stern B , with a direction perpendicular to her keel, she will not turn about her head A , but about her center of gravity; whereas, if she be push'd a head with a direction perpendicular to her keel, she will turn about her stern B , unless at the same time she be push'd on the contrary side a stern, for then

When she will turn about her center of gravity. From whence it follows, that when a ship turns, she almost always turns about her center of gravity; because she is almost always thrust fore and aft on opposite sides. These rules are so plain they need no farther explication.

P R O P. II.

Of the Rudder.

1. Suppose AB the keel of a ship, and BC the rudder inclined upon that keel; as the keel moves forwards, the water will have the same effect upon the rudder, as if the keel remain'd immoveable, and the water run a stern in lines parallel to the keel, with the same velocity as the keel advances; that is, the water will strike the rudder by lines sensibly parallel to the keel, and push it back with a force proportionate to the velocity of the keel. Fig. 14.

2. All the parts of the rudder being struck with the same force, it will be repell'd in the same manner as if the whole force which strikes it were united in its center of gravity D . Draw the perpendiculars DF upon the keel continued, and DG upon the rudder; if then the absolute force of the water be measured by the line BD ; the impression it makes on the rudder shall be measured by DF the sign of the angle of incidence BDE , and the impression of the rudder on the keel by FB the sign of the angle of incidence BGD (by *Sup.* 2.) But since the impression of the water on the rudder increases in a duplicate ratio of the sign of the angle of incidence

eldence (by *Sup.* 8.) It may be concluded, that the force of the rudder upon the keel may be express'd by the product of the sign BF , multiplied by the square of the sign DF . Thus by a trigonometrical calculation may be found, the force of the rudder upon the keel in every position; and it will appear, that the most advantageous scituation of the rudder, is when it makes the angle CBG with the keel continued of $54^{\circ} 44'$. For if the said angle be made either more or less, the force of the rudder upon the keel will be diminished. *

R E M A R K S.

1. Care should be taken that the helm be never so far put over, as to make the angle CBG of the rudder with the keel more than $54^{\circ} 44'$.

2. Though the more the rudder be inclin'd, the more it stops the ship's way, it does not therefore follow, that the foregoing proposition is the less exact, as the Author of the Theory seems

* The Author here gives an algebraical calculation of the most advantageous angle the rudder can make with the ship's keel; as likewise he does at the end of the 18th Prop. of the most advantageous scituation of the sail with the wind; but as he has inserted no Tract upon the subject of Algebra in his collection, but seems to have purposely omitted it throughout his whole Scheme, I rather chuse to leave out the said calculations, than improperly (I think) introduce them into a Work, which the Author himself, in the projection of his Plan, seems to have thought compleat without Algebra.

to apprehend ; since the impulse of the rudder is given before the ship's way is lost, and her after-motion, is according to the first stroke of the water against the rudder.

3. Another remark of the same Author's is better founded, for it is true, that a ship's not always advancing in a line parallel to her keel, does something affect the said rule ; for the oblique way of a ship requires that the angle of inclination of the rudder with the keel prolong'd, be greater when the rudder is to leeward, and less when to windward.

4. When the rudder B C is to leeward, it pushes the after-part of the keel to windward, and makes the head of the vessel fall to leeward ; on the contrary, if the rudder is to windward, it thrusts the after-part of the keel to leeward, and makes the vessel come to the wind.

5. This is to be understood when the ship has head-way ; but if she goes a stern, the effect of the rudder is quite different, for the water which is behind her strikes it in the direction H D ; so that in stern way, if the rudder be to leeward, it brings her head to the wind ; if to windward, the contrary.

P R O P. III.

Of the Sails in general.

1. Sails have the more force the higher they are hoisted ; not because the mast is a kind of Lever, as some of the ancients thought ; for it is very certain

certain their height does not increase their proper motion in that respect: But the greater force they obtain in that situation, is occasioned by the winds blowing more fresh aloft, where its motion is less impeded by the vapours of the earth or sea; besides that the higher the sails are hoisted, they are the more exposed to the wind.

2. Sails have more force the tighter they are hoisted, because, 1. They catch more wind. 2. The wind strikes them more directly. 3. The impression they receive is more uniform. For

supposing the taught sail A B, and
Fig. 15. the concave one A C B; 1. The taught sail A B, shall take as much wind, as the concave one A C B, though it be larger. 2. The wind communicates all its motion to the taught sail, as it falls perpendicularly upon all its parts; but to the concave sail, only a motion in proportion to the angles of incidence (by *Sup. 2.*) If the wind does not fall perpendicularly upon the sail, but strikes it obliquely by the lines A D, C D, B D, the wind will hardly have any effect on the windward part of the concave sail, and its impulse upon the leeward part, to which it is more perpendicular, serves scarcely for any thing else but to flat off the vessel, because it is nearly parallel to her keel; nay, it often happens, that that part of the sail near the clue, when the sheet is haled aft, proves intirely a back sail, and is of great disadvantage.

3. These considerations shew how much they are deceived, who cut their sails so as to bag in the middle, imagining that such bagging gives the wind a greater power, especially when sailing close

close upon a wind ; whereas, indeed, the part so bagging out is hardly struck at all by the wind, and is only fill'd with eddies from the adjoining parts of the sail, which have no force at all.

4. For the same reasons the top sails have a greater effect upon a wind than the lower sails ; for the lower sails not having yards to spread them at the foot, do not oppose the wind so flat. However in failing close upon a wind, the lower sails are not to be brac'd with the foot without board, because then not having a sufficient power to trim them taught, they will become in a manner useless ; they are best spread by belaying the backs and sheets to cleats, fastned to the ship's side, in such manner that they may be brac'd by the yards above, as the top sails are by the yards below. *

5. So likewise those top sails, whose lower yards are too long, are not so fit for failing close upon a wind, because they cannot be hal'd sufficiently taught. It is likewise proper the main sail should be so cut, that the parts nearest the hulk may not bagg when the ship is close upon a

* When a ship is to keep close upon a wind, the English manner of trimming the sails is as follows : The main-tack, fore-tack, and mizen-tack are brought close to the board, and over-hal'd as forward as may be ; the bowlines are the same on the weather-side ; the lee-sheets are hal'd close aft, but the lee-sheet of the fore-sail not so close as the others, unless the ship gipes ; the lee-braces of all the yards are braced aft ; and the top-sails are braced, and govern'd as the sails to which they belong.

wind,

wind, because the direction of those parts would rather hinder her way.

6. When the wind EC is perpendicular to the sail AB , and the sail

Fig. 16. AB perpendicular to the keel CD , the sail AB is thrust with the whole force of the wind, and communicates its whole motion to the keel, moving it a head in the direction CD ; so that this Disposition of the sail with the wind, and with the keel, is the most advantageous for making head-way with only one sail: But in ships which have many sails in this disposition, those at stern will keep the wind from filling those a head; therefore ships make most way when the wind is just abaft the beam; at least if there does not run too great a sea. And some Corsairs in chasing a vessel which sails before the wind, allow themselves two points of the compass sometimes on the starboard, and sometimes on the larboard side, in order to come up with her the sooner. It is not altogether the same thing when the sea runs high, for the waves striking upon the ship's counter, supply the deficiency of the wind on the head sails, and would make the ship fall very much off, if she were not exactly in the direction of the wind.

7. When the sail AB inclines with the wind, the impulse it receives there

Fig. 17. from, decreases in a duplicate proportion of the sine of the angle of incidence (see *Sup. 8.*) and when the sail AB , inclines with the keel CD , it will communicate thereto all its own impulse; but since its direction is not right a head the head motion it will impress thereon, will de-

crea

crease
keel.

8. S
ngula
quire
andin
from
se of

9. T
ngula
baft;
two ba
would
The
nd ma
wind
rac'd,
verfer
a po

* Our
iz. the
very tin
consequ
ted in t
sils, as
out, t

crease as the sign CD of its inclination with the keel.

8. Square sails have a greater power than triangular ones, as being larger ; but then they require more rigging, are more difficult, and slow in standing, besides that they are more dangerous. From whence comes that diversity of sails made use of in different vessels.

9. The most advantageous situation of a triangular sail, is when the yard stands before the mast ; because were it behind, 1. It would cause two baggings on the two sides of the mast, which would render a great part of the sails useless. 2. The yard would bear harder upon the mast, and make it more in danger of breaking. 3. The wind would have power of the sail before it is brac'd, which would put the vessel in danger of oversetting, if the wind should take it when it is in a position parallel to the keel. *

* Our ships have but one triangular sail bent to a yard, viz. the mizen, which is shifted to leeward of the mast every time the ship tacks, and can therefore be of no ill consequence. But there are certain small vessels much used in the *Mediterranean*, which have only triangular sails, as likewise have their gallies ; but still in going about, they are always shifted to leeward of the mast.

P R O P. IV.

Of the Head Sails.

1. The Head sails serve to keep the vessel steady, hindring her from sheering to and again; for suppose A B the vessel, if she be only impell'd by her main mast CD, her fore-part B will indifferently receive every motion of the bodies it meets; for since the motion of the point C tends precisely only to the carrying the point C forwards, it will only have its full effect upon the point B, when the said point B is precisely right before the point D, and consequently will not hinder the point B from receiving from the waves, a motion carrying it either to the right or left. But if the point B is fix'd to a power, which will carry it right forward, it will draw after it the rest of the vessel, and the water which strikes against both its sides, will keep the ship in equilibrium, and so overcome the motion which the waves would impress on the point B, which would otherwise throw her off to the right or left, and to this purpose the head sails chiefly serve.

2. The head sails, when brac'd sharp to the wind, help a ship to ware. For let the sail A B inclined upon the end of the keel, receive the wind F D from abaft, it will impress on the point D, a motion whose direction will be D E (by *Sup. 2.*) and which will consequently be compos'd of two motions, the one carrying the point D right forward, and will be express'd by the sign D H, of the angle of the

the sail with the keel; and the other carrying the point D sideways, and thrusting it to leeward, with a force expressible by HE, the sign of HDE, the complement of the angle of the sail with the keel.

3. From whence it follows, that the more the head sails are braced, the sooner the vessel wares, having more force to flat her off; for in bracing the yard A of the sail AB, 1. The angle of the wind upon the sail is increased, *vis.* FDB, and consequently the motion the sail receives from the wind (by Sup. 8.) 2. The angle EDH is increased, and consequently the force of the sail to thrust the point D to leeward (by the prec.) This rule is commonly found true in practice. Nevertheless the wind FD may so come from abaft, that in bracing in the lee-brace, the angle of the sail with the wind, may be so diminished, that the sail may lose more of the force it receives from the wind by the diminution of the angle FDA, than it acquires by the augmentation of the angle HDE, to make her ware. But this can only happen to such sails as may be so brac'd as to become nearly parallel with the keel.

4. If the wind DF take the sail B aback, the vessel will either fall *Fig. 20.* off, or come to, according as the lines FD divide the angle of the sail with the keel; that is, if the line FD divide the obtuse angle of the sail with the keel, she will fall off; but if the line FD divide the acute angle of the sail with the keel, she will come to; in both cases the sign H, of the complement of the angle BDH, measures

measures the force of the sail, either to flat her off, or bring her to.

5. In the first of these two cases, it commonly happens, that the more the sail is inclined with the keel, the more the angle of the wind with the sail is augmented; and consequently the more the sail is inclined, the more force it has to make the ship fall off. But it is not the same in the second case; for if the yard be too much braced in, the angle FDB of the wind with the sail will be diminished, and may become so acute that the wind shall hardly have any force upon the sail. It is therefore necessary, that the angle FDB be always greater than the angle EDH since the force of the wind upon the sail increases in a duplicate ratio of the signs of the angle FDB ; whereas the force of the sail to bring the ship to the wind, increases only in proportion as the signs of the angles EDH . In short, it is easy to determine in all cases, the content of the angle FDB , which shall have most power to bring the ship to the wind; since the product of the square of the sign of the angle FDB , by the sign of the angle HDE , expresses the force of the sail in bringing a ship to the wind, and consequently the angle FDB will be most advantageous, when it makes that product greatest. A table might easily be calculated for this purpose, if it be found useful in practice.

6. What has been said of the head sails, may be applied to the sprit-sail, which is still more useful in flattening off, or wareing a ship, as it is farther remov'd from the ship's center of gravity and is capable of being braced sharper, as may be seen by the windward

being hinder'd by the shrouds: Its chief use being to keep the ship from sheering backwards and forwards; for being very much inclined a head, it greatly checks the rising motion which the waves impress upon the head of the ship.

7. The fore sail, and fore-top sails being situated upon the end of the keel, have all the effects of the head sails. 1. They hang something forward, to prevent the vessel's sheering. 2. The fore sail is narrowest at the bottom, that it may more easily be brac'd taught. 3. The fore sail and fore-top sails have but little force (the ship wareing) when their lee-braces are hal'd in close, because then the angle they make with the wind is very small, though that which they make with the keel is large enough. 4. For which reason when they would ware expeditiously, they hale in the weather braces as close as possible, which makes the ship immediately fall off; for *they call this way of wareing, by laying the head sails aback.* 5. The fore sail serves likewise to turn to windward, after the manner explain'd above. 6. The fore sail and fore-top sails may also, if laid aback, bring up the ship to the wind, notwithstanding they stand perpendicular to the keel. For let A B *Fig. 21.* represent a sail perpendicular to the keel CD, and the course of the wind be CE, the sail being thrust by the wind CE, will force the vessel back by the direction CD, (Sup. 3.) but as at the same time the wind will find better hold on the stern, it will consequently push it to leeward, and make the ship lose its equilibrium, the water too abaft, having better hold on the windward side of the ship's counter, and pushing

it likewise to leeward, the vessel will be in danger of turning quite round; to hinder which effect of the fore sail, they put the helm a-lee, that the water a stern pushing the rudder D F windward, may resist the wind which thrusts the stern D to leeward.

P R O P. V.

Of the Main Sail.

1. The motion impress'd by the Main Sail on a ship, tends directly only to move that part of the vessel where the main mast is fix'd, viz. in the center of gravity, communicating to the other parts no more force than is necessary to move the said center of gravity in the direction of the said sail.

2. If the main sail AB is thrust forward in the direction CD parallel to the keel, it shall impel the ship in the same direction, and the water striking against both sides, shall keep her in equilibrium, and hinder her turning either to the right or left.

3. If the direction CD of the main sail were perpendicular to the keel AB the ship would by degrees range herself in that direction, and would bring her head A to the point D, for the water finding better hold on her stern B, than on her head A, will by degrees repel it behind the point C.

4. If the direction of the main sail oblique upon the keel, as CE ; the ship will sail in another direction between CD and CE , and make more head than she way; because the water striking against her sides, will keep her in equilibrium, and this oblique direction of the sail will commonly hinder her turning either to the right or left. But still this doth not hinder but that a ship only under a main sail, may readily enough come to the wind; for the wind having great hold of the stern, will force her after-part to leeward, even with more force than is necessary to break the equilibrium.

Fig. 24.

5. When the wind takes the main sail AB aback, in the line EC , the keel is thrust in the direction CF , and the same thing will happen, as when the sail is in the situation above explain'd.

Fig. 25.

6. If the main sail AB being taken with the keel aback in the line CE , is not perpendicular to the keel, but that its direction is some other as CH , the ship will nearly keep the same direction; but the water thrusting up her stern against the wind, will soon make her fall off, unless the rudder FG being put to leeward, overcomes the said force of the water upon her stern.



P R O P. VI.

Of the Mizzen.

1. The Mizzen serves as the other sails, to give the ship head-way; but its chief use is to bring the ship's head to the wind, by forcing her stem to leeward.

2. The triangular figure of the mizen, is well adapted to this design; 1. Because it is easily hal'd up or out. 2. It presents itself more effectually to the wind, as its yard is less flexible than a rope or stay. 3. The shrouds are no hindrance to it, but it may be easily inclined in any manner with the keel, insomuch that it may be full when all the other sails are aback.


3. It is true, that triangular sails design'd to give ships head-way, ought not to have the sheet hal'd to windward, lest the greatest part of the sail should become a back sail. But it is not so with the mizen, whose chief use, as was said, is to force the after-part of the ship to leeward, by a line perpendicular to the keel; for it has often times more force to bring a ship to the wind with the sheet to windward, than to leeward, as when the wind is far forward. For


Fig. 27. AB represent the ship, and HG the wind, then shall the mizen CD have more force to bring the ship to the wind, than the mizen FE. However the making thus a back sail of the mizen, is seldom practiced, except in some extraordinary cases, because it breaks the ship's head-way.

P R O P. VII.

Of the other Sails.

The other sails which are made use of besides these already explain'd, as bonnets and stay-sails, have nothing particular. It is only necessary to observe, that oftentimes the stay-sails only serve to make a ship fall off, because they are parallel to the keel, as when a ship sails close upon a wind.





P A R T II.

To turn a S H I P any way.

P R O P. VIII.

To render a Ship ready to turn easily any way.

1. **T**HE figure of a ship causing her naturally to present her head to the wind, makes it necessary to have a great proportion of sail forward, for the more readily wareing her.

2. Notwithstanding which, there are many vessels too ready to come to the wind, and unapt to ware; which fault may proceed from several different causes: 1. Some have their sterns too high built, and their poops serve as a sail abaft. 2. Others have their fore-mast set too far aft, which makes them less capable to resist the force which so readily carries them to windward. 3. Others are built too sharp a head, which is remedied by thickning the bows.

3. If a ship be too backward in coming to the wind, the fault is to be corrected by some opposite means.

4. Great care ought to be taken, that the rudder be well proportion'd to the ship, and that it be sufficiently exposed to the water that passes along the sides of the vessel.

5. When a ship is in a just equilibrium, and feels her helm as she ought, it is still no easy matter to keep her constant in her course, because of the uncertainty of the waves and wind; it is therefore necessary to take the following precautions, 1. The range of the ship from her course, ought in the very beginning to be broke, which a slight motion of the helm will then easily do.

2. When a ship is much yaw'd from her course, you must not bring her to it again at once, lest you throw her into a contrary sheer. 3. But if you should be obliged so to do, you must ease the helm before she be return'd to her course, to prevent the opposite sheer, which else the force of her way will be apt to run her into.

P R O P. IX.

To make a Ship fall off.

Let the vessel be A B, the head-sails D C, those of the main mast E F, the mizen G H, the line of the wind A N, N, M N, the rudder B R, the tiller B O. *Fig. 28.*

F 3

I. A

1. A vessel is said to ware, or fall off, when her head is thrust to leeward, or her stern to the wind (*Def. 6.*)

2. When a vessel has head-way, the tiller is to be put over to windward, that the rudder BR may present its self to the current of water to leeward, and so push up the point B to the wind, which cannot be done without making the head A fall off to leeward (*Prop. 1.*)

3. To ware the easier, hale up the mizen, that so the line of the wind NM, which thrusts the stern to leeward, may not impede the impulse of the rudder BR, in bringing up the stern to the wind.

4. Encrease the head-sails, and brace them in as sharp as possible to leeward, that they may have the more force to make the ship fall off (*Prop. 4.*)

5. Hale up the main sail, and shiver the main-top sail, in order to ease the ship's way, which will facilitate her turning; but take heed you lay not the main-top sail aback, which would perhaps give her stern-way, and so bring her again to the wind, especially as the rudder BR is to leeward.

6. Another way to ware a ship, is to brace in the head-sails as much as possible, to windward, that the wind A N may have the greater power, and that their direction being less inclined upon the keel, they may

may have more force to thrust the point A to leeward, and so make the vessel fall off. But this method is not practised without an absolute necessity, because it very much hinders a ship's way; and when other ships are in company, puts her in danger of falling foul of those which follow.

7. When this practice is made use of to avoid a danger, the main sail and mizen-top sail may be laid aback, in order to give the ship stern-way, and the helm should be put over to leeward, that it may not check her falling off. But skilful mariners take care not to shift the helm, before the ship begins to get stern-way.

P R O P. X.

To bring a Ship to the Wind.

To bring the Ship A B to the wind, that is, to turn her head to windward, *Fig. 30.* the following things are to be done.

1. Put over the tiller B O to leeward, that so the rudder B R meeting the current of water to windward, may force the stern B to leeward, which will consequently bring the head A to the wind (*Prop. 1.*)

2. Hale out the mizen G H, that the wind N M may force the stern M to leeward.

3. Diminish the head sails, by letting go the fore sheet, and setting in the weather braces.

F 4

4. Make

4. Make what sail you can on the main-mast, that the ship having more way, may the better answer her helm; and that the wind may have more force upon the mizen, and after-part of the ship. To explain myself,

The swifter the ship's motion is, 1. The water strikes the stronger against the rudder. 2. It pushes the stern of the ship with more force, 3. The wind has a greater effect upon the mizen, and after-part of the vessel, therefore the swiftness of a ship's motion helps the rudder every way in bringing her to the wind. But in falling off, as it helps on one hand, in striking stronger against the rudder; so it hinders on the other hand, by its force on the mizen, and stern of the ship, in pushing her after-part to leeward.

P R O P. XI.

To Tack with the Wind before the Beam.

To Tack, is to turn a ship that is close hal'd on one side, so that she may be the same on the other. To tack therefore with the wind before the beam, is to turn a ship so that she may still take the wind before.

Let therefore A B represent a ship, *Fig. 30.* which is to tack, 1. After having given her as much way as possible, right the helm, and hale out the mizen; then when the vessel begins to come to, put over the helm B O to leeward, and brace to the fore-top sail, that the windward part of the

the
(P)
wind
2.
and
sails
off.
3.
ward,
force
ase o
4.
ship l
ne w
force b
coming
5. F
nd Sh
st the
orce th
6. W
lift th
st set
eak th
* The
m's a
e-top
shake
n their
they f

the sail may lay aback, which as before remark'd
(*Prop. 4. 3.*) will help her to come to the
wind. *

2. Ease a little the fore-bowlines to windward,
and the fore-sheets to leeward, that so the head
sails may lose all power of making the ship fall
off.

3. The mizen may likewise be brac'd to lee-
ward, that the wind NM may have the more
force to bring her tq; but this is not done but in
case of necessity, because it deadens her way.

4. The head-sails are not to be shifted, till the
ship has pass'd some degrees beyond the line of
the wind, lest the wind NA should
force back her head A, and hinder her *Fig. 32.*
coming to.

5. For the same reason it is, that the bowlines
and sheets of the fore sails, are not entirely let go,
lest the sails should bag behind the mast, and so
force the ship's head to leeward.

6. When the ship is come enough about to
lift the sails; the mizen should be
first set, that so the wind NM may *Fig. 33.*
break the way she has in turning.

* The *English* practice in tacking is, as soon as the
ship's a lee, to let go the fore sheet, and not lay the
fore-top sail a-back, till the ship is so far come up as
to shake it; then laying it a-back, they tend it, and
haul their after-sails sharp, not easing their fore-bowlines
till they find the ship falls off too fast.

7. In filling the sails again, begin with the after-ones, if they cannot be all filled together; in order to make the most of the time in which the ship is falling off, to fill the head-sails. In this case the main sail, as soon as it shivers, should be immediately shifted.*

8. There is no fear that the wind A N, should make the ship fall off too much, since the braces D being eas'd, and the main sail being set, will bring her up again to the wind.

9. 'Tis not easy to tack a ship, only with her top sails, when the sea runs high, because they do not give a ship way enough to overcome the swell which beats on her bow; the courses are yet less sufficient, as giving her still less way, besides that the fore-sail when it takes aback, makes too much of a bag to windward of the mast, which will flat her off again.

10. If when a ship begins to come to the wind, her head-sails are brac'd to, though not exactly perpendicular to her keel, she will stay sooner, but will fall more a stern: On the contrary, if they are not brac'd, the ship will gain a head in staying, because the force of her way will sustain her against any contrary impulse im-

* Our way is always to brace about our after-sails, and keep the head-sails a-back till the after-sails are full, and then brace about the head sails; for a ship in tacking is frequently caught, or comes back again, if the head-sails are brac'd too soon.

press'd on her by those sails aback ; therefore when a ship is lively enough to stay, the head-sails are not brac'd to at all.

P R O P. XII.

To change the Board with the Wind abaft the Beam.

Suppose the vessel A B, were obliged to change her board with the wind *Fig. 34.* abaft the beam, either because she cannot bring the wind forward, or that for some particular reason she is obliged to change her board with the wind abaft the beam, and to take luff for luff.

1. Hale up the mizen, and put over the tiller O B to windward, then when the vessel has got lee-way, bring to the weather-braces, and in proportion as she falls off, continue to brace in, that so when the ship comes right into the direction of the wind, the sails may stand trim'd right before it.

2. When the ship's way has brought her beyond the line of the wind, hale out the mizen, that so with the rudder, which will then stand right for bringing her to the wind, it may continue to help the vessel to turn; continue likewise to brace in the sails, till they are brought close upon the wind. Then haling up again the mizen, shift the helm to break the force of her way to windward.

3. If when the mizen is hal'd up, and the helm shifted, she does not fall off; it may be effected by bracing in the sails as close as possible to windward. But as soon as ever the ship begins to get leeway, right the sails again to help her, left when she comes near the line

Fig. 35. of the wind, the wind N A should break the ship's way in turning.

4. Take care not to be too hasty in bracing the sails, when the ship begins to fall off, lest by some sudden motion the wind should take the sails aback.

P R O P. XIII.

To prevent the Accident, call'd building a Chapel.

A Ship is said to build a Chapel, when the wind taking her a head, forces her unexpectedly about. This accident is dangerous, because it may throw a ship in the way of another a stern of her, or upon other dangers.

1. Suppose the ship A B, take the
Fig. 36. wind a head, if she remains in that disposition, the wind N A falling upon the sail C D, will make the ship come to the wind till she passes the line of the wind, when striking her with still greater force, it will bring her stern to windward. To hinder which, put the helm over to windward, hale up the mizen, and brace the head-sails D C to the wind, till the angle C A B becomes a little acute, that so the wind N A

N A falling upon the sail DC, may thrust back the head A to leeward, and make the vessel fall off. Then when the ship has got leeway, right the sails DC again, and hale out the mizen, putting over the helm too to leeward, to prevent her falling off too much.

2. If the angle CAB be made very acute, the ship will fall off sooner, and force her less a stern. But then it may happen, that the ship has already turn'd so far that the sails DC may shiver, or even fill, which will render it impossible to prevent the accident. 'Tis therefore proper to brace the sails CD no more than is just necessary to flat the ship off.

3. Suppose the ship AB has all its sails a back, in order to fall a stern, if *Fig. 37.* after she has lost her head-way, the helm BO be put over to leeward, the water which strikes against the rudder when the ship begins to get stern-way, will throw up her stern B to the wind, and the wind NA will fling her head to leeward with so much force that nothing can stop her turning about. But this accident may easily be prevented, by bracing a little the sails DC to the wind, that is, by making the angle CAB a little acute, and putting the helm and mizen to bring her to the wind. Nor need it be feared that the vessel should come too much to the wind; for the sails CD will receive the wind NA more perpendicularly, as the ship gains to windward, and force her with the greater strength to leeward.

4. Many

4. Many skilful seamen make use of this practice when they found, because the ship then makes little or no way, and is not at all liable to build a chapel.

P R O P. XIV.

To lye to under the top Sails.

A ship is said to lye to, when her sails are so disposed, that producing contrary effects the one to the other, they render the ship as it were immoveable.

1. Let A B represent a ship, whose
Fig. 38. sails are so disposed, that the angles C A B, F A B, may be somewhat acute, the mizen G H being hal'd out, and the rudder B R to leeward. In this scituation, the head-sails will push the ship's head A, by the line N A, to leeward; and the after-sails G H, bearing her stern to leeward, by the line N M, will force up her head to windward: So likewise the sails D C, E F thrusting the ship a stern, and the sails H G bearing up a little a head, consequently as the ship cannot easily divide the water a stern, she will remain almost immoveable, making but very little way, and that a stern; for which reason the effect of the rudder B R will be to bring up the ship a little to the wind.

2. The lower sails being furl'd, and
Fig. 39. the top sails a little lower'd, brace in the fore-top sail D C till the angle C A B becomes a little acute, gaining a little at the

[111]

the same time to windward, that the fore-top sail may be taken aback, whilst the main-top sail is fill'd by bracing it in to leeward. In this scituation the ship is thrust a head, and to windward by the main-top sail, (*Prop.* 5. 4.) and a stern, and to leeward by the fore-top sail (*Prop.* 4. 2.) so that between both, she remains as it were immoveable.

3. If in this disposition the ship falls off too much, hale out the mizen, or make use of the mizen-top sail, and if notwithstanding all that, she still falls off, make the angle CAB less acute, and the angle CAN more acute, by bracing in the fore-top sail a little to leeward. There is no fear of her coming too much to the wind, because as she comes to windward, the sail DC will take the wind more directly, which will give it more power to flat her off. Thus a ship lies to most safely under a mizen; but then she is most liable to fall off.

4. The helm ought for the most part to be put over to leeward, since the vessel more commonly falls a stern than gains a head; for both the hull and rigging serve as a back sail.

5. A ship may lye to, with her fore-top sail DC fill'd, and her main-top sail EF a-back; and in this disposition she will not so easily fall off, because the sail DC keeps her closer to the wind, and has less force to flat her off. (*Prop.* 4. 3.) 2. The sail EF has more power to bring her to the wind (*Prop.* 5. 5.) Therefore this way of lying to, seems the most convenient for a fleet in a line of battle;

Fig. 40.

battle ; but as it puts a ship in greater danger of taking the wind a head, it is seldom used but in engagements, when it is of much more consequence not to fall to leeward, than to prevent the accident of taking the wind a head.

P R O P. XV.

To lye to under the Courses.

When on account of the violence of the wind, or the fear of danger, or of any other reason it is thought convenient to lye by: If then the ship cannot come to an anchor, nor lye to under her top sails, they then try under her courses ; that is (as before with her top sails) they so dispose her lower sails, that she may make little or no way.

1. The top sails being furl'd, and the lower sails trim'd close, keep as near the wind as possible, without hazard of taking the wind a head, that so the ship may make very little head-way, and only fall off in a line between the direction of the wind and the rumb of the course.

2. A ship will still make less way, if the main sail be likewise furl'd, and only the fore sail and mizen set, or the mizen alone.

3. Sometimes the main sail only is made use of, and then the ship will move only by jerks as it were, and fall too near the line of the wind. She will thus make but little way, but then she will labour very much. The rudder will be but of little service in this case ; but that the ship
may

may labour the less, let the helm be so put to leeward, that the rudder may be nearly parallel to her course.

4. Sometimes the wind blows so hard, that a ship cannot bear any sail. *Fig. 41.* In such case, having furl'd all the sails, and squar'd the lower yards, brace the top-sail yards in the same manner as if the sails were spread, and put the helm hard over to leeward. Thus shall the ship move as it were by jerks, most commonly presenting her side to the wind, because when she is pretty much fallen off, she gets head-way, and the rudder B R will bring her again to the wind, and when she has gain'd too much to windward, she will fall a stern, and the rudder B R will again throw her to leeward. If the helm be put over to windward, the rudder will bring the ship about, since if she be much fallen off, and has got head-way, the rudder will make her fall still more off; and if she comes too close to the wind, and falls a stern, the rudder will still bring her more to windward. From whence it follows, that by means of the rudder, a ship may be turn'd, though she has not a single sail spread.

5. If when a vessel is thus only driving with her masts and yards, it is thought proper to let her go before the wind, when the ship comes into the line of the wind, right the helm, and manage it altogether the same as if the vessel were under sail, for in such hard gales especially, the hull and rigging are in effect a sail. And thus driving before the wind, a ship will sometimes make such great way, that she may run much

much hazard of being lost, if she hath not sufficient sea room.

P R O P. XVI.

To govern a Ship with the Yards.

1. It is easy to govern a Ship with the sails, since some of them serve to make her fall off, and others to bring her to the wind; and since the yards serve in some degree as sails, a ship may in like manner be govern'd with her yards.

2. When in fine weather it is thought convenient to change the place of a ship's riding, in a road where there are many other vessels; unfurl the mizen, and mizen-top sail, and in weighing the anchor, let the yards be brac'd as much as possible opposite to the place where the ship is to fall. Then when the anchor is up, and the ship sufficiently fallen off to take the proper direction, set the yards in all respects as if the sails were spread; If the ship comes too much to the wind, hale up the mizen, and brace the fore yards close in to windward. If she falls off too much, hale out the mizen and mizen-top sail. If the ship has too much head-way, check her by laying the mizen-top sail a-back. If she has too little head-way, increase it by assistance of the mizen and mizen-top sail. In this manner you may traverse a road as you please, and moor a ship just where you have a mind. But for the greater security, they commonly send out a boat with a small anchor, in case of a calm or a contrary wind.

R E M A R K.

R E M A R K.

Many other common practices in the working of a ship might be added to these above explain'd ; but as they have nothing particular to be accounted for, I shall pass them over, that I may not tire my reader with tedious repetitions.



PART



P A R T III.

Of sailing from one Place to another at a distance.

P R O P. XVII.

To come to sail.

1. **A**T a proper time to go to sea, having unmoor'd your ship, in heaving up to your other anchor, steer your ship right with the anchor, and having recover'd the buoy and brought your ship a peek, loose your top sails, and set them, bracing the main yard and main-top sail up sharp, and your fore-top sail a-back, to flat her off to that side you would cast her; at the same time haling out the mizen to bring her the more readily to again; in this manner if you have nothing to oblige you to make sail, keep her till your anchor is stow'd, when you may wear her to her course, and then make use of what sails you think proper.

2. If in bad weather you are oblig'd to come to sail, and in doing it, are in danger of falling upon

upon some rock as A, carry out a small anchor on that bow your danger lies, *Fig. 42.* and bring the hawser in abaft on the same quarter, and make him fast, which having done, vere away the cable D, till the ship is fallen off so far as that you may serve your self with such sails as are proper for the weather, which, when you can do, cut away your cable and hawser.

3. If time and weather will permit, it would be better to carry an anchor farther out a head, after having hove in as much as may be on the anchor down, and come to sail from the anchor so carried out, from whence you will probably have room to cast.

4. When the weather permits you not to come to sail with the top sails, you may with the fore sail and mizen.

5. When you are obliged to cut, in order the more readily to come to sail, be sure you do it not till your top sails are hoisted, and brac'd for casting, lest you fall to leeward, and lose more time than if you had hove up your anchor. Remember also to leave a buoy on the end of the cable, that you may take it up again if opportunity offers.

P R O P. XVIII.

Of gaining as much as may be to windward.

1. If a ship had as much difficulty to divide the water with her head, as with her sides, as would

Fig. 43. would be the case were she round, she could then no way gain to windward. For let the ship be A, the line of the wind BA, the perpendicular to the wind CA, the sail DA, its direction AE. If the vessel A were round, she would continually keep the direction AE of the sail, and consequently fall off from the line AC; which is called falling to leeward or making lee-way (*Def. 4.*)

2. If on the contrary, a ship could not at all divide the water with her sides; but always kept the line she looks in, without making any lee-way, she would continually gain to windward when she looks above the line AC, as in the line AF, and what she gains to windward will be measured by FG, the sign of the angle FAG, provided her absolute motion be measured by the line FA. That is to say, the product of the sign of the angle FAG by FA, the sign of the angle FEA, or FAD, will always be what the ship gains to windward in the course FA. But this product will always be greatest when the two signs are equal; therefore the ship A will always gain most to windward when the line FA, divides the angle CAD into two equal parts.

Or, if you like better so to express it, the point F in the middle of the arch AFC, is the most distant point from AC, or more to windward than any other point as H, in the same arch; and moreover the ship will arrive as soon at the point F, as at the point H. (*Prop. 2. 7.*) Therefore she will gain most to windward, when her course AF, equally divides the arch AFC or the angle DAC.

3. Lee-way makes no alteration in this rule; for if a ship making lee-way, shall only arrive at the point I, in the line FE, in looking up to the point F; in looking up to the point H, she shall only reach the point K, of the line HE; and the lines FH, IK, shall be parallel (by *Prop. 1. 7.*) Therefore if F is to windward of H, I shall be to windward of K (by *Def. 4.*)

4. Let us go on supposing the ship to make no lee-way; draw BD, the sign of the angle BAD, which the scituation of *Fig. 44.* the sail makes with the wind. Since the signs DB are to one another, as the roots of the impulsions of the wind upon the sail (by *Sup. 8.*) in its different scituations; and that the different velocities of a ship's sailing are also to one another, as the roots of the same impulsions (by *Sup. 7.*) the different velocities of sailing shall be to one another, in the different scituation of the sail, as the sign DB; and consequently the velocity of a ship may always be express'd by the sign DB, in supposing the sign total to express the velocity of a ship sailing before the wind. Make then AE equal to DB; and having describ'd the semicircle ACE, from the center H draw HF perpendicular to AC, which shall divide the arch AFC equally in the point F (by *Euc. 1. 3.*) and cut the line AC in the point G. But the line AF is the most advantageous course for the ship to gain to windward in the scituation of the sail DAB (by the prec.) therefore the line FG shall be all that the ship is able to gain to windward in the scituation DAB. Upon which we may make the following reflections,

1. If

1. If the angle DAB is just 30 degrees, FG shall be exactly $\frac{1}{8}$ of radius.

Demonst. DB , or AE being the sign of 30 degrees, will be $\frac{1}{2}$ the radius, and since all the angles of the triangle HAF are of 60 degrees, FA will be equal to AH , or $\frac{1}{4}$ of radius. But FG being the sign of 30 degrees, will be the half of AF ; it will therefore be $\frac{1}{8}$ of radius.

2. If the angle DAB be more than 30 degrees, FG will be less than $\frac{1}{8}$ of radius. Let us call d the difference between the sign of 30 degrees, and the sign DB , which we suppose greater.

Demonst. AE being equal to $\frac{1}{2}$ radius with d , and consequently HF being equal to $\frac{1}{4}$ of radius, and $\frac{1}{4} d$. Moreover HG being the sign of above 30 degrees, will be equal to the $\frac{1}{4}$ of HA , or $\frac{1}{8}$ of radius, and $\frac{1}{4}$ of d , and besides of a magnitude which will be to d , as AH to the sign total, or more than its fourth; therefore HG shall be more than $\frac{1}{8}$ of radius, and $\frac{1}{4}$ of d , and consequently if it be subtracted from HF , the remainder FG will be less than $\frac{1}{8}$ of radius.

3. If the angle DAB be less than 30 degrees, FG will be less than $\frac{1}{8}$ of radius. Let us again call d the difference between the sign of 30 degrees, and the sign DB which we suppose less.

Demonst. HF will be $\frac{1}{4}$ of radius less $\frac{1}{4} d$. Moreover HG will be $\frac{1}{4}$ of AH less a magnitude, which will be to d as HA to radius; that is to say, less than its fourth; therefore AG will be equal

equal to more than the $\frac{1}{2}$ of AH less $\frac{1}{4}$ of d , or will be equal to more than $\frac{1}{3}$ of radius, less $\frac{1}{4}$ of d , and consequently if it be subtracted from FH , the remainder will be less than $\frac{1}{3}$ of radius.

C O R O L L A R Y.

From whence it follows, that if the ship makes no lee-way, the situation DAB , the most advantageous to gain to windward, ought to be just 30 degrees.

5. To find what alteration *lee-way* will make in this rule. Draw EL , and HM , parallel to CA , and continue FG , till it meets EL , in the point L . Again, draw CE , in proportion to EA , as DB to BA . Then supposing EI to FE , as the difficulty of the ship's dividing the water by her head, to that of dividing it by her side; and as any magnitude d (which we call *lee-way*) is to the sign total. Lastly, supposing EK parallel to CA , in the situation DAB of the sail with the wind, the line FG less FK , will be what the ship gains to windward, knowing therefore FK , her advance to windward may be known; for FG is easily known as above explain'd. Thus therefore may be found FK . Since the angle CAB is equal to the angle DAB , the sign total AB , is to DB , as AE equal to DB , is to CE , which by this means will be known; and consequently FL may be found; which is the half of CE , and the half of AE . Therefore since $EF : EI :: LF : LK$, EK is consequently discovered.

COROLLARY.

As it may be known what a ship gains to windward in every scituation of the sail, it will be found that the most advantageous scituation for that purpose, is when it makes the sign DB, equal to half the radius, less a magnitude or quantity, which is to the sign total; as the lee-way Δ , is to the sign total more the lee-way Δ . For in augmenting or diminishing ever so little this scituation, GK will be found less.

LEMMA.

If A being greater than B, does not exceed more than B does C, the square of B shall be greater than the product of A into C (by *Euch. 16. 6.*) Since A will have a lesser ratio to B, than B to C.

PROP. XIX.

To find the most advantageous scituation of a Sail for a Course given, when a Ship makes no lee way.

1. Let AB be the line of the wind
Fig. 45. AF the course, and DA the sail. Draw AE perpendicular to the sail, and equal to the sign of the angle DAB, and upon AE describe a semi-circle cutting the course AF in the point F, so shall AF be the velocity of the ship, in the scituation of the sail DAB.

2. The

2. The angle EEA being equal to the angle FAD ; the sign total will always be to the line AE the sign of the angle DAB ; as the sign of the angle FAD , to the line AF ; and consequently, the product of the sign DAB by the sign FAD , being divided by the sign total, will give the velocity AF .

3. This product will always be greatest when the two angles DAB , FAD are equal (by *Lemma*, prec.) since in augmenting the one, its sign is only increased, in proportion as the other is diminished; so that the velocity of the ship is always greatest, when the sail AD divides the angle FAB of the course with the wind, into two equal parts.

R E M A R K.

This rule then serves for gaining the most that may be to windward in a given course, when a ship is supposed to make no lee-way; because in that case to go most swift, is the same thing as to gain most to windward. This rule therefore is of great service in practice, since lee-way is very often insensible.

P R O P. XX.

Of the alteration in Velocity, which lee-way will cause in the foregoing Proposition.

1. If AF be the rumb line upon which the ship ought to sail, the sail *Fig. 45.*
shall be still in the most advantageous

scituation for velocity upon such rumb, when it equally divides the angle FAB .

Demonst. Let us suppose the sail to divide the angle FAB unequally, then if the vessel having no lee-way, would arrive but at the point H , in the time she would have got to the point F ; (by the prec.) with lee-way she will only obtain the point K of the perpendicular HI , in the time she would have come to the point G of the perpendicular FE .

2. If the ship keeping the rumb AF , is carried by her lee-way to the point G of the perpendicular FE , when the sail equally divides the angle FAB ; the angle DAB cannot be augmented without retarding the ship's arrival at the point G .

Demonst. If the angle DAB be augmented, and the ship keeps the same rumb AF , she will come but to the line HI , in the time she would have got to the line FE ; but as her lee-way would carry her on in a line below the line AG , it is therefore necessary she should run more to windward, for which reason at the time she should have gain'd the line FE , she will be found in a line still nearer the point A , than the line HI , and consequently will only arrive at some point nearer A , than the point K , at the time she should have arrived at the point G .

3. If the angle DAB be diminished, the ship will then sooner arrive at the point G , and it will be easy to find the velocity AG in every position of the sail. For the sign total will always be to the

the sign of the angle DAB ; as the sign of the angle FAE the complement of FAD , to FE ; therefore FE may be known, and consequently FG , which is to FE , as the lee-way, to the sign total. Farther, the angle GAF may be known, for the tangent of the angle EAF , is to the tangent of the angle GAF , as EF to GF . Lastly, AG may be found, for the sign of the angle GAF , is to GF ; as the sign total to AG .

C O R O L L A R Y.

The angle DAB which shall be the most advantageous, may be found by a trigonometrical calculation, that is, such an angle as cannot be augmented or diminished, without lessening AG . For example, suppose it were requir'd to find the most advantageous scituation of the sail for a ship, whose lee-way is to the sign total, as 1 to 10, and is to keep the course AG , making an angle GAB with the wind of 100 degrees. I begin by supposing that the angle DAF ought to be 51 degrees, that is a little more than half the angle GAB . Its complement FAE will be 39 degrees, subtract the logarithm of 10 from the logarithm of the tangent of 39 degrees, and the remainder will be the logarithm of the tangent of the angle GAF , which will be 4 degrees 38'; this added to the angle FAD , gives $55^{\circ} 38'$ for the angle GAD ; and consequently the angle DAB will be $44^{\circ} 22'$. Add the logarithm of $44^{\circ} 22'$ to the logarithm of 39° and from the sum subtract the logarithm of the sign total, the remainder will be the logarithm of FE , from which must be taken the logarithm of 10 to get the logarithm of FG . Then adding the

G 3

loga-

logarithm of the sign total to that of FG, and subtracting from the sum the logarithm of the angle GAF, the remainder will be the logarithm of the velocity GA, for the scituation which makes the angle DAB $44^{\circ} 22'$.

9.908369 Log. Tan. 39 degrees

1.000000 Log. 10

8.908369 Log. Tan. 4 deg. 38'

9.79887 Log. Sine 39 degrees

9.84463 Log. Sine 44 deg. 22'

15.64350

10.00000

9.64350 Log. FE

1.00000

8.64350 Log. FG

10.00000

18.64350

8.90692 Log. 4 deg. 38'

9.73658 Log. AG

Do the same in augmenting, or diminishing the angle DAF till it cannot be more increas'd or diminished, without lessening the velocity AG, and you will obtain the most advantageous scituation.

After this manner the following table is made, and so may be calculated for every possible case.

A Table

A Table of the Scituation of the Sail for the several Courses therein given.

Angle of the Wind with the course given	Lee-way					
	$\frac{1}{3}$		$\frac{1}{6}$		$\frac{1}{2}$	
	Angle of the Wind with the Course to be kept	Angle of the Wind with the Sail	Angle of the Wind with the Course to be kept	Angle of the Wind with the Sail	Angle of the Wind with the Course to be kept	Angle of the Wind with the Sail
Degr.	Degrees	Degr.	Degrees	Degr.	Degrees	Degr.
170	169	84	170	85	170	85
160	158	79	159	79	160	80
150	147	73	148	74	149	74
140	135	66	138	67	139	69
130	124	60	127	62	129	64
120	113	54	117	57	118	58
110	102	48	106	51	108	52
100	90	41	95	45	98	47
90	79	33	84	39	87	41
80	67	26	73	34	77	35
70	55	18	62	27	66	31

P R O P. XXI.

Of the alteration which Lee-way will make in the foregoing Propositions, when a ship is to gain more to windward.

1. If the course be determined, there will be no alteration in the last proposition.

2. If only the rumb line $A F$ be determined, the angle $D A B$ must not be greater than half the angle $F A B$.

Demonst. The angle $D A B$ being above the half of $F A B$, the ship would only gain the point L , in the time she should have got to the point G , if the angle $D A B$ had been but half the angle $F A B$ (by the prec.) which point G , must always be to windward of the point L , since if it be required to gain to windward, the angle $F A B$ must be acute.

3. In making the angle $D A B$ less than half of $F A B$, the ship will gain to windward, since the angle of the lee-way becoming less, the ship may arrive at the point N , in the time she would have come to G , if the angle $D A B$ had been half of $F A B$.

4. It is easy to determine what a ship gains to windward upon every situation of the sail; for having drawn the perpendicular $G M$ upon $A B$, the line $M A$ will be the ship's gain to windward; and the sign total will always be to $A G$, as the sign of the angle $M G A$ the complement of $G A B$, to the line $A M$.

Corol. The most advantageous situation of the sail for gaining to windward, may therefore be also found, and thrown into tables serving every possible case, as in that which follows.

A

A Table of the Scituation of the Sail for gaining to Windward upon the several Rumb Lines therein given.

Lee-way	$\frac{1}{3}$	$\frac{1}{10}$	$\frac{1}{10}$
Angle of the given Rumb with the Wind	Angle of the Sail with the Wind	Angle of the Sail with the Wind	Angle of the Sail with the Wind
Degrees	Degrees	Degrees	Degrees
85	0		19
80	16	20	24
75	18	21	33
70	20	23	31
65	23	26	30
60	22	25	26

G 5

PROP.

P R O P. XXII.

To find the proper Rumb a Ship should keep, in sailing from one fix'd Place to another.

1. If the vessel has no lee-way, let her head point directly to the place she is to sail to.

2. When a ship has lee-way, turn her head to windward of the point she is to make, in the following manner. Suppose the ship *Fig. 47.* A, the line of the wind B A, the point she is to sail to, C; then must the ship range upon some other line as A D, and there will be two ways of observing whether she makes too much or too little to windward. 1. Take notice of some object as E, which answers directly with the point C, and if when the ship has sailed some length, the object still continues to answer directly with the point C, it is plain the ship keeps the line A C E, and will run directly upon the point C. But if after some time sailing, the object E opens to windward of the point C, you may be sure the ship's head points too much to windward, and that the ship will run to windward of the point C, unless she falls off a little. If the object E opens to leeward of the point C, then 'tis certain the ship falls off too much, and will not weather the point C. 2. Set the point C by the compass, and if after some time sailing, the point C continues to bear the same, the ship then keeps the right course; but if the point C falls to lee-ward, the ship runs too much to windward; on the contrary, if the point

point C appears more to windward, the ship then falls off too much.

3. In the same manner it may be known whether a ship will double a Cape; or whether she will gain to windward, or fall to leeward of another ship riding at anchor, &c.

P R O P. XXIII.

To find the proper Course for chasing a Vessel to Leeward.

Suppose the ship A were to chase the ship B, and FA the line of the wind. Fig. 48.

1. If the ship A were to bear right down upon the ship B, she would describe, in approaching her, a curve line, till she falls into her wake, and would run a hazard of not coming up with her at all; both as she would have more way to run, and would lose the advantage of the wind.

2. The ship A must then look to windward of the ship B, and range upon some line as AB, wherein she may come up with the ship B at the point E. But to know that line, it must be considered, that if the vessel A comes up with the vessel B at the point E, she must run through the line AE, in the same time that the vessel B is running through the line BE; and consequently imagining the lines CD parallels to AB, to cut the lines AE, and BE, into proportional Parts, (by 2. 6. of *Eucl.*) the two ships will arrive at the same time upon each of these parallels, and consequently with regard to each other, will con-

tinue on the same rumb, as when they were on the line A B.

3. It is then easy to know, if the line A E, upon which the ship A ranges, is a proper course for meeting the ship B at the point E, by repeatedly setting the ship B by the compass, at little intervals of time. For if the same bearing continues, it is a certain sign the two ships arrive at the same time upon each of the lines C D, and will consequently meet at E; but if after some time, the ship B falls to leeward, it may be concluded that the ship A keeps too much to windward; on the contrary, if the ship B is found more to windward, after having made a small run, it shews that the ship A falls off too much, and must keep closer to the wind, not to fall to leeward of the ship B.

R E M A R K S.

1. Though the ships A and B sail equally well, yet if the ship B continues sailing close upon the wind in the line E E, the ship A, which is to windward, may come up with her by some other line as A E. Since the ship A sailing with a larger wind will run swifter, and may therefore run through the lines A C, while the ship B is running thro' the lines B D.

2. In like manner the ship A may come up with the ship B, by many different lines, if in falling off, she increases her velocity in the same ratio as the lines A C.

P R O P.

P R O P. XXIV.

To find the proper Course for a Ship to cut, or cross the Way of another, to windward of her.

1. The ship A being to leeward of the ship B, may possibly be so good a *Fig. 49.* sailer, that in tacking on any line as A E, she may run through the parts A C, while the ship B is running through the correspondent parts B D, and consequently come up with her at the point E. Whether A E be the proper line, may be tried as before, by frequently setting the ship B by the compass; for if she be found still to bear upon the same point, it shews the two ships answer each other by the parallels C D, and that they will meet at the point E. But if the ship B falls to leeward, the ship A keeps too much of the wind; on the contrary, if the ship B gains to windward, the ship A falls off too much; and therefore if she can lay no nearer, she will not be at all able to cut or cross the way of the ship B.

P R O P. XXV.

To find the Point where a Ship ought to Tack, to cut or cross another to windward of her.

1. If the two Ships A and B, sail with equal velocity, they cannot cut or *Fig. 50.* cross each other, unless one be to windward of the other.

2. If

2. If the ship A, which is to leeward, out-tails the ship B, she may cross the other before she gains the wind, and the point where she is to make her tack for that purpose, may be determined, if the time she would take up in running through a line equal to the space between them, is nearly known, as thus;

3. Suppose the ship A is to run the course AD, and the ship B to run the course BE, parallel to AD; and that the time the ship A would take to run thro' a space equal to the distance AB of the two courses, were nearly known. Observe the time which has past since the ship A answer'd to the ship B, by the line AB perpendicular to the courses, and that wherein she answers by the line CH, which makes the angle HCA 45 degrees; and from that time, subtract the time the ship would have taken in running through a line equal to AB, then will the root of double the square of the remainder, be the time that the Ship A should continue on her course from the point C, before she makes her tack to cross the course of the ship B. Continue AB, and CH, till they meet in the point G; and make CD, HE, equal to GH; then draw DG, which shall cut HE, in the point I; lastly, compleat the parallelogram GCDI, and draw HL parallel to BA.

I say, 1. That the point D, shall be the point where the ship A ought to tack, according to the rule given.

Demonst. Since in the rectangled triangle CAG, the angle C is 45 degrees, it will be equal

equal to the angle G , and the lines AC , AG , will be equal; as also BH , BG ; and CL , LH , or AB . Then since from the time that the ship has taken to run through the line AC , the time she would have taken to run through the line AB , or CL is taken; the remainder will be the time she has taken in running through the line LA , or HB ; and the root of its square doubled, will be the time she must take up in running through GH , or CD : and consequently the point D , must be the point where the ship A must tack, according to the rule given.

I say, secondly, That the ship A , tacking at the point D , shall meet the ship B , in the point E .

Demonst. $CD : HI :: CG : HG$, or $CA : HB$; then since the ship A has run through the line AC , while the ship B has been running through the line BH ; she will run through the line CD , while the ship B runs through the line HI . Likewise since $DE : EI :: DF : FG$, or CG , or $CA : BH$, the ship A shall run through the line DE , while the ship B runs through IE , and both shall come at the same time to the point E .

4. It is plain enough, that in practice the ship A should run something beyond the point D , by reason she will lose some time in tacking.

P A O P.

P R O P. XXV.

Remarks upon giving Chace.

1. If the distance A B between the
Fig. 50. courses of the two ships is small, it
will be best for the ship A. to hold on
her course, till in tacking she can cut the other.

2. If the distance A B is very great, the ship A
ought not to stand so far on one tack, as in chang-
ing her board to expect to cut the ship B, lest
she should run too far, and so the ship B escape,
either by being favoured by the wind, or imper-
ceiveably making some alteration in her course.

3. Neither ought a ship to tack, every time
she shall see the ship she chases about, by reason
of the time she will thereby lose.

4. I think it may be laid down for a general
rule, *always to tack upon the vessel in chase*:
that is to say, that the ship A ought not to tack,
till the ship B is fix'd in her course after tacking,
by which means she will never be distanc'd from
the ship in chase; and if the wind does not shift,
will probably fetch her upon the second tack; or
if the wind does shift, if to her advantage, she
will be ready to reap the benefit of it; or if on
the contrary, she will be the readier to recover the
disadvantage.

5. In regard to the ship that is chased, she
ought, 1. To make the best of the inadvertencies
of her adversary; she should often change her
course,

course, and keep to that she finds most to her advantage; that is to say, that which distances her most from her enemy: 2. Not to be too solicitous to keep close upon the wind, if she sails better with a large wind; for as the wind often changes during a chase, she may possibly find herself to leeward, by keeping the wind too close. 3. Above all things avoid keeping up to the wind, when you are very much to leeward of your enemy; on the contrary, go a little more large away than he, unless he steers directly down upon you, for in that case you must ply to windward.

P R O P. XXVI.

Of boarding a Ship.

1. If the vessel you would lay aboard be at anchor, you may anchor on his buoy, and veer away your cable till you fall aboard him; but then too he may cut away, and so you may lose your labour.

2. Neither would I advise the furling your sails in falling aboard him; because it will be easy for him to keep you off with his booms and boats.

3. This way then I would prefer. First, I would get my sprit-sail yard fore and aft, then with my top sails a trip, I would lay him aboard on the bow. In this manner I should have more time and means to grapple him fast.

4. If the ship you would board is under sail, and keeps her wind, it would be best then too, to board her on the bow, but it must be to windward,

ward, else she may easily avoid you, by keeping her wind close: If in the instant you lay her aboard, she wares from you, you must ware after her, or she will shoot a head of you, which if you cannot avoid, be sure you keep the weather-gage of her, for the next opportunity of boarding.

5. If the ship you would board, goes before the wind, and you can out sail her, range up along her side, before you sheer aboard her.

6. When your Ship is under sail, you may easily avoid being boarded. For 1. If the enemy would board you on your bow to windward, you may ware short round; and if the enemy wares too, you may take luff for luff, which will infallibly put her to leeward of you; if the enemy keeps the wind, wait till she has past you a stern, and then tack again to the wind upon the same board you were before, which will entirely prevent his boarding you. 2. If he would board you on your bow to leeward, keep as close as possible to the wind, so shall the wind of your ship support you, and becalm him, which will consequently make him fall to leeward, and a stern. 3. If your enemy would board you on the poop, it will be easy to avoid it, by giving your ship ever so small a sheer the contrary way.

7. If two ships friends, come with a large wind one against the other, they may avoid running foul, if the one falls off ever so little, while the other keeps her wind; but if one is close upon a wind, the other ought to fall off, because a ship close haled is not always so ready to ware.

8. If

8. If a ship is coming a thwart you a head, you may avoid it, by laying all your sails aback, if you are to leeward, but if you are to windward, she ought to ware short.

9. If in sailing on a wind in a line of battle, the ship A a-head be taken at *Fig. 51.* stays, she will be in danger of falling aboard the ship B which follows; in this case the ship B must not put to stays for fear of falling on a third, and unless she wares a great deal, so as to run out of her line, she will only bear up into the other's way, by the line B D; she should therefore luff up, even to touching into the wind, from whence these two things will follow, 1. The ship B will lessen her way. 2. She will get out of the line in which the ship A falls, by keeping the line B F.

10. If the ship A being at anchor, is like to be run aboard by the ship B, *Fig. 52.* the ship B ought to ware short round; but if they are obstinate and will not, the ship A ought immediately to veer away her cable. If the ship coming on the ship A, be close on her wind as C, she ought speedily to lay all aback, unless she is so much to windward as D, for then she ought to keep as much of her wind as possible, so as not to shake all her sails, lest in laying aback she drive foul of the ship A.

11. If in a calm the current throws the ship B upon the ship A at anchor, *Fig. 53.* the ship B must be tow'd a stern with boats; unless she be so far advanc'd a thwart her, that it would be easier to tow her clear a head.

12. If

12. If the ship A at anchor, drives
Fig. 54. upon the ship B likewise at anchor,
 they must both veer out cable, for it
 is the only means to bring him up that drives ; it
 will be also proper for him to carry out another
 anchor.

13. If the ship A drives, and the
Fig. 55. current CD throws her upon the ship
 B at anchor, where the channel is of a
 sufficient breadth, the ship A must veer out cable,
 and back her mizen-top-sail, to make her fall
 towards E, till her anchor takes, or she falls be-
 yond the ship B. In this case, as the cables will
 probably cross each other, one must cut, or veer
 it quite out, with a buoy at the end.

14. There may be many other circumstances
 with relation to the boarding of ships, which
 might perhaps require particular rules ; however,
 these laid down, will sufficiently lead to whatever
 else may occur in practice.

P R O P. XXVII.

Of running into Land.

1. If you are obliged to run in upon an un-
 known coast, make as little sail as possible, sending
 out your boats to sound a head, and at the same
 time keep the lead going on both sides aboard ;
 when you think you have a good birth for anchor-
 ing, brace too to give time for the boats to sound
 all about ; you may then if you find the place
 convenient, anchor, but not moor, till you have
 better

better examined it, sounding all around, and setting the neighbouring capes, to know if you have safe riding. Lastly, if you have time, make yourself perfectly acquainted with the place, and lay down a plan thereof.

2. If you are acquainted with the land you are running into, set the head-lands you know, to find the exact point where you are, then running in with small sail, observe the proper marks which lead you to good anchorage.

P R O P. XXVIII.

To bring a Ship to an Anchor.

1. In fine weather, drawing near your anchoring-place, get your anchor clear, and your buoy ready to stream, also take a range with the cable about the bits, in proportion to the depth of water you are to anchor in ; at the same time furl your main-sail, hale up your fore-sail, and lower a little your top-sail yards. Lastly, when you are come to your anchoring-place, hale out the mizen to bring up the ship to the wind, then clewing up one of the top-sails, brace too the other to stop her way, which when she has wholly lost, and begins to fall, let go your anchor, and veer away the cable till your anchor is a ground, which if you have any wind, and the ship will fall, keep still veering, till you have as much out as you think proper ; if the ship will not easily fall a stern, you may help her with the mizen-top-sail aback.

2. If there be any currents against the course, you must not hale up all your sails till at the place

of
†

of anchorage, otherwise the currents will soon carry the ship away again.

3. You may also in fair weather, come to an anchor with all your sails abroad ; laying all aback to stop the ship's way the moment before you come to. But this is not so convenient, unless you have a great many hands to furl all at once.

4. In bad weather, it is most proper to come to with the fore-sail only ; by bracing which aback, you may stop the ship's way. 2. In such case, take two turns with your cable about the bits. 3. Let go the weather anchor, lest the vessel in falling should rub the cable against her cut-water. 4. Veer away a great scope of cable to ride her.

P A R T. XXIX.

To Moor.

1. In places where the tides are commonly stronger than the winds, you moor according to the set of the tides ; that is to say, if the tides set east and west, your anchors ought to lie east and west.

2. Ships generally moor with a large anchor and a less, commonly the small bower ; giving the greater scope of cable to the best anchor ; which is always laid where the most danger is expected.

3. In places where the tides are very small, and the winds generally strong, you should moor in a line perpendicular to the wind, that so both your cables

cables may bear alike; which cannot be done in a tide, where there are two motions entirely opposite.

4. Most commonly the anchor you moor with, is carried out with the boat, and so drop'd as to answer right with the larger anchor a head; but if it be necessary, by reason of bad weather, to moor with too large anchors, after having let go your first, carry out a small anchor in your boat, something farther than you design to let drop the second, and heave your ship by the said small anchor, till you come to the proper place to let go the second. In this case there should be but a small range of cable allowed to the second anchor, lest falling all at once to the ground, it should break or bend; but biting it short, pay out the cable gently, as you recover that of the first anchor.

5. In fair weather, coming to an anchor, you may moor in this manner: Haul up your courses, and take in the main-top-sail, then letting go your anchor without biting it, and with a good range, pay out the cable very fast, and shoot your ship over with the fore-top-sail, till you are where you would let go the other anchor, which do with the former precautions; after which as before, heave in the cable of the first anchor, as you veer out this.

6. Where you have strong tides, 'tis very easy to moor, by veering away your cable upon the strength of the tide, till it is proper to let go the other anchor; then in heaving in the first cable, you veer away the second.

R E-

†












R E M A R K S.


1. The reasons of several of the rules above given are omitted, because they are self evident.


2. Many things too I have let pass, that I might not run this Tract into too great a length, besides, that for the most part, those things which are omitted, are such as will be easily learn'd in practice, tho' very difficult to be explain'd.


3. Those operations which depend more immediately on Mechanicks, may serve as corollaries to the Tract upon that subject.

Before we proceed to the Explanation of Terms used in this Work, I must desire the Reader to observe what was said in prop. 4. that the head-sails hinder a ship from yawing, is not to be understood, as if you were to increase the head-sails; that she might yaw less; it being certain, a ship fetches the greater sheers, the greater way she has thro' the water. It is therefore only meant, that the head sails correct the yaws a ship will necessarily take in a sea; so that if a ship were thrust forward in a certain velocity by her after-sails, she would sheer more, than if thrust on with the same velocity by her head-sails only. So also in 4. of the same proposition, when it is said the head-sails bring a ship to, it is to be understood as there explained, for the head-sails being aback, flat her off from the wind.











AN ALPHABETICAL
EXPLANATION
OF SUCH
NAVAL TERMS

A S

occur in the foregoing TRACTS; or
are occasionally used in this, for the
Explanation of others.

A



FT, or A B A FT; is a sea-term
to distinguish between things done,
or plac'd from-wards the stern or fore
part of a ship, towards the stern, or
hind-part: As when they say, come
or go *ast*; that is, go towards the stern.
aul the sheet *ast*: The mast hangs *ast*; that is,
wards the stern.
Astward; the hinder part of the ship.

H

ALTI.

ALTITUDE of the sun, or a star. Height above the horizon.

ANCHOR, is a massive iron, which being cast into the sea or river, by sticking fast in the ground, prevents a ship's being carried away with the wind or current. It consists of a shank or beam, with flocks at one end to enter the ground, and a stock of wood at the other, serving to guide the flocks; it has also a ring, by which it is fastened to the cable.

There are several sorts of *anchors*, differing only in weight, which is according to the burden of the ship.

Sheet-anchor, is the greatest of all that belong to a ship, and is never used but in great necessity, as being their utmost refuge, when forc'd to ride on a lee-shore.

Bow anchor, *first* and *second bower*, or *best* and *small bower*, are such as the ship in fair weather may ride by.

Kedge-anchor, or *kedger*, used in calm weather in a low stream, or to kedge up and down a narrow river, lest the wind or tide should drive the ship ashore. See **KEDGING**.

Grapples, or *Grapplings*; are the smallest of all the *anchors*; they have four flocks, but no stock. Their use is for a boat to ride by; or to throw into an enemy's ship in a close engagement, to catch hold of the gratings, rails, &c. in order for boarding her.

To ride at anchor, is said of a ship which is held fast by her *anchors*, so as not to be driven with either wind or tide.

To cast or drop anchor, is to let it fall, to stop the course of the ship.

To weigh anchor, is to get it up, in order to set sail.

To shoe an anchor, is to put boards fitted for that purpose, on the flook, that the anchor may the better hold in soft ground.

The anchor is foul ; that is, the cable is hitch'd about the flook, by the turning about of the ship.

The anchor is come home, is said when it does not hold the ship, but that she drives away by the violence of the wind or tide.

The anchor is a-peek ; that is, the anchor is right under the hawse (or hole) through which the cable belonging to that anchor runs out.

The anchor is a cock-bell ; that is, hangs right up and down by the side of the ship, ready to be dropt.

Padding of the anchor, are those ropes which are wound round the ring, to save the clinch of the cable from being gaul'd by the iron.

B

BEAK, or *Beak head* ; is that ornamental projection at the head of a ship, supported by the cut-water.

BEAM. The *beams* are those great cross timbers, which keep the ship's sides asunder, and support the decks. The *main-beam* or *midship-beam*, or, as it is called by way of eminence, The *Beam*, is that next the main-mast, and is the measure of the ship's breadth.

BEAR, is a word us'd at sea in various senses, as in the following instances:

Bear up; that is, let the ship fall more before the wind.

Bear up round; that is, put her right before the wind.

Bears in with the land or harbour; that is, the ship falls towards the shoar or harbour, with the wind large or before it.

Bears off; that is, keeps from the land.

The ship bears a good sail; that is, having all her sails abroad in a gale of wind, sails upright in the water.

To bring the guns to bear; that is, to lie right with the mark.

BEARING; the point of the compass that one place bears from another.

To BELAY, is to make fast a rope in its proper place.

BIRTH, is a convenient place to moor a ship in; as also a due distance observed between ships lying at anchor, or under sail.

BITTS, are two main pieces of timber standing pillar-wise abaft the manger, in the loof of the ship, with a cross-piece for belaying the cable when the ship rides at anchor. In great storms to strengthen the *bitts*, and secure the bows, the cable is fastned to the main-mast.

BOARD, is a word variously used at sea;
as,

To

To go aboard ; signifies to go into the ship.

To heave over board ; is to throw a thing out of the ship into the sea.

To slip by the board ; is to slip down by the ship's side.

Board and board ; is when two ships come so near as to touch one another ; or when they lie side by side.

To make a board ; is to turn to windward ; and the longer your *boards* are, the more you work into the wind.

To board it up, is to beat it up sometimes upon one tack, and sometimes upon another.

She makes a good board ; that is, the ship advances much at one tack.

The weather board, is that side of the ship which is to windward.

To board a ship, is to enter an enemy's ship in a fight.

BOOM, is a long piece of timber with which the clew of the studding sail is spread out ; and sometimes the clew of the main-sail and fore-sail is *boom'd* out, that by spreading them the broader they may receive the more wind.

Booming ; we say a ship comes *booming* towards us, when she comes with all the sail she can make.

BOW of a ship, is that part of her, which begins at the loof and compassing ends of the stem, and ends at the stern-most part of the fore-castle.

Bow-line, is a rope made fast to the leech or middle part of the out-side of the sail ; it is fastned by two, three or four ropes like a crow's

foot, to as many parts of the sail; only the mizen bow-line is fastned to the lower end of the yard; this rope belongs to all sails except the sprit-sail, and sprit top-sail; therefore those sails cannot be used close by a wind, for want of room to hale the bow-line forward by, since the use of the bow-line is to make the sails stand sharp, or close by a wind.

BRACES, are ropes belonging to all the yards of a ship, except the mizen, two to each yard, reev'd through blocks that are fastned to pennants seiz'd to the yard arms: Their use is either to square, or to traverse the yards. All these braces come aftward on, as the main-braces come to the poop; the main top-sail braces to the mizen-top, and thence to the main shrouds; the fore and fore-top-sail *braces* come down by the main and main-top-sail stays; and so of the rest. But the mizen bow-line serves to *brace* to that yard; and the cross-jack *braces* are brought forwards to the main shrouds, when a ship sails close by a wind.

BUOY, is a short piece of wood, or close-hoop'd barrel, fastned so as to float directly over the anchor; and by that means it is alway known whereabouts it lies.

Stream the buoy; that is, let the anchor fall while the ship has way.

To buoy up a cable, is to fasten some pieces of wood, barrels, &c. to the cable near the anchor, that the cable may not touch the ground, in case it be foul or rocky, lest it should be fretted, and cut off.

C

CABLE, is a great rope fastned to the anchor, and proportioned to it; serving to keep the ship fast whilst she rides at anchor.

Serve or plat the cable; that is, bind it about with ropes, clouts, &c. to keep it from gawling in the hawse.

To splice a cable, is to make two pieces fast together, by working the several strands of the rope one into another.

Pay more cable, that is, let it more out from the ship, that the boat which carries the anchor may row the easier, the *cable* lying slack in the water.

Pay cheap the cable, that is, put or hand it out apace.

Veer more cable, that is, let more of it run out.

A shot of cable; when the *cable* is double in length, to make the ship ride the easier.

To quoil a cable, is to roll it up in a ring.

To bend, or unbend a cable, is to fasten it to, or loose it from the ring of the anchor.

CAPSTAN. Ships have usually two (tho' both of the same form) distinguish'd by the names of the *main-capstan* and the *jeer capstan*; the *main-capstan* is a great piece of timber in the nature of a windlass, but standing perpendicularly just abast the main-mast, its foot standing in a step on the lower deck, and its head between the two upper decks, form'd into several squares with holes in them. Its use is to welgh the anchors; to hoist up, or strike down the top mast; to heave

any weighty thing; or to strain any rope that requireth a main force. The *jeer-capstan* is plac'd between the main-mast and the fore-mast, and serves to strain any rope, to heave upon the jeer-rope, or upon the viol, or hold off by, at the weighing of an anchor.

Capstan bars, are the bars or pieces of wood that are put into the *capstan* holes to work the machine in heaving up any thing of weight into the ship, by the help of as many men as can well stand at them.

Spindle of the capstan, is the main body thereof.

Whelps of the capstan, are short pieces of wood like brackets, made fast to it to keep the cable from coming too nigh in turning it about.

Pawl of the capstan, is a short piece of iron made fast to the deck, close to the body of the *capstan*; but yet so as that it hath liberty to turn every way, and against it the whelps of the *capstan* do so bear, that the *capstan* may be thereby stopt from turning or reversing, and this stoppage is term'd *pawling the capstan*.

Man the capstan; that is, have all the hands necessary to heave at the *capstan* bars.

Come up capstan; or *launch out the capstan*; that is, slack the cable which you heave by.

CHASE, signifies the ship chased or pursued.

CHASER, is the ship in pursuit of the chase.

Stern-chase, is when the chase is right a head of the chaser.

To lie with a ship's fore-foot in a chase, is to sail the

the nearest way to meet her, and so to cross her in her way, or *to come a cross her fore foot*.

CHESSE-TREES, are two small pieces of timber with a hole in them, on each side of the ship, a little before her loof; their use is for the main-tack to run through, and to hale it down to.

CLEATS; or, as some call them, *Chevils*, *Kevels*, or *Knevels*, are small pieces of wood nailed to the inside of the ship: Their use is to belay the sheets and tacks unto. *Cleats* are also pieces fastned on the yard arms, to keep the ropes from slipping off the yard.

CLOSE-HAWL'D; a ship is said to be *close-hawl'd*, when her sails are trim'd sharp, so as to sail as near the wind as possible.

CLEW of a sail, is the lower corner of it, to which are made fast the sheets and tacks.

COUNTER of a ship, is usually distinguished into upper and lower.

Upper-counter, is the hollow arching from the gallery to the lower part of the strait piece of the stem.

Lower-counter, is between the transom, and the lower part of the gallery.

COURSE of a ship, is that point of the compass on which she sails; and is indeed the angle, that the rumb-line steer'd upon makes with the meridian.

COURSES, are the lower sails, particularly the main-sail and fore-sail.

CUT-WATER, is that thin projecting knee under the beak-head, and is so call'd, because it cuts or divides the water before it comes to the bow.

D

DECK of a ship, is a plank'd floor from stem to stern, whereon is plac'd the ordnance, and on which the men walk. Great ships have three decks, first, second, and third, beginning to account from the lower-most.

Half-deck, reaches from the main-mast to the stem of the ship.

Quarter-deck, is that aloft the steerage, reaching to the round house.

F

FALL of a tackle, is that part of the rope which is haled upon.

Fall off; a ship is said to fall off, when in sailing she keeps not so near the wind as she should do

FATHOM; a measure of six foot.

FORE and aft, that is, from stem to stern.

FRESHENS; the wind *freshens*, that is, blows stronger.

FURLE

FURLE, (bind or make up) as to *furle* a sail, is to wrap up, and bind it close to the yard.

G

GAGE, a ship's *gage*, is so many feet as she sinks in the water, or so many feet of water as she draws; which seamen find thus: They drive a nail into a pike near the end, then putting it down by the rudder till the nail catch hold under it; for then as many feet as the pike is under water is the ship's *gage*.

Weather gage; when one ship has the wind, or is to windward of another, she is said to have the *weather gage* of her.

To **GRAPPLE**, is to hook fast an enemy's ship, in order for boarding.

GRAPLING. See **ANCHOR**.

GRIPE; the *gripe* of a ship, is the compass and sharpness of the stern under water, especially toward the lower part. The use thereof is to make a ship keep a good wind, and therefore sometimes when a ship will not keep a wind well, they put on another false stem to the true stem, to make her *gripe* more.

To gripe; we say a ship doth *gripe*, when she is apt (contrary to the direction of the helm) to run her head more in the wind than she should. There may be two causes of this, the one when a ship is too deep a-head, so that by reason of the weight which presses down her head, she is unapt to fall away from the wind; the other may be

the staying of the masts; for if she be a short ship, and draw much water, if her masts be stay'd too much aft, it will cause her head still to run into the wind.

H

H A L E, signifies pull; as to *hale up*, is to pull up; to *hale in* or *out*, is to pull in or out.

H A W S E S, are great holes in the ship's head through which the cables run, when she lies at anchor.

Bold hawse; that is, when the holes are high above the water.

Fresh the hawse, or *veer out more cable*; is when part of the cable that lies in the *hawse* is fretted or chafed, and it is requisite that more cable should be veered out, so that another part of it may rest in the *hawse*.

Fresh the hawse; that is, lay new pieces upon the cable in the *hawse*, to preserve it from fretting.

Burning in the hawse; that is, when the cable endures a violent stress.

Clearing the hawse; when two cables that come through several *hawses* are twisted and entangled one with the other; the untwisting of them is call'd *clearing the hawse*.

Thwart the hawse, or *rides upon the hawse*; that is, when a ship lies thwart, or cross, or with her stern just before another ship's *hawse*.

H A W S E R, is a great rope, or a sort of small cable, serving for various uses aboard a ship; particularly to warp a ship by as she lies at anchor, and
wind

wind her up to it by a capstan, &c. Note, *hawfers*, like cables, are in proportion to the ships for whose use they are design'd ; for a great ship's *hawfer* may serve for a cable to the sheet anchor of a small ship.

HEAD sails, are the sails belonging to the fore mast and bolt-sprit ; for they govern the head of the ship, and do make it fall off ; and these in quarter-winds are the chief drawing sails.

H E A V E ; that is, to throw away ; as *heave it over board* ; that is, fling it over board.

Heaving at the capstan ; that is, turning about the capstan.

Heave and set ; that is, when a ship being at anchor, rises and falls by the force of the waves, she is then said to *heave and set*.

HELM, or *Tiller*, is that piece of timber which is fastned into the rudder, and so comes forward into the steerage, or place where he at the helm steers the ship, by holding the whip-staff in his hand. Large ships have commonly a wheel like those in cranes, plac'd between the quarter-deck and coach, which has several advantages above the common method.

Bear up the helm ; that is, let the ship go more large before the wind.

Helm a mid ship, or *right the helm* ; that is, keep it even with the middle of the ship.

Bear up round ; that is, let the ship go directly before the wind, in the middle, between her two sheets.

Port the helm ; that is, put the helm over to the left side of the ship.

Star-

Starboard the helm ; that is, put it to the right side of the ship.

Ease the helm ; that is, let the ship go more large, or more before the wind.

Feel the helm ; a ship is said to feel her helm when she steers readily.

HOISE, is to hale up any thing into the ship ; or getting up a yard, &c. as *hoise* up the yard ; *hoise* the water in, &c.

HULL of a ship, is the full bulk, or main body of a ship, from stem to stern, without either masts, or rigging.

To strike a bull ; that is, in a storm, to lie close in the sea, or tarry for some consort, bearing no sail, with the helm lashed a-lee.

To hull, or lie a bull, or hulling ; is said of a ship when either in a dead calm (to prevent her beating the sails against the masts by rolling) or in a storm, when she cannot carry them, she takes all her sails in ; so that nothing but her masts, yards and rigging are abroad ; the helm is lash'd fast to the lee-side of the ship : In this condition, if she is a good sailer, she will lie easily under the sea, and make her way one point before the beam.

K

KEDGING, is when a ship is brought up or down in a narrow river, the wind being contrary to the tide, and yet she is to go with the tide : They set the fore-sail, fore-top-sail and mizen-sail, and let the ship drive with the tide, so that they may flat her about : And if she hap-

pen

pen
small
hawk
drop
wend
fully
This
and t

K
in a
one e
stem
and l
Fa
case
roll t

L
ship,
head

L
goes
but,
fre h

To
fair v

L
gener
as th
wind

pen to come too near the shoar, then having a small anchor in the head of the boat, with a small hawser fastned to it from the ship, they let it drop in the middle of the stream; and this will *wend*, or turn her head about; when she is come fully about, they heave up the anchor again. This sort of working is called to *kedg*, or *kedging*; and the anchor thus used is called a *kedger*.

K E E L, is the first or lowest piece of timber in a ship; it lies in the very bottom of her hull, one end whereof is at the stern, the other at the stem; and into this, are all the ground timbers and hooks fasten'd and bolted fore and aft.

False keel, is a keel put on under the first, in case the ship be shallow, and so over-floaty, and roll too much.

L

L A R B O A R D, is the left hand side of the ship, when you stand with your face towards the head.

L A R G E; *a ship goes large*, that is, she goes neither before the wind nor upon the wind; but, as it were, *quartering* between both, with a fresh gale, and all sails drawing.

To sail with a large wind, that is, with a fair wind.

L E E. This word is variously used; but generally signifies the part opposite to the wind; as the *lee shoar* is the shoar against which the wind blows; but to be under the *lee* of the shoar, is

is to be close under the weather shoar, that is, the shoar whence the wind doth come.

Lee-hatch : Have a care of the *lee-hatch* ; that is, take care the ship does not go to the leeward of her course.

A-lee the helm ; that is, put the helm to the leeward side of the ship.

To lie by the lee ; or *to come up by the lee* ; is to bring the ship so, that all her sails may lie flat against her masts and shrouds, and that the wind may come right upon her broad-side.

LOG, is a little piece of wood of a triangular form, with as much lead in one end thereof, as will serve to make it swim upright in the water, at the other end it is made fast to the *log-line*.

Log line, is a small line, having the *log* fastned to one end ; and is wound upon a reel. The *log-line* for about 10 fathom in small ships, or more in great ones from the *log*, has or ought to have no knots or divisions, because so much should be allowed, that the *log* may be out of the eddy of the ship's wake, before the glass be turned up : Then the knots begin and ought to be at least 50 feet asunder ; though the common practice at sea is to have them but 7 fathoms, or 42 feet distance. The use of the *log* and *log-line*, is to make an estimate of the ship's way, or distance run, by heaving it every hour, or every two hours.

To heave the log, is first to throw it into the water, and let it run away so far, as to be out of the eddy of the ship's wake ; then one having a half-minute glass ready in his hand, turns it up just when the first knot runs off the reel ; and so the line running easily off as the ship moves, when the glass is out, he cries *stop*, and the other
stops

stops the reel : Then counting the knots run out with the odd fathoms or feet (if any) they reckon, for as many knots as run out in half a minute of time, so many miles the ship sails in an hour ; and for every 5 odd feet, a tenth part of a mile more. Thus three knots in half a minute, is three miles an hour ; and four knots 25 feet in half a minute, is four miles and a half an hour.

The common division of the *log-line*, is grounded upon this supposition ; that a mile contains 5000 feet, and 60 of such miles a degree ; whence a degree would contain 300000 feet. Now half a minute being the 120th part of an hour, and the 120th part of 5000 feet, being 41,6, *&c.* or near 42 feet, therefore as many times 42 feet as the ship runs in half a minute, so many miles she goes in an hour. So that according to this supposition, 42 feet must be the distance between the knots upon the *log-line*. But this supposition, and consequently the practice from it, is certainly erroneous ; for a degree is now found to contain 360000 feet at least ; therefore a minute or a mile must contain 6000 feet (which is the true sea mile) and since half a minute is the 120th part of an hour, the 120th part of 6000 feet is 50 feet, consequently as many times 50 feet as the ship runs in half a minute, so many miles she makes in an hour (supposing her to hold her pace) therefore the distance between knot and knot should be 50 feet.

LOOF, or *Louf* of a ship, is that part of her aloft, which lies just before the cheffe-trees.

Loof or *Luff*, is also a word used in condng a ship : As,

Luff, keep your luff, that is, keep the ship near the wind. *Luff*

Luff up, that is, keep nearer the wind.

To luff into a harbour ; is to fail into it close by the wind.

To spring the luff, is when a ship that before was going large before the wind, is brought close by the wind.

Lexodromick-line, is the line of the ship's way, when she sails upon a rhumb oblique to the meridian.

LYE *under the sea* ; is said of a ship when her helm is lash'd fast a-lee, and she lies so a-hull, that the sea breaks upon her bow, or broad side.

M

MOOR ; to *moor* a ship, is to lay out her anchors so as is most convenient for her safe and secure riding. A ship is not said to be *moor'd*, unless she has at least two anchors out.

P

POINT *of the compass*, is the 32^d part of the circumference of the circle on the card, or 11 degrees 15 minutes ; therefore *half a point* is 5 degrees 37 minutes ; *quarter point* is 2 degrees 48 minutes.

POOP *of a ship*, is the highest, or uppermost part of her hull a stern.

PORT, or *port the helm*, is a word of command to him at the helm, to put it to larboard, which will make the ship go to starboard.

The ship heels a port, that is, leans to the left.

Ports, are those holes in a ship's side, through which the great guns are put out.

QUAR.

Q

QUARTER of a *ship*, is that part of the ship's hull which lies from the steerage-room to the transom.

QUARTERING ; *the ship goes quartering*, that is, she goes upon a quarter-wind ; or she goes neither by a wind, nor before the wind, but betwixt both.

Quarter-wind, is when the wind comes in abaft the main-mast shrouds, even with the quarter.

R

RAKE of a *ship*, is so much of her hull as hangs over both ends of her keel.

Fore-rake, or *rake-forward*, is that part of it which is before, and is usually more than a third, but less than half the length of the keel. A long *rake* forward gives the ship a good way ; but then if she has not a full bow, it will make her apt to pitch much a head into the sea ; besides, is a great charge and stress to a ship ; because she hangs over so a head. But when a ship has a small *rake* forward, she becomes so bluff-headed, that the sea beating continually upon her bow, she cannot cut the water so readily as she ought, and consequently will make but small way.

Rake aft, or *rake astward*, is that part which is at the setting on of the stern-post, and is generally about a fourth or a fifth part of her *fore-rake*.

Rake of the rudder, is the aft-most part of the rudder.

REEVE,

R E E V E ; is to draw a rope through a block to run up and down.

R I D E ; a ship is said to *ride*, when her anchors hold her fast, so that she drives not by the force of the wind or tide. And a ship is said to

Ride well, when she is built so, that she does not over-beat her-self into a head-sea, so that the waves do not over-rake her, that is, over-wash her from stem to stern.

Ride a-thwart, is to ride with her side to the tide ; and then she never strains her cable.

Ride betwixt wind and tide, is to ride so that the wind has equal force over her one way, and the tide the other ; which makes a ship roll and tumble very much, yet not strain her cables much.

Ride hawsful, or *to ride a stress* ; that is, when in a stress of weather, the ship falls deep into the sea with her head, so that the water runs in at her hawses.

R O A D, is any place near the land, where ships may ride at anchor.

R U D D E R of a ship, is a piece of timber which hangs at the stern-post, having four, five, or six irons, call'd *pintles*, according to the bigness of the ship, which pintles are fitted to the gudgeons at the stern-post : this *rudder* is, as it were, the bridle which governs the ship ; the narrower the *rudder* the better, if the ship do feel it, for a broad *rudder*, as it holds much water, too much stops a ship's way, when put over to either side ; but if the ship have a fat quarter, so that the water cannot come quick and strong

to t
rudd
the
next
the a
Th
in th
the f
Its u
it cha

R
angle
meric

Co
the li
equat

Ra
comp
that i

Ra
ship's
the c
merid
spiral
windi
infini
end.

In p
are re
shew
other
any p

R U
water,

to

to the rudder, then she will require a broad rudder. The putting to of the rudder, is term'd *the hanging of the rudder*. The part or edge next the stern-post, is call'd *the inside of the rudder*; the aftermost part, is call'd *the rake of the rudder*.

The rudder rope, is a rope reev'd thro' a hole in the rudder near the head, and likewise through the stern post, both ends being splic'd together. Its use is, to save the rudder, if by any accident it chance to be unhung.

R U M B, *Rhumb*, or course of a ship, is the angle which she makes in her sailing with the meridian of the place where she is. See **COURSE**.

Complement of the rumb, is the angle made by the line of the ship's way, with any parallel to the equator.

Rumb signifies also one point of the mariners compass, or the 32d part of the card, or horizon, that is, 11 degrees 15 minutes.

Rumb-line, is the line that is describ'd by the ship's motion, on the surface of the sea, steer'd by the compass, making equal angles with every meridian. These *rumb-lines* are helispherical, or spiral lines, proceeding from the point set out from, winding about the globe of the earth, and after infinite revolutions come the pole, where they end. See **LOXODROMICK-LINE**.

In plain and *Mercator's* sailing, these *rumb-lines* are represented by strait lines. Their use is, to shew the bearing of any two places one from another; that is, upon what point of the compass any place lies from another.

R U N of a ship, is that part of her hull under water, which comes narrower by degrees from the floor-

floor-timbers to the stern-post. This is also call'd *the ship's way aft-ward*; and according to the ship's *run*, she steers well or ill, by reason of the easiness or difficulty of the water's passage to the rudder. If too short, and too full below, the water comes but slowly to the rudder, because the force of it is broke by her breadth. This is sometimes remedied by putting on a false stern-post, tho' it is better to lengthen her.

Good-run; a ship is said to have a *good run*, when she comes off handsomely by degrees, and her tuck not lying too low.

Bad run, when the tuck of a ship lies too low, it hinders the passage of the water to the rudder, and therefore she cannot steer well, nor keep a good wind, nor make any good way thro' the sea; but will be still falling to leeward.

S.

SEEL signifies much the same as *heel*; for as it is called *heeling*, when a ship lies down constantly or steadily on one side; so it is called *seeling*, when she tumbles on one side violently and suddenly, by reason of the sea's forsaking her, that is, the waves leaving her for a time in a rolling sea.

Lee seel; that is, when the ship tumbles to *lee-ward*. In this, even in a storm, there is not much danger, for the sea will presently right her up again: But in case a ship *seels*, or rolls to *wind-ward*, then there is fear of her coming over too short or suddenly, and so in danger of being foundered, by the sea's breaking right into her; or at least having some of her upper-works carried away.

SET ; to observe on what point of the compass the sun, a ship, or any head-land bears, is call'd *setting the sun, land, &c.*

SHEER ; that is, to swing too and again.

The ship sheers ; that is, goes in and out, and not right forward, either by not steering steadily, or by means of the swift running of the tide, &c. In such case, they say, *she sheers, or goes sheering.*

SHEATS, are ropes bent to the clew of the sails ; serving in the lower sails, to hale aft, or round off the clew of the sails ; but in top-sails, their use is to hale home, that is, to bring the clew of the sail close to the yard arm.

Standing part of the sheat, is that part of it which is made fast to the ring of the ship's quarter.

Over hale the sheat ; that is, hale upon the standing part of the sheat.

To hale aft the main sheats, is in order to make the ship keep by a wind.

To hale aft the fore sheats, is that the ship may fall off from the wind.

Ease the sheat ; that is, veer it, or let it go out gently.

Let fly the sheat ; that is, let it go all at once, and run out as fast as it can ; then the sail will hang loose, and hold no wind.

Tally the sheats ; that is, hale aft the sheats of the main and fore sail.

Flown sheats. A ship is said to sail with *flown sheats*, when her sails are not haled home, or close to the blocks.

The

The sheats are flown ; that is, they are let loose, or to run as far as they will.

False sheat, is a rope bent to the clews of the main and fore-sail, above the sheat block, to succour and ease the sheat in a violent gust of wind.

To SHIVER or *Shake* a sail, is to bring the yard in a line with the wind.

SHOT of a cable, is the splicing of two cables together, that a ship may ride safe in deep waters and great roads : For a ship will ride easier by one shot of a cable, than by three short cables out a head.

To SOUND, or *sounding*, is to try the depth of water by a line and plummet, call'd a

Sounding-line ; that is, a line by which seamen find where the ship may fail by the depth of the water. It is generally about 20 fathom in length, and mark'd at two fathom next the lead, with a piece of black leather ; at three fathom the like, but slit ; at five fathom with a piece of white cloth ; at seven fathom with a piece of red, &c. with some such distinction all along. This line may be used when the ship is under sail ; which cannot be done so well with the *deep sea-line*, in using of which the ship is usually brought upon the back-stays.

SPOOMING, or *Spooning* ; when a ship being under sail in a storm at sea cannot bear it, but is forc'd to put right before the wind, without any sail ; then they say, the ship *spooms* : So that

if a
spoon
Sp
spoon
her m
under
set up
especi

ST
Ship,
left.
Star
condin
side of
to mak
always

ST
the stay
thus,
At th
fore-shea
weather
done to
their sh
e out,
ore-shea
But th
of the
not alter
And v
efore w
ack war
at the

if a ship will neither *try*, nor *bull*, then they *spoon*; that is, put her right before the wind.

Spooming with the fore-sail; that is, when in spooming there is danger that the ship may bring her masts by the board with her rolling, or feel under water, and so founder; then it is usual to set up the fore-sail, to make her go the steadier, especially if there be sea-room enough.

STARBOARD, is the right side of the ship, or the right hand; as larboard-side is the left.

Starboard the helm, or *helm a starboard*, in bringing a ship, is to put the helm to the right side of the ship, or to put the helm a-starboard, to make the ship go to the larboard; for the ship always sails contrary to the helm.

STAYING a ship, or to bring a ship upon the stays, is in order to her tacking; and is done thus,

At the same time, *bear up the helm*, *let fly the fore-sheat*, *let go the fore-bowline*, *brace the weather-brace of the fore-sail*. The same is also done to the *top-sail* and *top-gallant-sail*, only their sheats must be kept fast. If the sprit-sail be out, then *let go the sprit-sail sheat*, with the *fore-sheat*, and *brace the weather-brace*.

But the tacks, sheats, bracings, and bowlines of the main-sail, main-top-sail and mizen, are not altered.

And when the wind comes in at the bow, which before was the *lee-bow*, it drives all the sails backwards against the shrouds and masts; so that the ship makes no way forward, but drives
I with

with her broad side. Those are accounted the best ships, which will *stay* with the fewest sails.

STEER. *To steer a ship*, is to guide or direct her course by the helm. There are three kinds of direction to *steer* by, *viz.*

1. By any *mark* on the *land*, so as to keep the ship even by it.

2. By the *compass*; which is to keep the ship's head upon such a rumb, or point of the compass as best leads to the design'd port.

3. To *steer* as one is bidden, or conn'd; which is the duty (in great ships) of him that is taking his turn at the helm: And he is reckon'd the best *steers-man*, that uses the least motion in putting the helm over to and again, and that keeps the ship best from making *yaws*, that is from running in and out.

STEERAGE, is that part of the ship next below the quarter-deck, before the bulkhead of the great cabin: 'Tis here, in most ships of war, stands the *steers-man*, or he that guides the helm or rudder of the ship.

STEM of a *ship*, is that great timber, which comes compassing from the keel (wherein it is skarfed) up before the fore-castle. This *stem* guides the rake of the ship; and all the butt ends of the planks forwards are fixed into it.

False-stem, is fixed before the right one, where that is made too flat for the ship to keep the wind well; which defect is remedied by a *false stem*, that will make her rid more way, and be a better sail.

STE

tha
sta
S
par
it is
S
the
whi
post
geor

T
one
is re
brou
serve
make
ship
is a c
they
mizen
to sta
mizen
over-h
lines a
are ha
the sa
are br
belong
Ha
down

STEP of the *mast*, or *capstan*, in a ship, is that piece of timber whereon the mast or capstan stands at bottom.

STERN of a ship, is properly the outmost part of a ship abaft; though generally speaking, it is all the hindermost or aftmost part of a ship.

Stern-post, is a great timber let into the keel, at the stern of the ship, somewhat sloping, into which are fasten'd the after-planks; and on this post hangs the rudder, by its pintles and gudgeons.

T

TACK, is a great rope with a whale knot at one end, which seiz'd into the clew of the sail, is reev'd through the ches-trees, and then is brought through a hole in the ship's side. It serves to carry forward the clew of the sail, to make it stand close by a wind; the *racks* of a ship are usually belay'd to the birts, or else there is a chevil or cleat on purpose to fasten them; they belong only to the main-sail, fore-sail, and mizen. When the sails are to be trimed, so as to stand close to a wind, the main, fore, and mizen *tack* are brought close by the board, and over-haled as forward as they can be; the bow-lines are so also on the weather-side, the lee-sheats are haled close aft; as also the lee-braces of all the sails are likewise braced aft, and the top-sails are braced and govern'd as the sails to which they belong.

Hale aboard the racks; that is, bring the *tack* down close to the ches-trees.

Ease the tack ; that is, slacken it, or let it go, or run out.

Let rise the tack ; that is, let it go all out.

The ship sails, or stands close upon a tack ; that is, close by the wind.

To tack about, is to bring the ship's head about, so as to lie the contrary way ; which is perform'd thus : First make the ship stay ; and when she is stay'd, they say she is *pay'd* ; then *let rise and hale* ; that is, let the lee-tack rise, and hale aft the sheats ; and so trim all the sails by a wind as before ; for they cast off that which was before the weather-bowline, and set up the other taught. And thus they do also by all sheats, braces and tacks, which a ship that is trimm'd by a wind must have.

TACKLES, are ropes running in three Parts, having a pennant with a block at one end, and a block with a hook at the other end.

TAUGHT, or *Taut*, signifies stiff or fast ; as *hale taught a rope*, that is, set it stiff or strait.

TILLER, the same with the helm of a ship : It is most properly used in a boat, where that which would be the helm of a ship, is call'd the *Tiller*, and serves for the same use.

TRANSOM, is a piece of timber that lies a-thwart the ship's stern, between the two fashion pieces, directly under the gun-room port ; and it lays out the breadth of the ship at the buttocks : As when a ship is built broad or narrow at her *transom*, she is said to have a broad or narrow buttock.

TRIM

TRIM of a ship, is her best posture, proportion of ballast, and hanging of her masts, &c. for sailing.

To find the trim of a ship; that is, to find the best way of making any ship sail swiftly, or how she will sail best: This is done either by trying her sailing with another ship, so many glasses trimm'd a-head, so many a-stern, and so many upon an even keel; or else by easing of her masts and shrouds; some ships sailing much better when slack, than when they are taught. But this depends very much upon experience and judgment, and the several trials which the commander and other officers may make a board.

TRIP; as the ship goes with her top-sails a trip; that is, when she carries her top-sails hoisted up to the highest, when it blows not too hard, but a gentle or loom-gale, as it is called.

TRY; as the ship lies a-try under a main-sail, or main course; that is, when she has no other sails abroad; the tacks haled close a-board, the-bowlines set up, the sheats haled close aft, and the helm tied down close by the board, and so she is let lie in the sea. But at this time if she be upon a wind, she usually makes her way good, near three points before the beam.

To try under a mizen; this is done when it blows so hard, that they cannot maintain the main-sail; that is, cannot bear the main-sail out; and then if she lie close by the wind, she will make her way about two points before the beam.

But if she *try* under a main-sail and mizen, she will make her way good about four points before the beam.

If a ship will neither *try* nor *hull*, then *spoom*; that is, put her right before the wind.

V

VEER; as, *veer out a rope*, that is, let it go by hand, or let it run out of itself.

Veer, is also used in reference to the wind; as *the wind veers*; that is, when it changes often, and suddenly, or shifts from point to point.

VEERING, as *the ship goes veering*; that is, she goes at large, neither by a wind, nor directly before it; but between both; which is also call'd *quartering*.

VIOL, a kind of hawser, made use of to purchase in the cable, when the main capstan cannot do it; because the ground in which the anchor is fix'd, is too stiff; or else the sea runs too high, so that they cannot weigh it. In which cases they take a hawser, and opening one end of it, they put therein nippers, of about eight fathoms from each other, wherewith they bind this hawser fast to the cable, and then bring it to the jear capstan, to heave upon it. And this will purchase far more than the main capstan can.

W

WAKE of a ship, is the smooth water a stern, when she is under sail. This shews the way she has

has gone in the sea, whereby the mariners judge what way she makes ; for if the *wake* be right a-stern, they conclude she makes her way right forwards ; but if the *wake* be to leeward a point or two, then they conclude she falls to leeward of her course.

The ship stays to the weather of her wake ; that is, when in her staying she is so quick, that she does not fall to leeward upon a tack ; but that when she is tacked, her *wake* is to the leeward ; ~~then it is a sign that she feels her helm very well,~~ and is quick of ~~steering.~~

WARPING, is to hale a ship up by a hawser, or any other rope, sufficient for that purpose, with an anchor bent to it. This is used when a wind is wanting to carry a ship into, or out of a harbour.

Warp, so is the hawser, or rope used to hale the ship up, called.

WAY of a ship ; as, *To keep an account of the ship's way :* is one of the most necessary things in the practice of navigation ; and the most approv'd method of doing this, is by the log and log-line. Which See.

Lee-way, or leeward way, is the angle made by the point steer'd upon, and the way of the ship ; and since most ships are apt to fall a little to leeward of their course, it is necessary at all times in casting up the log-board, to allow something for the lee-way ; as,

1. If the ship be upon a wind, allow one point for lee way.

2. If the wind blow hard, and cause one top-sail to be taken in, allow two points for lee-way.

3. If the wind blow so hard that both top-sails are taken in, and the sea run high, allow three points for lee-way.

4. If the fore-sail be furl'd, and she try under a main-sail and mizen, she will make her way four points before the beam.

5. If she try under a main-sail only, she will make her way near three points before the beam.

6. But if she try under a mizen only, she will make her way about two points before the beam.

7. If she lie a-hull, with all her sails furl'd, she will make her way one point before the beam.

Way astward on, or *forward on*; that is, the rake or run of a ship. Which see.

WEATHER; as, *To weather a point*; that is, to pass by it on the weather-side. *To weather a ship*; that is, to go to windward of her.

Weather-coyle; that is, when a ship has her head brought about, so as to lie that way which her stern did before, without loosing of any sail, but only by bearing up the helm.

Weather-gage. See **GAGE**.

WHIP, or *Whip-staff*, is a strong staff fasten'd into the helm of small ships, for him that steers to hold in his hand, thereby to move the helm. and steer the ship.

WIND, is defined to be the stream or current of the air, which blows from some one of the two and thirty points of the horizon, or compass.

Windward; that is, nearer the rise of the wind.

To have the wind of a ship; that is, to be to windward of her.

Towsh

2
the
T
wind

W
ships
mast
eight
length
wood
turne
holes
serves
weigh
much
any da
the we
happen
felt.

Y A
timber
end, an
with th
hoisted
quires.
the mas
Tard
side of t
Brace
arm, wh

Touch the wind; that is, keep as close upon the wind as possible.

The winds eye; that is, directly against the wind.

WINDLASS, is an instrument, in small ships, placed upon the deck, just abaft the fore-mast. 'Tis made of a piece of timber six or eight foot square, in form of an axel-tree, whose length is plac'd horizontally upon two pieces of wood at the ends thereof, and upon which it is turned about by the help of handspikes, put into holes made for that purpose. This instrument serves for weighing anchors, or hoisting of any weight in or out of the ship; and will purchase much more than any capstan, and that without any danger to those that heave: for if in heaving the *windlass* about, any of the handspikes should happen to break, the *windlass* would paul of its self.

Y

YARDS of a ship, are those long pieces of timber made somewhat tapering towards each end, and fitted each a-thwart its proper mast, with the sails made fast to them, so as to be hoisted up, or lower'd down, as occasion requires. They have their particular names from the masts they belong to.

Yard arm, is that half of the yard on either side of the mast.




Brace the yard; that is, traverse aft the yard-arm, whose brace is haled.

Square the yards; that is, see that they hang right a-cross the ship, and one yard-arm not traversed more than another.

Top the yards; that is, make the yards stand even for to top the main and fore-yards, the clew-lines are the most proper; but when the top-sails are stow'd, then the top-sail sheets will top them.

Y A W S; as *the ship makes yaws*; that is, does not steer steady, but goes in and out when there is a stiff gale. And he that keeps the ship most from yawing, does commonly use the least motion with the helm; and those steer best.





D

45	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
40	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
30	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
25	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
20	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
15	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
10	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
5	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100

These instruments are made by J. Jyson in the Strand, Mathematician Instrument Maker to His Royal Highness The Prince of Wales



A N
A P P E N D I X,

Containing the

DESCRIPTION and USE

Of a Compleat

SETT or CASE of POCKET-INSTRUMENTS.



Compleat set of pocket-instruments (though sometimes made according to particular direction) generally consists of the following particulars, *viz*, 1. A large pair of compasses with one point made to take out, in order to receive in its place, either a drawing pen, a port-crayon, or a dotting-wheel; according as you would describe your circles or arches, with ink, black lead, &c. or only with dots. 2. A smaller pair of compasses for the exact taking of distances, or striking obscure arches, &c. in working geometrical problems. 3. A longer drawing pen, whose handle contains

a protracting pin, and a socket to hold a pencil.
 4. A parallel ruler. 5. A protractor, either semicircular, or (as they are more commonly fitted up for cases) in form of a parallelogram or long square, for the conveniency of laying down on the back side thereof, several lines of equal parts, both diagonally and otherwise divided, with two or three lines of chords of different radius's; and sometimes all the several lines of the common plain scale are laid down thereon. 6. A sector. These cases of instruments are made of several sizes; but most commonly either of the length of four inches, four inches and a half, or six inches, which last size, though somewhat heavier for the pocket, are much more preferable in use, as the divisions upon the sector are more sensible, and consequently their application in practice more exact.

Of the Compasses.

A pair of compasses is a thing so well known, that it would be little less than ridiculous to waste words in its description; but a few hints of direction in judging of their goodness, may probably be of service. Observe therefore, 1. That the motion of the head be equal, that is, that in opening or shutting you find no sudden jerks, or leaping. 2. That the joints are well fitted, so that there be no shake in the application of any of the points. 3. That they be well filed and polished. And, lastly, That the steel points are close join'd, equal, and well tempered.

The use of a pair of compasses is as well known as their form; I have therefore little to say

say under this head, but that it is an instrument well adapted to the taking of distances, and describing circles, or arches from a given center; which, as before was intimated, may be done either obscurely, with the steel point; in ink, with the drawing pen point; in black-lead, &c. with the crayon point; or by dots only, with the dotting wheel point; as the occasion requires. Note, also, either of these points may be used to draw a strait line along the edge of a ruler.

*Of the longer drawing Pen, with the
protracting Pin.*

This instrument is composed of two steel blades fixed into a small pillar of brass, silver, &c. one of which by means of a joint, may be made to open for the conveniency of cleaning, and by help of a little screw, they are easily set to the proper thickness of the line you would draw; the ink being inserted into the cavity betwixt the blades, with a pen; so that if the blades are well fitted and polished, the line they draw will be exceeding smooth and even, which cannot be so certainly done with a common pen. The use therefore of this part of the instrument is only to draw strait lines, which generally should be drawn very fine. The other part, which is call'd a *protracting pin*, is only a short piece of fine steel wire, fix'd in one end of the other part of the handle: and its use is to set off angles from the protractor, as shall be hereafter shewn in describing that instrument.

of

Of the parallel Ruler.

This instrument consists only of two equal rulers, so connected to each other, by moveable cross-pieces, fix'd parallel to each other, and lying asslant when the two rulers are closed, or crossing each other with a joint in the middle, that to whatever degree the rulers are opened, they are still kept in a true parallel position to each other; by which means one part being set true upon any line, another line may be drawn by the other part of the ruler exactly parallel to that whereon the first is placed: Which expedient is of great use in delineating most sorts of draughts, particularly in plans of architecture, both military and civil; and in reducing a multangular figure to a triangle, for the more accurate and ready finding the content.

Of the Protractor.

The protractor is commonly a semi-circle, on whose chord or diameter is mark'd its center, and whose arch is divided into 180 equal parts, called degrees; being the half of 360, which every whole circle is supposed to be divided into (See fig. 1. at the end of the Appendix.) But for cases of instruments, it is frequently made in form of a parallelogram, upon three sides of which the same divisions are laid down from a center, mark'd on the fourth (as in the plate fronting the title, in the figure mark'd C.) Every 10 of these degrees are numbered, and every fifth distinguished with a longer mark than the others, for the greater ease in reckoning. They are usually number'd both

both
to rig
angle
to be
where
as to
exact
which
protra
manne

I. I
an ang
A of
of the
center
A, the
exactly
your in
the fai
60 deg

2. I
angle g
B A C.
the line
upon th
limb of
the con

On t
form o
in the
down
differen
25, and

both ways, viz. from right to left, and from left to right, for the more readily laying down an angle from either end of a given line. The side to be applied to the paper is made flat, and that whereon the degrees are mark'd is filed so sloping, as to render the edges thin for the greater exactness in setting off, or measuring an angle; which are all the uses of this instrument as a protractor, and perform'd in the following manner.

1. If it was required to lay down an angle of 60 degrees, from the point A of the line A B. Lay the diameter of the protractor on the line A B, so that the center of the instrument may fall upon the point A, then with your protracting pin make a mark exactly against the number 60 upon the limb of your instrument, so shall a line drawn through the said mark to the point A, form an angle of 60 degrees. Fig. 2.

2. If it be required to find the content of an angle given, as in the foregoing figure the angle B A C. Lay the diameter of the protractor on the line A B, so that the center may fall exactly upon the point A; then shall the degree on the limb of the instrument cut by the line A C, shew the content of the angle, as before 60 degrees.

On the reverse of a protractor, when made in form of a parallelogram (*Vide* figure mark'd D in the plate fronting the title) are usually laid down several scales, or lines of equal parts of different proportions, that is, of 45, 40, 35, 30, 25, and 20 parts to an inch, distinguish'd by the said

said numbers prefixed, those of 20 and 40 being commonly diagonally divided; likewise lines of chords of different radius's; and if the diagonal scales be laid down within the vacant space on the face of the protractor (as in fig. C.) there may be room on the reverse (as in fig. D) for all the lines usually placed on the instrument, called the *plain scale*, as well as the before-mentioned lines of equal parts, &c. In giving therefore the construction and use of the plain scale, I shall sufficiently describe all the lines ever laid down on the reverse of a protractor, and shew their several uses and application in practice. But first I shall shew the use of these several scales or lines of equal parts, both as they are simply, and diagonally divided.

Of the Use of Scales, or Lines of equal Parts.

1. *Simply divided* (*Vide* fig. D). A line of equal parts is no more than a scale of measure in miniature, for laying down by way of plan, lengths taken by any known measures, as chains, yards, feet, &c. each part on the scale answering accordingly to one chain, one yard, or one foot, &c. The plan therefore will be the greater or less, as the scale used contains more or less parts in the space of an inch. Note, the first division on every scale is subdivided into 10 equal parts, which smaller divisions are the parts to be understood, when we say it is a scale of 20 or 30, &c. If, therefore, these lesser divisions be taken as units, and each represent one league, one mile, one chain, one yard, or one foot, &c. the larger divisions will consequently be tens, tho' number'd with single figures; so that to set off 36 leagues,
miles,

miles, chains, yards or feet, &c. extend the compasses from 3 of the larger divisions, to 6 reckon'd backwards upon the smaller, and that extent laid down on your plan, shall accordingly represent 36 leagues, miles, chains, yards or feet, actually measured in the thing represented. To adapt these scales to foot measure, you will likewise find the first division of each duodecimally divided, above the decimal division, the halves and quarters of which are distinguished by longer marks than the rest; which are generally only dots; so that to lay down any number of feet and inches, as suppose 8 F. 9 I. extend the compasses from 8 of the larger divisions, to 9 of the upper smaller divisions; and the said extent laid down on your plan, shall represent by whatever scale it is taken, from 8 F. 9 I. in length actually measured. This may suffice for those scales which are only simply divided.

2. *Diagonally divided* (*Vide fig. C.*) For those which are more accurately divided by diagonal lines, as one of the larger divisions are thereby exactly divided into 100 equal parts, if the scale contains 10 of the larger divisions, any number under 1000, may thereby be accurately laid down.

The projection of these diagonal scales is in this manner. First draw eleven parallel lines at equal distances, (*vide fig. C.*) the whole length of which being divided into a certain number of equal parts, according to the length of the scale, by perpendicular parallels; let the first division be again subdivided into ten equal parts, both above and below; then drawing the several oblique lines from the first perpendicular below, to the first

first sub-division above, and from the first sub-division below to the second sub-division above, &c. the whole first space shall thereby be exactly divided into 100 equal parts; for as each of the sub-divisions is one tenth part of the whole first space or division, so each parallel above it is one tenth of such sub-division, and consequently one hundredth part of the whole first space, and if there be 10 of the larger divisions, one thousandth part of the whole scale. If therefore the larger divisions be accounted as units, the first sub-divisions will be tenth parts of an unite, and the second sub-divisions mark'd by the diagonals, upon the parallels, hundredth parts of an unit; if the larger divisions be reckoned tens, the first sub-divisions will be units, and the second tenth parts: And if the larger divisions be accounted as hundreds, the first sub-divisions will be tens, and the second units. The numbers therefore 576. 57,6 . 5,76 are all expressible by the same extent of the compasses, viz. setting one foot in number 5 of the larger divisions, extend the other along the sixth parallel, to the seventh diagonal: For if the 5 larger divisions are taken for 5 hundred, 7 of the first sub-divisions will be 70, which upon the sixth parallel, taking in 6 of the second sub-divisions, or 6 units, makes the whole number 576. Or, if the five larger divisions be taken for 5 tens or 50, seven of the first sub-divisions will be 7 units, and the 6 second sub-divisions included upon the sixth parallel, will be six tenths of an unit. Lastly, if the 5 larger divisions be only esteem'd as five units, then will the 7 first sub-divisions be seven tenths, and the 6 second sub-divisions six hundredth parts of an unit. And this I think may be sufficient to shew the

the un
equal

The

Have
vided
diame
other.

1. T
end C
dicular
nine e
the fev
they cu
by beco

2. Fo
the poin
arch C
of semi
arch, is
by the
that an
t the ci

3. For
rom the
ne qua
ecants o
ngths
ne EF

4. For
the ar

the use both of the simple and diagonal scales of equal parts : I now proceed to

The Construction and Use of the Plain Scale.

Having described the circle $A B C D$, and divided it into four quadrants, by the diameters $A B$ and $C D$, crossing each other at right angles. Fig. 3.

1. To project the line of *Tangents*. From the end C of the diameter $C D$, erect the perpendicular $C G$; then dividing the arch $C B$ into nine equal parts; from the center E , through the several divisions of the arch, draw lines till they cut the perpendicular $C G$, which will thereby become a line of tangents.

2. For the *Semi-tangents*. Lines drawn from the point D , through the same divisions upon the arch $C B$, will divide the radius $B E$, into a line of semi-tangents. For the semi-tangent of any arch, is but the tangent of half such arch; and by the 20th of the 3d of *Euclid*, it is prov'd, that an angle at the center, is the double of one at the circumference.

3. For the *Secants*. Since the lines drawn from the center through the several divisions of the quadrant $C B$, to form the tangents, are the secants of those respective arches, transfer those lengths to the line $E B$ continued to F , and the line $E F$ will be a line of secants.

4. For the *Sines*. From the several divisions of the arch $C B$, let fall perpendiculars upon the radius

radius C E ; so shall the radius C E be divided into a line of sines, which is to be numbered from E to C for the right sines, and from C to E for the versed sines. Note, the versed sines may be continued to 180 degrees, if the same divisions be transferr'd on the other side of the center E.

5. For the *Chords*. The arch C B being divided into 9 equal parts, in the points 10, 20, 30, &c. if therefore you imagine lines drawn from C, to the said several divisions, they will be the chords of their respective arches. Setting therefore one foot of your compasses in the point C, and transferring the several lengths C 10, C 20, C 30, &c. to the line C B, and the line C B shall thereby be made a line of chords.

Note, *These several lines (which in the figure are drawn but to every 10 degrees) might be constructed to every single degree, if the circle were made large enough to admit of 90 distinct divisions in the arch of its quadrant.*

6. A line of *Rhumbs* is thus constructed. Divide the arch D B into 8 equal parts, in the points 1, 2, 3, 4, &c. then setting one foot of the compasses in D, transfer the several distances D 1, D 2, D 3, &c. from the arch to the line D B, by which means you will form a line of rhumbs, each of which will answer to an angle of $11^{\circ} 15'$.

7. For the line of *Longitude*. Divide the radius E A into 60 equal parts (because 60 miles make a degree of longitude under the equator) marking

marking every ten with their proper number; from these divisions let fall perpendiculars upon the arch A D, then having drawn the line A D, with one foot of the compasses in A, transfer the several distances where the perpendiculars cut the arch, to the line A D; which shall thereby be made a line of longitude.

Now if the several lines with their respective divisions thus projected, in fig. 3. be transfer'd to the scale mark'd D, in the plate fronting the title, where they are distinguish'd by their proper names; and thereto be added lines of equal parts, as before describ'd, the instrument called the *Plain Scale*, will thereby be form'd.

But as upon the reverse of some protractors (particularly those made by Mr. *Sisson*) besides the several lines already explain'd, there are two other lines laid down, *viz.* the line of latitude, and the line of hours; I shall likewise shew the manner how they are projected.

Projection of the Lines of Latitude, and of Hours.

1. To project the line of *Latitude*. In the same diagram (*viz.* fig. 3.) the radius C E being already divided into a line of fines, laying a ruler from the point B, through every of the said divisions, mark the points cut on the opposite arch A C, with the numbers 10, 20, 30, &c. then having drawn the right line A C, with one foot of your compasses in A, transfer the several intersections of the arch, to the said right line, which will thereby become a line of latitude, and may accordingly be laid down on your scale.

2. To
†

2. To project the *Hour-Line*. Draw the tangent I K, equal and parallel to the diameter CD; and divide half the arch of each quadrant A C and A D, from the point A, into three equal parts, which will be 15 degrees each part, for the degrees of every hour from 12 to 6; each of which parts are to be again sub-divided into halves and quarters, &c. then drawing lines from the center of the circle, through each of these divisions and sub-divisions, till they cut the tangent line I K, the said tangent line will thereby be divided into a line of hours.

3. To these may be still added, another line, applicable to the same use, *viz.* the line of *Inclination of Meridians*, which is projected in the same manner as the hour-line; only divided into degrees, instead of time, every 15 degrees being equal to an hour.

The uses of the several lines thus laid down on the scale D, from the foregoing Projection, are as follow.

1. The *Tangents, Semi-tangents* and *Secants* serve to find the centers, and poles of projected circles, in the stereographical projection of the sphere, &c.

2. The *Sines* serve for the orthographical projection of the sphere, &c.

3. The line of *Chords*, serve either to set off an angle from a given point in any right line or to measure the quantity of an angle already

laid down. The first is done by opening your compasses to the extent of 60 degrees upon the line of chords (which is always equal to the radius of the circle of projection) and setting one foot in the angular point, with that extent describing an arch; then taking the quantity of the angle required, between the feet of your compasses from the same chord-line, set it off from the given line upon the arch described; so shall a right line drawn from the given point, through the point mark'd on the arch, form the angle required. Thus to lay down from the point A of the line A B, an angle of 40 degrees, taking the extent of 60 degrees between the feet of your compasses from the line of chords, strike the arch C D, then setting off upon the said arch from D to C, the extent of 40 degrees taken from the said line of chords, from the point A draw the line A C, to pass through the point C, so shall the lines A B and A C form an angle of 40 degrees. The latter is done by describing as before, an arch with the extent of 60 degrees, and then taking the extent betwixt the lines which form the angle upon the said arch; that extent measur'd upon the same line of chords, will shew the quantity of the angle. Fig. 4.

4. The line of *Rhumbs* serves with more readiness than the line of chords, to lay down or measure the angle of a ship's course in navigation. For example, suppose a ship's course being N.N.E. it is required to lay down the angle. Draw the line A B for the meridian, then with 60 degrees of the chords, describe from the point A, the arch B C; and as N.N.E. is the second rhumb from the north, Fig. 5.
open

open your compasses to the second rhumb, and lay off the extent upon the arch B C, so shall a right line from the point A through the point C, give the angle of the course B A C. Or if it were required to find the quantity of the angle of a ship's course B A C; having described the arch B C, with 60 degrees of the chords, take the distance of the lines upon the said arch between the feet of your compasses, which measur'd upon the line of rhumbs, will shew the quantity of the angle.

5. The line of *Longitude*, being laid down on the scale contiguous with a line of chords of the same radius, numbered the contrary way, shews by inspection, how many miles there are in a degree of longitude, in each parallel of latitude; accounting the latitude upon the line of chords, and the miles of longitude upon the line of longitude. Thus in the latitude of 30 degrees, it appears that 52 miles make a degree of longitude; in the latitude of 60 degrees, 30 miles make a degree; and in the latitude of 80 degrees, 10 miles make a degree, &c.

6. The two lines of *Latitudes* and *Hours*, are used conjointly, and serve very readily to mark the hour-lines in the construction of dials, on any kind of upright plains.

As an instance of which, I shall give one example of an horizontal dial for the latitude of *London*, viz. 51° 32'.

To

To construct an horizontal Dial, by the Lines of Latitude and Hours; for the Latitude of $51^{\circ} 32'$.

First, draw the line EW of a convenient length, for the six a clock line, and at right angles thereto, the line NS for the meridian, or 12 a clock line, of a breadth equal to the thickness of the stile; the intersection of which lines, viz. the point A will be the center of your Dial: Then taking $51^{\circ} 32'$ (the latitude of the place) from the line of latitude, with one foot of your compasses in A, set off that extent on both sides, from A to E, and from A to W; then with the whole length of the line of hours between your compasses, set one foot in E, and cross the meridian line with the other; do the same on the other side from W, and draw the lines NE and NW, then taking between your compasses from the line of Hours, the distance from the beginning thereof to I, lay down that distance both ways from N to I, and from N to II, likewise from E to 5, and from W to 7; set off also the distance from the beginning of the line to II on the line of hours, both from N to 2 and 10, and from E to 4, and W to 8; and lastly, lay down the distance from the beginning of the line of hours to III, from N to 9, and from N to 3, which said distance will likewise reach from E to 3, and from W to 9. Thus having divided your trigon into its proper distances, lines drawn from the center A of the dial, through these several divisions, will mark the respective hour points on the limb of the dial, whether its figure be square or round; and for the hours before 6

K

in

in the morning, and after 6 at night, they are easily found by continuing the lines of the opposite hours through the center.

Note, The stile, which is general by a thin plate of brass, must make an angle with the plain, equal to the latitude of the place; the angular point being fix'd just at the center A, and the stile standing upon the meridian line, at right angles with the plain of the dial.

Of the Sector.

The *Sector* is a mathematical instrument, taking its name from a geometrical figure, which *Euclid* thus defines; a sector is a part of a circle, bounded by two radii, or semi-diameters, and part of the circumference, *viz.* the included arch. As an instrument, it consists of two equal legs, moveable about a joint like the common carpenter's rule; which being each of the length of 6 inches (tho' they may be made of any other determinate length, as in the figures mark'd A and B in the plate fronting the title, they are of 4 inches and a half) when quite open, they form an exact foot rule; and may be used as such in taking dimensions, being like other common rules, divided into inches and parts.

The lines commonly laid down on the faces of this instrument to be used sector-wise, are as follow, *viz.* upon one face (that mark'd A in the print.) 1. The lines of *Lines*, or of equal parts. 2. The lines of *Chords*. 3. The lines of *Secants*. 4. The lines of *Polygons*. On the other face (marked B in the print.) 1. The lines of *Sines*. 2. The

2.
line
de
75

line
the
mer
Mr.
ope
of l
give
the

T
the
dow
poly
certa
secto
betw
90 or
chord
The
parts,
halve
length
tange
radius
that is
of cho
to 45
10 de
where
their r

2. The lines of *Tangents* to 45 degrees. 3. Other lines of *Tangents* to a lesser radius, to supply the defect of the former, from 45 degrees to about 75 degrees.

Note, If the lines of lesser tangents, and the lines of secants, be projected from a radius $\frac{1}{2}$ of the larger lines, and laid down upon the instrument to the same angle (as is the practice of Mr. *Sisson*) then without any alteration in the opening of the legs, any extent taken on the lines of lesser tangents or secants, 4 times repeated, will give the proper tangent or secant, to the radius of the larger lines.

These several lines are projected and divided as the same lines upon the plain scale; but laid down upon the sector (all except the lines of polygons) so as that they may all make one certain angle, that is, to whatever degree the sector is opened, the distance will be the same betwixt 100 and 100 on the lines of lines, 90 and 90 on the lines of sines, 60 and 60 on the lines of chords, and 45 and 45 on the lines of tangents. The lines of lines are each divided into 100 equal parts, each of which are again sub-divided into halves and quarters, if the legs are of sufficient length; and with the lines of sines, chords and tangents, are each extended to the length of the radius of the circle from which they are projected; that is, the lines of sines to 90 degrees, the lines of chords to 60 degrees, and the lines of tangents to 45 degrees; each being numbered at every 10 degrees from the center to their several ends, where they are mark'd with the initial letters of their respective names.

Note, The correspondent parallels of the several lines are intended for the better distinguishing the several divisions upon each.

The lines of secants, and of lesser tangents, are each projected from a circle, whose radius is $\frac{1}{2}$ of that from which the other lines are projected; and beginning at the length of that radius from the center of the instrument, run to about 75 degrees. The tangents beginning at 45, where the larger lines of tangents end, have their degrees distinguished by the numbers 45, 50, 60, 70, 75, and the secants with the numbers 10, 20, 30, &c. to 75; and both are mark'd for distinction sake, with the small initial letters of their names.

The lines of polygons are laid down from the center of the joint, very near the inward edges of the instrument, and are numbred backwards from the ends towards the center, with the figures 4, 5, 6, &c. to 12, which comes within about three inches of the center.

These are all the lines which are usually laid down on this instrument to be used sectorwise.

The other lines which are placed upon, and parallel to the outward edges on both faces, and used as on common scales, the sector being quite opened, are, on the edge its self, a line of *Inches* with each inch sub-divided into 10 equal parts and on the faces, the line of *Numbers*, commonly called *Gunter's Line*, with the lines of *Artificial Sines* and *Tangents*; also sometimes a line of *Hours*, with a line of *Chords*, and a line of

La
eac
Of
dep
boo
hon
tria
Sup
to r
sect
angl
BC
line
or
lines
&c.
acco
&c.
be r
a b
lines
fines
A C
chor
of d
a b
fame
Ar
are
paral
found
A C

Lat

Latitudes, with a line of Inclination of Meridians, each being distinguished with its proper letter.

Of the Foundation and general Use of the Sector.

The foundation and general use of the sector depends upon the 4th proposition of the 6th book of *Euclid*, where it is prov'd, that the homologous sides of similar and equiangular triangles, are proportional to each other.

Suppose therefore the lines AB, AC , Fig. 7.
to represent any pair of lines upon the sector, particularly the lines of lines, making an angle BAC , with each other. If then, the line BC be drawn, and Aa, Ab taken equal, and the line ab also drawn; as Aa , or Ab is to AB , or AC , so will ab be to BC . Whence if the lines Aa, Ab , be the half, the third, the fourth, &c. of the lines AB, AC ; the line ab will accordingly be the half, the third, the fourth, &c. of the line BC . As suppose AB , or AC be 100, and Aa , or Ab 50; then if BC be 60, ab shall be 30. Hence it follows, that if the lines AB, AC , represent the lines of chords, sines or tangents, that is, if the line AB , or AC be the radius, and the line Aa or Ab the chord, sine or tangent, of some proposed number of degrees to the said radius AB ; then the line ab will be the chord, sine or tangent of the same number of degrees to the radius BC .

And here note, that lines taken upon the sector, are distinguished by the terms *lateral* and *parallel*; those being call'd lateral, which are found upon the sides of the instrument, as AB, AC ; and parallel, are such extents as are taken

from one leg to the other, at equal distances from the center of the joint, as B C, a b.

If therefore it be required to find the chord, sine or tangent of 20 degrees, to a radius of 5 inches; open the sector so that the distance from 60 to 60 on the lines of chords, may be equal to 5 inches; then will the parallel distance between 20 and 20 on the lines of chords, be the chord of 20 degrees, to a radius of 5 inches; so likewise the distance between 20 and 20 on the lines of sines, and between 20 and 20 on the lines of tangents, will be the respective sine or tangent of 20 degrees, to the said radius of 5 inches.

If a chord of more than 60 degrees be required to any assign'd radius; as suppose the chord of 80 degrees; open the sector as before directed to the radius given, and with the said radius, describe an arch sufficiently large, as
Fig. 8. AD; then taking the chord of half the number of degrees, *viz.* 40, lay it off twice upon the said arch, *viz.* from A to B, and from B to C, so shall a line drawn from A to C, be the required chord of 80 degrees.

If a tangent of more than 45 degrees be required, as suppose the tangent of 70 degrees, it must be taken from the lines of lesser tangents, which if not laid down to the same angle as the larger lines, as in most sectors they are not, then must the sector be so opened, that the distance between 45 and 45 on the said lesser tangents, may be equal to the given radius; so shall the distance between 70 and 70 upon the said lines of lesser tangents, be the tangent of 70 degrees, to the
the

the radius given. But if the lines of lesser tangents are made (as they should be) to $\frac{1}{4}$ of the radius of the larger, and laid down to the same angle, then the tangent of any required number of degrees, either more or less than 45, may be taken off without any alteration in the opening of the sector; for in the instance above of 70 degrees, the distance between 70 and 70 on the line of lesser tangents, 4 times repeated, will be the tangent of 70 degrees, to the radius so set off between 45 and 45 on the line of larger tangents.

To find the secant of any propos'd number of degrees to a given radius, as suppose the secant of 60 degrees, to a radius of two inches; open the sector to the distance of 2 inches between 0 and 0 on the lines of secants; so shall the distance between 60 and 60 upon the said lines, be the secant of 60 degrees, to the radius of 2 inches: Or, if according to the above remark on the lesser tangents, the lines of secants are projected to $\frac{1}{4}$ of the larger radius, and form the common angle; the distance between any proposed point, 4 times repeated, will give the proper secant to the radius the larger lines are open'd to.

If the contrary of any of these operations be required, that is, if a given right line be the chord, sine, tangent or secant, of any certain number of degrees, as suppose 20, and the radius be sought; open the sector to the length of the given line, in the points 20 and 20 of the lines of chords, sines, tangents or secants, according as the said line is either chord, sine, tangent or

secant ; and the distance between 60 and 60 on the chords, between 90 and 90 on the sines, between 45 and 45 on the tangents, and between 0 and 0 on the secants, shall be the radius to the given line, whether it be chord, sine, tangent or secant.

This may suffice to shew the nature, general use, and excellence of this instrument ; it evidently appearing from what has been said, that the *Sector* is, as it were, an universal *Plain Scale*, to any radius not greater than the extent of the instrument its self, when quite open, or less than the distance between the numbers at the ends of the respective lines, when quite shut.

And as the several lines make equal angles with each other respectively, they are thereby adapted to the working of proportions in equal parts and sines, equal parts and tangents, &c. so that among other things the several cases of Trigonometry may very readily be resolved by the sector. Some instances of which shall be hereafter given ; but first I shall shew some particular uses of the lines of lines, and of the lines of polygons.

Of the particular Use of the Lines of Lines.

As lines of equal parts, their use is the same with such lines on common scales, serving to lay down any given length ; but as they are laid down sectorwise, they have other various uses, some of the principal of which are shewn in the following problems.

P R O B L E M I.

To divide a given Line into any Number of equal Parts.

Take the extent of the given line between the feet of your compasses, and set off that extent as a parallel between the legs of your sector, in the points expressing the number of parts into which the line is to be divided; so shall the parallel distance between 1 and 1, divide the given line into the parts required. For example, suppose the line A B were given to be divided into 6 equal parts; set off the extent of the line A B, betwixt the legs of the sector in the points 6 and 6, and the parallel distance betwixt 1 and 1, viz. A C, shall be the $\frac{1}{6}$ part of the line A B. Fig. 9.

If the given line be of too great extent to be applied to the legs of the sector, take one half, or one fourth of it, which being divided as above directed, into the parts required, the double, or quadruple of one of those parts, will accordingly divide the whole line into the number of parts proposed.

P R O B L E M II.

To divide a Line in the same manner as another is divided.

Lay down the divided line laterally on both sides of the sector, from the center, and mark the point of its extension; then opening the sector

to the extent of the second line, in the terms of the first; apply likewise the several parts of the first line laterally on the legs of the sector, so shall the several parallels in the terms of those parts, be the correspondent parts in the line to be divided. Thus if the line CD were to be divided in the manner as the line AB ;

Fig. 10. placing AB on the lines of lines, in AB and AC , open the sector to the extent of CD , in the terms BC ; the sector remaining in this position, set off the parts AE and AF , of the line AB , on both legs of the sector, in AE and AF , so shall the parallel EE , give the division CG , and the parallel FF , the division GH , on the line CD to be divided.

P R O B L E M III.

To find the Proportion between two, or more given Lines.

The proportion between any given lines may be measured upon either of the lines of lines, as on other scales of equal parts, without opening the instrument. But to perform the operation sectorwise, open the sector so that the extent between 100 and 100, may be equal to the greater of the given lines; then taking the lesser lines severally between your compasses, carry them along the legs of the sector, till both points rest exactly on the same number upon the lines of lines; which numbers will accordingly give their proportion to 100. Thus if it were re-

Fig. 11. quired to find the proportion between the lines AB and CD ; having set off the extent of the longer line AB , betwixt the points

points of 100 and 100, apply the shorter line CD parallel to the former, and you will find it cut the lines of lines, in the points 80 and 80; the proportion therefore of CD to AB, is as 80 to 100; or in smaller numbers as 4 to 5.

If the greater line AB, be too long to be applied in the points 100 and 100, then supposing the lesser line CD 100, cut off AE upon the greater line, equal to CD, and the part AE being set off on the sector as before directed, in the points 100 and 100, the part EB will be found to cut the lines of lines in the numbers 24 and 24, so that the proportion of the part EB, to the part AE, will be found to be as 24 to 100; therefore the proportion of the line CD, to the line AB, will this way be found to be as 100 to 124.

P R O B L E M IV.

To increase or diminish a Line in any given Proportion.

Set the extent of the given line betwixt the legs of the sector, in the points of the number given, on each of the lines of lines; and the parallel distance betwixt the points of the number required, will give the line sought. Thus if the line A, is to be increased in the proportion of 3 to 7; set off the length *Fig. 12.* of the line A, betwixt 3 and 3, on the lines of lines; so shall the parallel distance betwixt 7 and 7, be the increased line B sought. On the contrary, if the line B was to be diminished in the proportion of 7 to 3, set off the

line B betwixt 7 and 7, and the parallel distance betwixt 3 and 3, shall be the diminished line A sought. Note, it may be sometimes more convenient to work with the equimultiples of the numbers given, which will produce the same effect; thus for the proportion of 3 to 7, you may take the numbers 6 to 14, 9 to 27, 12 to 28, or 30 to 70, &c.

P R O B L E M V.

To find a third Proportional to two given Lines.

Lay down both the given lines laterally on the legs of the sector, observing the points of their extension; then taking the second line between your compasses, open the sector to its extent in the terms of the first line, so shall the parallel distance between the terms of the second line, be the third proportional sought. For example,

let the two given lines be A and B, which being laid down on the sides of the sector from the center A, suppose the terms of the first line to be B B, and the terms of the second C C; then opening the sector in the terms B B, to the extent of the second line B, the parallel distance between C C shall be the third proportional sought. For as A is to B, so is B B, equal to the line B, to C C.

P R O B L E M VI.

To find a fourth Proportional to three Lines given.

Let the first and third lines, be both laid down laterally on the legs of the sector, from the center; then

then opening the sector in the terms of the first line, to the extent of the second line; the parallel distance between the terms of the third line, shall be the fourth proportional. For example, let A, B and C, be the three lines given; set off A and C on the sides of the sector, from the center A, marking the terms of their extension BB, and CC; then taking the second line B, open the sector to its extent, in the terms of the first line A, *viz.* BB; and the parallel distance betwixt CC, the terms of the third line C, shall be the fourth proportional sought. *Fig. 14.*

Note, In Geometry, as well as in Arithmetick, it is not necessary that all the proportionals be of one denomination; but only that the fourth found correspond with the second, as the third with the first; therefore the first and third proportionals may be measured by one scale, and the second and fourth by another: Or, their respective proportions to each other, may be found as directed in *Prob. 3.*

P R O B L E M VII.

To find a right Line nearly equal to the circumference of a given Circle.

Since the proportion of the diameter of a circle to its circumference, is nearly as 3.18 to 10; therefore opening the sector to the length of the diameter of the circle proposed, in the points on the lines of lines, answering to the number 3.18, the parallel distance between 10 and 10, will be the

the length of a line nearly equal to the circumference of the given circle.

P R O B L E M VIII.

To open the Sector so that the two Lines of Lines (and consequently the others respectively, if they are laid down as they ought, at equal angles) may stand at right angles with each other.

Since by the 47th proposition of the 1st book of *Euclid*, it is demonstrated, that in a right-angled triangle, the square of the hypotenuse is equal to the sum of the squares of both the legs; therefore, if the whole lateral length of one of the lines of lines, taken as 10 equal parts, be set over from 8 on one leg, to 6 on the other, the two lines of lines (and consequently the rest respectively) shall stand at right angles with each other. For 64 the square of 8, added to 36 the square of 6, makes 100, equal to the square of 10.

To these few problems peculiar to the lines of lines, I shall add one or two of a more general nature.

P R O B L E M IX.

To open the Lines upon the Sector or the edges of the Instrument itself to any proposed Angle.

Take the quantity of the angle proposed, laterally from the center on one of the lines of chords, and set it off as a parallel betwixt 60 and 60 on the said lines, so shall the two lines
of

of chords, and every other pair of lines stand respectively with each other at the determined angle. Thus to open the lines to an angle of 20 degrees, set off the lateral extent of 20 degrees taken from the center, upon either of the lines of chords, as a parallel betwixt 60 and 60 upon the said lines; and the two lines of chords, and consequently all the rest, each being laid down to the same angle, shall accordingly form an angle of 20 degrees, each with the other respectively. And if (as in the print prefix'd to this work) every pair of lines form with each other an angle of 6 degrees, when the sector is quite shut, it is but adding 6 degrees to the quantity of the angle proposed, in taking the lateral extent, and the parallel so set off, shall set the edges of the instrument its self to the angle required.

P R O B L E M X.

The Sector being opened, to find the quantity of the Angle, which either the several Lines, or the edges of the Instrument, make with each other.

This problem is but the reverse of the former: For if the parallel distance betwixt 60 and 60 on the line of chords, be applied laterally from the center on either of the said lines, the degrees of its extension is the measure of the angle the several lines respectively make with each other; deducting therefore 6 degrees from the quantity so found, for the angle the several lines make with each other when the instrument is quite shut, and the remainder will be the quantity of the angle formed by the edges of the instrument.

of

Of the Use of the Lines of Polygons.

The lines of polygons are chiefly contrived for the ready division of the circumference of a circle into any number of equal parts from 4 to 12, that is, as a ready means to inscribe regular polygons of any given number of sides, from 4 to 12, within a given circle: To do which, set off the radius of the given circle (which is always the side of the inscribed hexagon) as a parallel betwixt 6 and 6, upon the said lines, so shall the parallel distance betwixt 5 and 5, be the side of a pentagon; between 7 and 7, the side of a heptagon; between 8 and 8, the side of an octagon, &c. All which is too plain even to need an example.

N. B. All such regular polygons, whose number of sides will exactly divide 360 (the number of degrees into which all circles are supposed to be divided) without a remainder, may likewise be very readily set off upon the circumference of a circle, from the lines of chords; for laying down the radius of the circle, as a parallel betwixt 60 and 60, upon the lines of chords; the sector remaining so opened, having divided 360 by the number of sides, the parallel distance betwixt the numbers of the quotient, shall be the side of the polygon required; thus for an octagon, take the extent betwixt 45 and 45; and for a pentadecagon, the extent betwixt 24 and 24, &c.

If it be required to form a polygon upon a given right line; set off the extent of the given line,

line, as a parallel betwixt the points, upon the lines of polygons, answering to the number of sides, of which the polygon is to consist; as for a pentagon, betwixt 5 and 5; or for an octagon, betwixt 8 and 8; so shall the parallel distance betwixt 6 and 6, be the radius of a circle, whose circumference shall be divided by the given line, into the number of sides required.

The lines of polygons are likewise useful in describing upon any given line, an isosceles triangle, whose base angles shall each be double that at the vertex. For taking the given line betwixt your compasses, open the sector till that extent reaches from 10 on one leg, to 10 on the other; then shall the parallel distance betwixt 6 and 6, be the length of the two equal sides of the triangle sought.

Before we proceed to the manner of working proportions upon the sector, it will be necessary to consider the nature of the lines of artificial numbers, sines, and tangents; because as the same proportions may likewise be work'd upon these artificial lines, so one method of working, will serve as a proof of the other.

Of the Lines of Artificial Numbers, Sines and Tangents.

These several lines, which are usually laid down upon sectors parallel to the outward edges, in the same manner as upon other scales, are only the logarithms of the natural numbers, sines, and tangents, thus transferred to a scale.

1. The

1. The line of numbers, or *Gunter's line*, as it is commonly called, is a line of geometrical proportion, divided into 9 unequal parts, beginning at 1 towards the left hand, and numbered on with 2, 3, 4, 5, &c. to 10, about the middle of the line; where another radius begins, and the same divisions are repeated, numbered as before to 10, at the end of the line on the right hand. Each of these primes, or first grand divisions, are sub-divided according to the same ratio, into 10 other parts, and each of these sub-divisions (if the line be of sufficient length) should again be sub-divided into 10 other lesser parts. But upon pocket-lectors, which when opened are but 12 inches in length, only the part from 1 in the middle, to 2 towards the right hand, is a second time divided, and that but into 5 parts instead of 10, every one of which must therefore be accounted as 2 centesims. In numbering therefore upon the line (wherein consists the greatest difficulty) the figures 1, 2, 3, &c. which denote the primes, may be taken arbitrarily either as units, tens, hundreds or thousands; or they may represent tenths, hundredths, or thousandths parts of an unit.

If 1 at the beginning of the line, be taken for unity, then 1 in the middle will be 10, and 10 at the end 100; but if the first 1 be accounted 10, then 1 in the middle will stand for 100, and 10 at the end for 1000; again, if the first 1 be reckon'd 100, then 1 in the middle will be 1000, and 10 at the end 10000.

When

When therefore the first 1 or prime, represents 10 units, the figures 2, 3, 4, &c. to 1 in the middle, will stand for 20, 30, 40, &c. and each tenth, or sub-division in the first radius of the line, will signify 1 unit, and each centesim in those tenths (if there be any) will be $\frac{1}{10}$ part of an unit; 1 in the middle will be (as before observed) 100, and the figures 2, 3, 4, &c. following 200, 300, 400, &c.; each tenth, or sub-division in the second radius, will denote 10 units, and each centesim 1 unit. Again, let the first 1 represent 100, then the figures 2, 3, 4, &c. will signify 200, 300, 400, &c. 1 in the middle 1000, and 10 at the end 10000; according to this supposition, in the first radius, each tenth of a prime will be 10 units, and each centesim 1 unit; and in the second radius, each tenth of a prime 100, and each centesim 10.

In accounting decimal fractions upon the line; if 1 in the middle of the line be accounted as unity, then will each prime in the first radius denote, 1, each tenth of a prime, .01, and each centesim, .001. If 10 at the end of the line to the right hand, be accounted as unity, the whole first radius will represent 1, and the numbers 2, 3, 4, &c. in the second radius, 2, 3, 4, &c. every prime in the first radius, and every tenth of a prime in the second radius, will signify, .01, or one hundredth part of unity, and every tenth of a prime in the first radius, or centesim in the second, will denote, .001, or one thousandth part of unity.

The

The numeration of the line thus explain'd, let it now be propos'd to find the point thereon answering to the number 436. For the 4 hundred, take the 4 first primes next the left hand; for the second figure 3, take 3 tenths of the grand division betwixt 4 and 5, and for the 6 units, reckon 6 centesms, or 6 parts of the next tenth; so that the extent from 1 at the beginning of the line, to that point, will express the number 436. The same point will likewise represent the numbers 43,6, 4,36. or ,436; if the first 1 be accordingly accounted 10, 1, or $\frac{1}{10}$ of unity.

To multiply upon the line, extend your compasses from 1 at the beginning, to the point representing the number of your multiplier, the same extent will reach from the number of your multiplicand, to the product; thus, if 125 were given to be multiplied by 42; extend the compasses from 1 to 42, and the same extent will reach from 125 to 5250.

To divide upon the line; extend the compasses backwards from the number of the divisor, to unity; the same extent laid the same way, will reach from the number of the divided to the quotient: Thus if 5250 were given to be divided by 125; extend the compasses backwards from 125 to unity, the same extent will reach the same way, from 5250 to 42.

2. The line of artificial fines, consists only of the logarithms of the natural fines, transferr'd from a table of logarithms to the scale; they are number'd from the left to the right, with the figures

figures 1, 2, 3, &c. to 10, which stands about the middle of the line; and so forward with 20, 30, 40, &c. to 90, at the end on the right. In the first part of the line, the grand divisions each represent one degree, so that if each prime be sub-divided into 12 parts (as they commonly are upon sectors) each sub-division will signify 5 minutes. In the latter part of the line, the grand divisions which are each 10 degrees, being sub-divided into 10 parts, each sub-division will represent 1 degree, and according as they are again sub-divided into 4, 3 or 2 parts, such second sub-divisions contain 15, 20, or 30 minutes each.

3. What has been said of the line of sines, is likewise to be understood of the line of artificial tangents, whose divisions begin also at 1, and run on to 10 in the middle of the line, signifying single degrees; in the second part it runs on with 20, 30, &c. to 45, which stands at the end of the line, then returns back again to 90 where you began, as is evident from the inspection of the lines themselves.

The use of these lines is in working proportions, whether arithmetical or geometrical; particularly they are of very ready service in trigonometrical solutions.

The method of working with them is thus: In all proportions you have three terms given, to find a fourth. Seek out therefore the first term, whether number, sine, or tangent, on its proper line; and in that point set one foot of your compasses, extending the other to the second, or third term, which-ever of them is of the same name with

with the first; the same extent laid from the other term, the same way, will reach to the fourth term required.

Thus to work the following proportion; as the sine of $52^{\circ} 30'$ to the number 85, so is radius, or the sine of 90° , to the fourth number required. Set one foot of your compasses in the line of artificial sines on $52^{\circ} 30'$, and extend the other foot to 90° on that line, the same extent will reach from 85 on the line of numbers to 107, the fourth number required. And thus are all questions in proportion work'd by the artificial lines of numbers, sines and tangents; as will more fully be seen in the following section.

Of the manner of working Proportions on the Sector; both by the conjoint use of the Lines of Lines, with the Lines of natural Sines, Tangents, &c. as also by the artificial Lines of Numbers, Sines and Tangents.

Having already in treating of the reason, and general use of this instrument, shewn the particular use of the several lines of chords, sines, tangents, and secants laid down thereon, and how universal their application is thereby made, above what it is upon the plain scale: I now proceed to shew the conjoint use of the lines of lines, with the lines of natural sines, and tangents, as they are laid down sectorwise, and also the use of the artificial lines of numbers, sines, and tangents, in working proportions; which I shall exemplify in the resolution of the several cases of plain Trigonometry, both right angled, and oblique angled.

The

The Seven Cases of right-angled plain Triangles.

C A S E I.

The angles, and one of the legs being given, to find the other leg.

As suppose in the triangle ABC, the angle A is 36 degrees, and the base AB 75 feet, it were required to find the height of the perpendicular BC. Fig. 15.

The trigonometrical proportion for working this case; is as radius, to the tangent of the angle A; so is the leg AB, to the leg BC.

To work which upon the sectoral Lines.

Take with your compasses on either of the lines of tangents, the tangent of 36° degrees laterally from the center, and set off that extent parallel-wise from 45 to 45, on the lines of tangents; with this opening of the sector, take between the feet of your compasses the parallel extent betwixt 75 and 75, the length of the given leg, on the lines of lines, which extent applied laterally on either of the lines of lines, will reach to 54, for the length of the other leg; so that the perpendicular BC, is thereby found to be 54 feet.

Upon the artificial Lines.

Set one foot of your compasses in 45 (the radius) upon the line of tangents, and extend the other

other backwards to 36 ; the same extent will reach upon the line of numbers, from 75 the length of the given leg AB, to 54 the length of the required leg BC.

C A S E II.

The angles, and one of the legs being given, to find the Hypothenufe.

As suppose in the former triangle, the base AB as before 75 feet, the angle A 36 degrees, and consequently the angle C 54 degrees ; and it were required to find the length of the hypothenufe AC.

Proportion. As the sine of the angle C, to the radius ; so is the base, to the hypothenufe.

To work which upon the sectoral lines.

Take with your compasses on either of the lines of sines, the sine of 54 degrees (the quantity of the angle C) laterally from the center, and set off that extent as a parallel betwixt 90 and 90 on the lines of sines ; the sector remaining in that position, take between the feet of your compasses the parallel distance betwixt 75 and 75 (the length of the base) on the lines of lines, and that extent laterally applied on either of the said lines of lines, will measure 93, the length of the hypothenufe sought.

Upon the artificial Lines.

Set one foot of your compasses in 54 (the Sine of the angle C) upon the line of sines, and extend the

the other to 90, (the radius) the same extent will reach upon the line of numbers, from 75, the length of the base, to 93, the length of the hypotenuse required.

C A S E III.

The hypotenuse and angles being given, to find either of the Legs.

As suppose in the foregoing triangle, the hypotenuse A C 93, the angle A 36 degrees, and consequently the angle C 54 degrees ; and it were required to find the length of the Base AB.

Proportion. As radius to the sine of the angle C, so is the hypotenuse to the Base.

To work which upon the sectoral lines.

Setting one foot of your compasses on the center of one of the lines of sines, extend the other laterally to 54 degrees, and set off that extent a parallel betwixt 90 and 90 on the said lines of sines ; the sector continuing so opened, take the parallel distance between 93 and 93, the length of the hypotenuse, on the line of lines, and applying it laterally from the center, upon one of the said lines, the extent will be found 75 for the length of the base requir'd.

Upon the artificial lines.

Set one foot of your compasses in 90, on the line of sines, and extend the other backwards to 54, the sine of the angle C ; the same extent
L will

will reach upon the line of numbers, from 93 the length of the hypotenuse, backwards to 75 the length of the base required.

C A S E IV.

The legs being given, to find the angles.

As suppose in the foregoing triangle, the base A B, as before, 75 feet, and the perpendicular B C 54 feet, and it were required to find the quantities of the angles A and C.

Proportion. As the leg A B to the leg B C; so is radius, to the tangent of the angle at A: whose complement to a quadrant will be the angle at C.

To work which upon the sectoral lines.

Setting one foot of your compasses on the center, extend the other laterally on one of the lines of lines to 54, the length of the perpendicular B C, and set off that extent as a parallel between 75 and 75, the length of the base, upon the said lines of lines; the sector continuing thus opened, take the parallel radius, or extent between 45 and 45 on the lines of the tangents, between your compasses, which laid down laterally from the center, on either of the lines of tangents, will give 36° for the quantity of the angle A, and that subtracted from 90° , will leave 54° for the quantity of the angle C.

Upon the artificial lines.

Set one foot of your compasses upon the line of numbers, in 75, the length of the base, and extend the other backwards to 54, the length of the perpendicular; the same extent will reach from

from 45 (radius) on the tangents, to 36 the tangent of the angle A.

C A S E V.

The legs given, to find the hypotenuse.

As suppose in the foregoing triangle, the base A B is 75, and the perpendicular B C 54; it were required to find the length of the hypotenuse A C.

To work this Case upon the sectoral Lines.

Open the instrument to a right angle, (by Prob. the last of the uses of the lines of lines) then taking between your compasses, the slant extent from 75 on one of the said lines of lines, to 54 on the other, apply the said extent laterally from the center, on either of the said lines, and you will find 93 for the length of the hypotenuse required.

Upon the artificial lines.

First find the angles, by case the 4th, then the hypotenuse, by case the 2d.

C A S E VI.

The hypotenuse and one of the legs given, to find the angles.

As suppose in the foregoing triangle, the hypotenuse A C 93, and the base A B 75; and it were required to find the angles A and C.

L 2

Pro-

Proportion. As the hypotenuse to the base, so is radius to the sine of the angle at C.

To work which upon the sectoral lines.

Setting one foot of your compasses in the center, extend the other laterally on one of the lines of lines to 93, the length of the hypotenuse AC; this extent set off parallelwise, as a radius betwixt 10 and 10, on the said lines of lines; then from the center laterally on one of the lines of lines, taking the extent of the base AB 75 between your compasses, run that distance parallelwise along the lines of sines, till the feet rest in like numbers, which will in this example be at 54 degrees, the quantity of the angle C, opposite to the base, which being subtracted from 90, there will remain 36 degrees, the quantity of the angle A.

Upon the artificial lines.

Set one foot of your compasses upon the line of numbers, in 93, the length of the hypotenuse, and extend the other backwards to 75, the length of the base; the same extent will reach upon the line of sines, from 90 (radius) backwards to 54, the sine of the angle C, which, subtracted from 90, leaves 36 for the angle A.

C A S E

C A S E VII.

The hypotenuse, and one of the legs, being given, to find the other leg.

As suppose (as before) in the foregoing triangle, the hypotenuse A C 93, and the base A B 75. and it were required to find the perpendicular B C.

To work this case upon the sectoral lines.

Open the sector to a right angle (by *Prob.* the last of the uses of the lines of lines) then taking between your compasses the length of the hypotenuse A C 93, from the center upon either of the lines of lines, set one foot in 75, the length of the base A B upon one line, and the other foot being turned towards the center, will rest upon the other line in the point 54, the length of the perpendicular B C required.

Upon the artificial lines.

First find the angles, (by *Case* the VIth) then to find the length of the perpendicular, set one foot of your compasses on the line of sines in 90, (radius) and extend the other backwards to 36, the sine of the angle A ; the same extent will reach on the line of numbers from 93, the length of the hypotenuse, backwards to 54, the length of the perpendicular required.

L ;

The

The Six Cases of oblique-angled plain Triangles.

C A S E I.

Two sides, and an angle opposite to one of them, being given, to find the other opposite angle.

As suppose in the triangle ABC, Fig. 16. the side AC being 65 leagues, and the side BC 54 leagues, and the angle A opposite to the side BC $35^{\circ} 30'$, it were required to find the quantity of the angle B.

Proportion. As the side opposite to the given angle to the sine of the given angle, so is the side opposite to the angle sought to the sine of the angle required.

To work which upon the sectoral lines.

Setting one foot of your compasses on the center, extend the other laterally on the lines of lines to 54, the length of the side BC, which extent set off as a parallel betwixt $35^{\circ} 30'$, and $35^{\circ} 30'$ on the lines of sines, the quantity of the given angle A ; then from the center of the lines of lines, take the length of the side AC 65 between your compasses, and run that distance parallelwise along the lines of sines, till the feet rest in like numbers, which in this example will be at $44^{\circ} 15'$ nearly ; and that shall be the quantity of the angle B, opposite to the side AC.

If you would know the quantity of the remaining angle C, subtract the sum of the angles A

A and B from 180 degrees, (the sum of the three angles of every triangle) the remainder $100^{\circ} 15'$, shall be the quantity of the angle C.

Upon the artificial lines.

Set one foot of your compasses on the line of numbers in 54, the length of the side BC, opposite to the given angle A, and extend the other to 65, the length of the side AC; the same extent will reach upon the line of sines, from $35^{\circ} 30'$, the given angle A, to $44^{\circ} 15'$, the quantity of the required angle B.

C A S E II.

The angles, and one side being given, to find either of the other sides.

As suppose in the foregoing triangle, the side BC as before, being 54 leagues, the angle A $35^{\circ} 30'$, the angle B $44^{\circ} 15'$, and the angle C $100^{\circ} 15'$, the sides AB and AC were required.

Proportion. As the sine of the angle opposite to the given side, to the side given; so is the sine of the angle opposite to the required side, to the side required.

N. B. When an obtuse angle is given, you must work by its complement to 180 degrees.

To work this case upon the sectoral lines.

From the center of the lines of lines, take the length of the given side BC 54 laterally between
 L 4 your

your compasses, which extent set off as a parallel betwixt $35^{\circ} 30'$, and $35^{\circ} 30'$, the sine of its opposite angle A, upon the lines of fines; the sector thus opened, take between your compasses the parallel distance between $44^{\circ} 15'$, and $44^{\circ} 15'$, the quantity of the angle B, upon the lines of fines, and applying the said distance laterally upon either of the lines of lines, it will give 65 for the length of the opposite side AC. So likewise the parallel distance between $79^{\circ} 45'$, and $79^{\circ} 45'$, (the complement of $100^{\circ} 15'$, the quantity of the angle C) will, when applied laterally on either of the lines of lines, give 92 for the length of the side AB.

Upon the artificial lines.

Set one foot of your compasses on the lines of fines in $35^{\circ} 30'$, the quantity of the angle A, opposite to the given side BC, and extend the other to $44^{\circ} 15'$, the quantity of the angle B; the same extent will reach upon the line of numbers from 54, the length of the given side BC, to 65, the length of the required side AC. Or setting the first foot as before in $35^{\circ} 30'$ on the fines, extend the other to $79^{\circ} 45'$, (the complement of $100^{\circ} 15'$ to 180°) the same extent will reach on the line of numbers, from 54 to 92, the length of the opposite side AB.

CASE III.

C A S E III.

Two sides, and an angle opposite to one of them being given, to find the other side.

As suppose in the foregoing triangle, the side AC being 65 leagues, and the side BC 54 leagues, and the angle A opposite to the side BC $35^{\circ} 30'$, it were required to find the side AB.

To work this case either upon the sectoral or artificial lines.

1. Find the angles, by Case the first.
2. The side, by Case the second.

C A S E IV, and V.

Two sides, and the contained angle being given, to find the other two opposite angles, and the other side.

As suppose in the foregoing triangle, the side AC as before, 65 leagues, and the side AB 92 leagues, and the contained angle A $35^{\circ} 30'$, it were required to find the other opposite angles B and C, with the side BC.

The proportion for finding the angles in this case is as follows, viz. As the sum of the two sides AC and AB, to their difference, so is the tangent of half the sum of the angles B and C, viz. $72^{\circ} 15'$, to the tangent of half their difference; which added to their half sum, gives the greater

greater angle C, but subſtracted from the ſaid half ſum, leaves the leſſer angle B.

N. B. The ſum of the angles B and C, is found by ſubſtracting the given angle A, viz. $35^{\circ} 30'$ from 180° .

To work theſe caſes upon the ſectoral lines.

Theſe two caſes are taken together, becauſe upon the ſectoral lines it is neceſſary to find the length of the third ſide, before the angles can be diſcovered. To find therefore the length of the ſide BC, take the quantity of the given angle A $35^{\circ} 30'$, laterally upon one of the lines of ſines, and ſet it off as a parallel betwixt 90 and 90, on the ſaid lines : The ſector thus opened, ſet one foot of your compaſſes in 92, the extent of the ſide AB, upon one of the lines of lines, and extend the other to 65, the length of the other given ſide AC, upon the other line of lines ; this extent meaſured laterally from the center, upon either of the lines of lines, will give 54 for the length of the required ſide BC : Then may the quantity of either of the required angles be found by caſe the firſt, which added to the given angle, and the ſum ſubſtracted from 180, will give the quantity of the other angle.

Upon the artificial lines.

Fiſt to find the angles. Set one foot of your compaſſes upon the line of numbers in 157, (the ſum of the ſides AB and AC) and extend the other backwards to 27, (the difference of the ſides) the ſame extent will reach on the line of tangents

tangents from $72^{\circ} 15'$ (half the sum of the angles B and C) to 28° , which added to $72^{\circ} 15'$, gives $100^{\circ} 15'$ for the greater angle C ; or subtracted from $72^{\circ} 15'$, leaves $44^{\circ} 15'$, the lesser angle B. The angles thus found, the side BC may be obtained by case 2.

C A S E VI.

The three sides being given, to find the angles.

As suppose in the foregoing triangle the side AB 92 leagues, the side AC 65 leagues, and the side BC 54 leagues.

To work this case upon the sectoral lines.

First fixing upon any one angle, as suppose the angle A, note the extent of the two sides which include it, viz. AB 92, and AC 65 ; then taking the extent of the third side BC 54 between your compasses, set one foot in 92, upon one of the line of lines, and open the sector till the other foot falls upon 65, on the other line of lines : the sector thus opened, take betwixt your compasses either the parallel distance between 30 and 30 in the sines, which measured laterally from the center on either of the lines of sines, will give $17^{\circ} 45'$, half the quantity of the angle sought ; or take the parallel radius, viz. the extent betwixt 60 and 60 on the chords, which measured laterally on either of the lines of chords, will give you the whole quantity of the required angle A, viz. $35^{\circ} 30'$. The angle B may either be found by the same method, from the three given sides, or by the

the help of the discover'd angle A, according to the method laid down in case I.

The two angles A and B thus found, subtract their sum from 180° , the remainder will be the quantity of the third angle C.

Upon the artificial lines.

To work this case upon the artificial lines : First divide the base, or longest side AB, into two segments, by a perpendicular let fall from the opposite angle C ; the value of which segments are discoverable by the following proportion, *viz.* As the true base to the sum of the other two sides, so is the difference of the said two sides to the difference of the segments of the base : Which difference added to the true base, will give the double of the greater segment ; but subtracted, will leave the double of the lesser segment.

Set therefore one foot of your compasses on the line of numbers in 92, the length of the true base, and extend the other to 119, the sum of the two other sides ; the same extent will reach on the same line, from 11 the difference of the sides, to 14, 228 the difference of the segments of the base ; which difference 14, 228 added to the true base 92, gives 106, 228 the double of the greater segment ; but subtracted, leaves 77, 772 the double of the lesser segment.

The triangle therefore being divided into two rectangled triangles, by the perpendicular, and the segments of the base thus found, the angles may

may be obtained by case the 6th of rectangled plain triangles.

I have now, I presume, pretty well exemplified the uses of the several lines laid down upon the modern sectors, tho' besides what I have mentioned, they are capable of very various applications, in mensuration, architecture, dialling, astronomy, &c. But as formerly other lines used to be put upon them, and still the *French* sectors are furnished with lines of superficies and solids, &c. And my Author too having in his *Practical Geometry*, treated of these two lines, which I there omitted, with reference to this appendix, I shall here, from him, give the manner of their projection and application.

Projection of the lines of superficies.

Let the lines AE AE represent the lines of superficies, to divide which, having a scale of 1000 equal parts of the same length as the intended lines, take therefrom 125 parts *Fig. 17.* which set off from the center A, as the first division upon each; 250 parts will give you the fourth division; the mean proportion between 125 and 250, will be the number of parts marking the second division; 375 parts taken from the scale, and set off from the center A, will reach to the ninth division; the third division will be the mean proportion between 125 and 375: again 625 parts will give the 25th division; and the mean proportion between 125 and 625, will be the fifth division, &c. lastly, 1000 parts will be the 64th division: All which is plain from the consider-

consideration, that similar surfaces are in a duplicate ratio of their homologous sides.

Use of the line of superficies.








Taking between the points of your compasses the radius of a circle, or the side of any plain figure, and setting it as a parallel betwixt 1 and 1, the first division from the center ; so shall the parallel extent betwixt 2 and 2, give you the radius of a circle, or side of a figure of a double area ; and betwixt 3 and 3 triple, &c.















In the same manner may be found circles, and other plain figures subdouble, subtriple, &c.

Projection of the lines of solids.

Let the lines AF AF represent the lines of solids : From the said scale of 1000 equal parts, set off from the centre A 250, for the first division, and 500 for the 8th ; then finding two mean proportionals betwixt 250 and 500, the first will give you the second division ; and the second the fourth : To find this first mean proportional, subtract the logarithm of 250 from the logarithm of 500, and adding the $\frac{1}{3}$ of what remains to the logarithm of 250, you will get the logarithm of the first mean proportional, which will be nearly 315 ; and if you add again the same $\frac{1}{3}$ to the logarithm of 315, you will have the second mean proportional. For the third division, take the first of two mean proportionals between 250, and the triple thereof, 750 ; and for the 5th division, take the first of two mean proportionals between 250 and 1250, five times

250,





250, &c. Lastly, the whole line A.G, or A.H, being 1000 equal parts, will be the 64th division.

Use of the line of solids.

Set over the side of any body, as a parallel betwixt 1 and 1, the first division on the lines of solids; and the parallel extent betwixt 2 and 2, shall give the homologous side of a similar Body, whose solid content shall be double; and so the several other divisions will accordingly give sides of bodies triple, quadruple, &c. or sub-double, sub-triple, sub-quadruple, &c.

F I N I S.





Lately Publish'd,

Printed for A. BETTESWORTH in Pater-Noster-Row ; and C. KING in Westminster-Hall,

The THIRD EDITION, of

AN ESSAY on BOOK-KEEPING, according to the TRUE ITALIAN METHOD of Debtor and Creditor, by Double Entry : Wherein the *Theory* of that *Excellent Art* is clearly laid down in a few Plain Rules, and the *Practice* made evident and easy, by Variety of *Intelligible Examples*. The Whole in a Method New and Concise.

By WILLIAM WEBSTER,

WRITING-MASTER,

At the Corner of Orange-Court, in Castle-Street, near Leicester-Fields :

Where Young Gentlemen may be Well-boarded, and expeditiously qualified for Business.